My Inventions

By Nikola Tesla

1. MY EARLY LIFE

THE progressive development of man is vitally dependent on invention. It is the most important product of his creative brain. Its ultimate purpose is the complete mastery of mind over the material world, the harnessing of the forces of nature to human needs. This is the difficult task of the inventor who is often misunderstood and unrewarded. But he finds ample compensation in the pleasing exercises of his powers and in the knowledge of being one of that exceptionally privileged class without whom the race would have long ago perished in the bitter struggle against pitiless elements.

Speaking for myself, I have already had more than my full measure of this exquisite enjoyment, so much that for many years my life was little short of continuous rapture. I am credited with being one of the hardest workers and perhaps I am, if thought is the equivalent of labor, for I have devoted to it almost all of my waking hours. But if work is interpreted to be a definite performance in a specified time according to a rigid rule, then I may be the worst of idlers. Every effort under compulsion demands a sacrifice of life-energy. I never paid such a price. On the contrary, I have thrived on my thoughts.

In attempting to give a connected and faithful account of my activities in this series of articles which will be presented with the assistance of the Editors of the ELECTRICAL EXPERIMENTER and are chiefly addrest to our young men readers, I must dwell, however reluctantly, on the impressions of my youth and the circumstances and events which have been instrumental in determining my career.

Our first endeavors are purely instinctive, promptings of an imagination vivid and undisciplined. As we grow older reason asserts itself and we become more and more systematic and designing. But those early impulses, tho not immediately productive, are of the greatest moment and may shape our very destinies. Indeed, I feel now that had I understood and cultivated instead of suppressing them, I would have added substantial value to my bequest to the world. But not until I had attained manhood did I realize that I was an inventor.

This was due to a number of causes. In the first place I had a brother who was gifted to an extraordinary degree—one of those rare phenomena of mentality which biological investigation has failed to explain. His premature death left my parents disconsolate. We owned a horse which had been presented to us by a dear friend. It was a magnificent animal of Arabian breed, possest of almost human intelligence, and was cared for and petted by the whole family, having on one occasion saved my father's life under remarkable circumstances. My father had been called one winter night to perform an urgent duty and while crossing the mountains, infested by wolves, the horse became frightened and ran away, throwing him violently to the ground. It arrived home bleeding and



Nikola Tesla at the Age of 23.
From An Unpublished Photograph.



Mr. Tesla at the Age of 29.

HOW does the world's greatest inventor invent? How does he carry out an invention? What sort of mentality has Nikola Tesla? Was his early life as commonplace as most of ours? What was the early training of one of the World's Chosen? These, and many other very interesting questions are answered in an incomparable manner by Nikola Tesla himself in this, his first article.

In his autobiography, treating mainly on his early youth, we obtain a good insight into the wonderful life this man has led. It reads like a fairy tale, which has the advantage of being true. For Tesla is no common mortal. He has led a charmed life—struck down by the pest, the cholera and what not—given up by doctors at least three times as dead—we find him at sixty, younger than ever. But—read his own words. You have never read the like before.

—Editor.

Copyright, 1919, by E. P. Co. All rights reserved.



Mr. Tesla at the Age of 39.

exhausted, but after the alarm was sounded immediately dashed off again, returning to the spot, and before the searching party were far on the way they were met by my father, who had recovered consciousness and remounted, not realizing that he had been lying in the snow for several hours. This horse was responsible for my brother's injuries from which he died. I witnest the tragic scene and altho fifty-six years have elapsed since, my visual impression of it has lost none of its force. The recollection of his attainments made every effort of mine seem dull in comparison.

Anything I did that was creditable merely caused my parents to feel their loss more keenly. So I grew up with little confidence in myself. But I was far from being considered a stupid boy, if I am to judge from an incident of which I have still a strong remembrance. One day the Aldermen were passing thru a street where I was at play with other boys. The oldest of these venerable gentlemen—a wealthy citizen—paused to give a silver piece to each of us. Coming to me he suddenly stopt and commanded, "Look in my eyes." I met his gaze, my hand outstretched to receive the much valued coin, when, to my dismay, he said, "No, not much, you can get nothing from me, you are too smart." They used to tell a funny story about me. I had two old aunts with wrinkled faces, one of them having two teeth protruding like the tusks of an elephant which she buried in my cheek every time she kist me. Nothing would scare me more than the prospect of being hugged by these as affectionate as unattractive relatives. It happened that while being carried in my mother's arms they asked me who was the prettier of the two. After examining their faces intently, I answered thoughtfully, pointing to one of them, "This here is not as ugly as the other."

Then again, I was intended from my very birth for the clerical profession and this thought constantly opprest me. I longed to be an engineer but my father was inflexible. He was the son of an officer who served in the army of the Great Napoleon and, in common with his brother, professor of mathematics in a prominent institution, had received a military education but, singularly enough, later embraced the clergy in which vocation he achieved eminence. He was a very erudite man, a veritable natural philosopher, poet and writer and his sermons were said to be as eloquent as those of Abraham a Sancta-Clara. He had a prodigious memory and frequently recited at length from works in several languages. He often remarked playfully that if some of the classics were lost he could restore them. His style of writing was much admired. He penned sentences short and terse and was full of wit and satire. The humorous remarks he made were always peculiar and characteristic. Just to illustrate, I may mention one or two instances. Among the help there was a cross-eyed man called Mane, employed to do work around the farm. He was chopping wood one day. As he swung the axe my father, who stood nearby and felt very uncomfortable, cautioned him, "For God's sake, Mane, do not strike at what you are looking but at what you intend to hit." On another occasion he was taking out for a drive a friend who carelessly permitted his costly fur coat to rub on the carriage wheel. My father reminded him of it saying, "Pull in your coat, you are ruining my tire." He had the odd habit of talking to himself and would often carry on an animated conversation and indulge in heated argument, changing the tone of his voice. A casual listener might have sworn that several people were in the room.

Altho I must trace to my mother's influence whatever inventiveness I possess, the training he gave me must have been helpful. It comprised all sorts of exercises—as, guessing one another's thoughts, discovering the defects of some form or expression, repeating long sentences or performing mental calculations. These daily lessons were intended to strengthen memory and reason and especially to develop the critical sense, and were undoubtedly very beneficial.

My mother descended from one of the oldest families in the country and a line of inventors. Both her father and grandfather originated numerous implements for household, agricultural and other uses. She was a truly great woman, of rare skill, courage and fortitude, who had braved the storms of life and past thru many a trying experience. When she was sixteen a virulent pestilence swept the country. Her father was called away to administer the last sacraments to the dying and during his absence she went alone to the assistance of a neighboring family who were stricken by the dread disease. All of the members, five in number, succumbed in rapid succession. She bathed, clothed and laid out the bodies, decorating them with flowers according to the custom of the country and when her father returned he found everything ready for a Christian burial. My mother was an inventor of the first order and would, I believe, have achieved great things had she not been so remote from modern life and its multifold opportunities. She invented and constructed all kinds of tools and devices and wove the finest designs from thread which was spun by her. She even planted the seeds, raised the plants and separated the fibers herself. She worked indefatigably, from break of day till late at night, and most of the wearing apparel and furnishings of the home was the product of her hands. When she was past sixty, her fingers were still nimble enough *to tie three knots in an eyelash.*

There was another and still more important reason for my late awakening. In my boyhood I suffered from a peculiar affliction due to the appearance of images, often accompanied by strong flashes of light, which marred the sight of real objects and interfered with my thought and action. They were pictures of things and scenes which I had really seen, never of those I imagined. When a word was spoken to me the image of the object it designated would present itself vividly to my vision and sometimes I was quite unable to distinguish whether what I saw was tangible or not. This caused me great discomfort and anxiety. None of the students of psychology or physiology whom I have consulted could ever explain satisfactorily these phenomena. They seem to have been unique altho I was probably predisposed as I know that my brother experienced a similar trouble. The theory I have formulated is that the images were the result of a reflex action from the brain on the retina under great excitation. They certainly were not hallucinations such as are produced in diseased and anguished minds, for in other respects I was normal and composed. To give an idea of my distress, suppose that I had witnest a funeral or some such

(*Continued on page* 743)

NIKOLA TESLA
THE MAN
By H. Gernsback

THE door opens and out steps a tall figure—over six feet high—gaunt but erect. It approaches slowly, stately. You become conscious at once that you are face to face with a personality of a high order. Nikola Tesla advances and shakes your hand with a powerful grip, surprising for a man over sixty. A winning smile from piercing light blue-gray eyes, set in extraordinarily deep sockets, fascinates you and makes you feel at once at home.

You are guided into an office immaculate in its orderliness. Not a speck of dust is to be seen. No papers litter the desk, everything just so. It reflects the man himself, immaculate in attire, orderly and precise in his every movement. Drest in a dark frock coat, be is entirely devoid of all jewelry. No ring, stickpin, or even watch-chain can be seen.

Tesla speaks—a very bigh almost falsetto voice. He speaks quickly and very convincingly. It is the man's voice chiefly which fascinates you.

As he speaks you find it difficult to take your eyes off his own. Only when he speaks to others do you have a chance to study his head, predominant of which is a very high forehead with a bulge between the eyes—the neverfailing sign of an exceptional intelligence. Then the long, well-shaped nose, proclaiming the scientist.

How does this man, who has accomplished such a tremendous work, keep young and manage to surprise the world with more and more new inventions as he grows older? How does this youth of sixty, who is a professor of mathematics, a great mechanical and electrical engineer and the greatest inventor of all times, keep his physical as well as remarkable mental freshness?

To begin with, Tesla, who is by birth a Serbian, comes from a long-lived hardy race. His family tree abounds with centenarians. Accordingly, Tesla—barring accidents—fully expects to be still inventing in A. D. 1960.

But tbe chief reason for his perpetual youth is found in his gastronomical frugality. Tesla has learned the great fundamental truth that most people not only eat all of their bodily ills, but actually eat themselves to death by either eating too much or else by food that does not agree with them.

When Tesla found out that tobacco and black coffee interfered with his physical well-being, he quit both. This is the simple daily menu of the great inventor:

Breakfast: One to two pints of warm milk and a few eggs, prepared by himself—yes, he is a bachelor!

Lunch: None whatsoever, as a rule.

Dinner: Celery or the like, soup, a single piece of meat or fowl, potatoes and one other vegetable; a glass of light wine. For dessert, perbaps a slice of cheese, and invariably a big raw apple. And that's all.

Tesla is very fussy and particular about bis food: be eats very little, but what he does eat must be of tbe very best. And he knows, for outside of being a great inventor in science he is an accomplished cook who has invented all sorts of savory dishes.

His only vice is his generosity. The man who, by the ignorant onlooker bas often been called an idle dreamer, has made over a million dollars out of his inventions—and spent them as quickly on new ones. But Tesla is an idealist of the highest order and to such men money itself means but little.

PRESIDENT WILSON ALWAYS IN TOUCH WITH WASHINGTON—VIA RADIO.

(*Continued from page* 708)

Lyons Station, France, was established long before the *Pennsylvania* was beyond communication range of the United States.

The *Pennsylvania* has six receiving booths, which were able to receive on eight different tunes simultaneously as follows: One booth guarded Annapolis or New Brunswick tunes 16,900-13,000 meters; one booth guarded Lyons tunes 15,500 meters; one booth guarded Tuckerton's tune 9,200 meters; one booth guarded 4,000 meters (the Standard arc calling tune); one booth guarded 450 meters for the U. S. S. *George Washington* vacuum tube transmitter tune and one booth guarded 297 meters (the radio telephone tune). One additional operator guarded 600 and 952.

The radio stations at Otter Cliffs, Maine and Lyons, France, were used to receive messages from the President, transmitted by the U. S. S. *Pennsylvania's* arc.

The *George Washington's* radio equipment consisted of the following: One low power spark transmitting set, one 16,900 long wave receiving set, one short wave 600 meter spark receiving set, one short range radio telephone transmitting and receiving set, one vacuum tube 450 meter transmitting and receiving set. The U. S. S. *George Washington* was able to intercept messages transmitted by the Annapolis or New Brunswick stations and guard 600 meter (commercial calling, and emergency tune and the radio telephone and vacuum tunes) simultaneously. Messages for the President transmitted from the United States by the Annapolis, New Brunswick, Tuckerton and the Lyons station were received by the U. S. S. *Pennsylvania* and relayed to the *George Washington* by means of radio telephone and vacuum tube transmitting sets simultaneously.

The messages from the President destined to United States or France were sent from the *George Washington* to the *Pennsylvania* by the vacuum tube or radio telephone set and were relayed by the *Pennsylvania's* high power arc transmitter direct to the United States, Lyons or Brest, France.

The radio communication was directed by Commander H. W. McCormack, U.S.N., Fleet Radio Officer. Lieutenant S. V. Edwards is in charge of the radio of the *Pennsylvania*.

NIKOLA TESLA AND HIS INVENTIONS.

(*Continued from page* 697)

nerve-racking spectacle. Then, inevitably, in the stillness of night, a vivid picture of the scene would thrust itself *before* my eyes and persist despite all my efforts to banish it. Sometimes it would even remain fixt in space tho I pushed my hand thru it. If my explanation is correct, it should be possible to project on a screen the image of any object one conceives and make it visible. Such an advance would revolutionize all human relations. I am convinced that this wonder can and will be accomplished in time to come; I may add that I have devoted much thought to the solution of the problem.

To free myself of these tormenting appearances, I tried to concentrate my mind on something else I had seen, and in this way I would often obtain temporary relief; but in order to get it I had to conjure continuously new images. It was not long before I found that I had exhausted all of those at my command; my "reel" had run out, as it were, because I had seen little of the world—only objects in my home and the immediate surroundings. As I performed these mental operations for the second or third time, in order to chase the

Learn Public Speaking

10 LESSONS FREE

Write — quick — for particulars of this extraordinary offer; an opportunity you will never forget if you take advantage of it. Ten lessons in effective public speaking absolutely FREE to those who act promptly, to introduce our course in localities where it is not already known.

We teach you by mail to become a powerful and convincing speaker—to influence and dominate the decisions of one man or an audience of a thousand. We have trained hundreds and helped them to increase their earnings and their popularity. Learn, in your spare time at home, how to overcome "stage fright" and conquer fear of others; how to enlarge your vocabulary; how to develop self-confidence and the qualities of leadership; how to RULE others by the power of your speech alone; how to train your memory. Our

WHAT THE COURSE TEACHES YOU.

How to talk before your club or lodge;
How to address board meetings;
How to propose and respond to toasts;
How to make a political speech;
How to tell entertaining stories;
How to make after-dinner speeches;
How to converse interestingly;
How to write better letters;
How to sell more goods;
How to train your memory;
How to enlarge your vocabulary;
How to develop self-confidence;
How to acquire a winning personality;
How to strengthen your will power and ambition;
How to become a clear, accurate thinker;
How to develop your power of concentration;
How to be the master of any situation.

New Easy Method

perfected and taught only by Prof. R. E. Pattison Kline, former Dean of the Public Speaking Department of the Columbia College of Expression, can be learned in 15 minutes a day. Prof. Kline is one of the foremost authorities in the country on public speaking and mental development. Do not let this chance escape you.

Offer Limited

Send This Free Coupon Now

This Special Offer of TEN LESSONS FREE is made strictly for advertising purposes and will be withdrawn without notice. Write now, before it expires, and receive full particulars with enrollment blank by return mail. No obligations of any kind. Just tear off and mail this free coupon—or a postal will do.

FREE LESSONS COUPON

North American Institute,
7442 Manhattan Bldg., Chicago

I am interested in your course in Effective Public Speaking and your offer of ten lessons free. Please send full particulars. It is understood that this request places me under no obligation of any kind.

.....

.....

Learn Telegraphy-Wireless

Right In Your Own Home, in your spare time

Remarkable opportunities are offered experienced wireless operators and telegraphers. The demand is greater than the supply—steady positions at increased pay and rapid advancement are assured.

DEPENDABLE KNAPP ELECTRIC SPECIALTIES

Combination Wireless-Telegraphy Outfit



will soon make you an accomplished operator. Teaches Light and Sound Signals, both Radio and Morse. Outfit consists of exceptionally fine Telegraph Key, Buzzer, 3 Binding Posts, Lamp, Lamp Socket and Control Switch —all mounted on a highly finished base. Two outfits can be operated at considerable distance apart for sending and receiving practice.

$3.00

This Same Outfit Without Lamp **$2.50**

Order to-day. Or your dealer can secure it for you. Descriptive circular and catalog of celebrated Knapp Motors and Electrical Specialties from 10c up mailed free on request.

Knapp Electric & Novelty Co.
523 West 51st Street New York City



KNAPP LEADER
Radiates real power-plant efficiency. Will drive from either pulley.
Price, Complete, $3.50

The Breakers

Atlantic City's Newest Fire-Proof Hotel

Ocean Front. Unusually attractive during the Autumn and Winter seasons.

American and European Plans

Luxurious lobbies, spacious verandas and sun parlors overlooking the ocean. Charming afternoon musicales and evening concerts. A palatial residence for those seeking rest and recreation. Sea water baths. Fireproof garage. Illustrated booklet sent on request.

The House of Taylor

400 Baths
600 Rooms

HOTEL MARTINIQUE

BROADWAY, 33D STREET, NEW YORK
One Block from Pennsylvania Station.

Equally Convenient for Amusements, Shopping or Business

157 Pleasant Rooms, with Private Bath, $2.50 PER DAY.

257 Excellent Rooms, with Private Bath, facing street, southern exposure, $3.00 PER DAY.

Also Attractive Rooms from $1.50.
The Restaurant Prices Are Most Moderate.

What 15c will bring You from the Nation's Capital

Washington, the home of the Pathfinder, is the nerve center of civilization; history is being made at this world capital. The Pathfinder's illustrated weekly review gives you a clear, impartial and correct diagnosis of public affairs during these strenuous, epoch-making days.

The little matter of **15c** in stamps or coin will bring you the Pathfinder **13** weeks on trial. The Pathfinder is an illustrated weekly, published at the Nation's center, for the Nation; a paper that prints all the news of the world and tells the truth and only the truth; now in its **26th** year. This paper fills the bill without emptying the purse; it costs but $1 a year. If you want to keep posted on what is going on in the world, at the least expense of time or money, this is your means. If you want a paper in your home which is sincere, reliable, entertaining, wholesome, the Pathfinder is yours. If you would appreciate a paper which puts everything clearly, fairly, briefly—here it is. Send **15c** to show that you might like such a paper, and we will send the Pathfinder on probation **13** weeks. The 15c does not repay us, but we are glad to invest in new friends. **The Pathfinder, Box 76, Washington, D. C.**



Monuments—Mausoleums—Statuary

No matter what your needs, we can serve you most advantageously. Estimates and designs submitted. Mail orders as carefully executed as though you had called in person. Write for particulars.

J. L. Wegenaar Co., 299 A B'way, N.Y.
SPECIALISTS IN DESIGN AN DCONSTRUCTION

appearances from my vision, the remedy gradually lost all its force. Then I instinctively commenced to make excursions beyond the limits of the small world of which I had knowledge, and I saw new scenes. These were at first very blurred and indistinct, and would flit away when I tried to concentrate my attention upon them, but by and by I succeeded in fixing them; they gained in strength and distinctness and finally assumed the concreteness of real things. I soon discovered that my best comfort was attained if I simply went on in my vision farther and farther, getting new impressions all the time, and so I began to travel—of course, in my mind. Every night (and sometimes during the day), when alone, I would start on my journeys—see new places, cities and countries—live there, meet people and make friendships and acquaintances and, however unbelievable, it is a fact that they were just as dear to me as those in actual life and not a bit less intense in their manifestations.

This I did constantly until I was about seventeen when my thoughts turned seriously to invention. Then I observed to my delight that I could visualize with the greatest facility. I needed no models, drawings or experiments. I could picture them all as real in my mind. Thus I have been led unconsciously to evolve what I consider a new method of materializing inventive concepts and ideas, which is radically opposite to the purely experimental and is in my opinion ever so much more expeditious and efficient. The moment one constructs a device to carry into practise a crude idea he finds himself unavoidably engrost with the details and defects of the apparatus. As he goes on improving and reconstructing, his force of concentration diminishes and he loses sight of the great underlying principle. Results may be obtained but always at the sacrifice of quality.

My method is different. I do not rush into actual work. When I get an idea I start at once building it up in my imagination. I change the construction, make improvements and operate the device in my mind. It is absolutely immaterial to me whether I run my turbine in thought or test it in my shop. *I even note if it is out of balance.* There is no difference whatever, the results are the same. In this way I am able to rapidly develop and perfect a conception without touching anything. When I have gone so far as to embody in the invention every possible improvement I can think of and see no fault anywhere, I put into concrete form this final product of my brain. Invariably my device works as I conceived that it should, and the experiment comes out exactly as I planned it. In twenty years there has not been a single exception. Why should it be otherwise? Engineering, electrical and mechanical, is positive in results. There is scarcely a subject that cannot be mathematically treated and the effects calculated or the results determined beforehand from the available theoretical and practical data. The carrying out into practise of a crude idea as is being generally done is, I hold, nothing but a waste of energy, money and time.

My early affliction had, however, another compensation. The incessant mental exertion developed my powers of observation and enabled me to discover a truth of great importance. I had noted that the appearance of images was always preceded by actual vision of scenes under peculiar and generally very exceptional conditions and I was impelled on each occasion to locate the original impulse. After a while this effort grew to be almost automatic and I gained great facility in connecting cause and effect. Soon I became aware, to my surprise, that every thought I conceived was suggested by an external impression. Not only this but all my actions were prompted in a similar way. In the course of time it became perfectly evident to me that I

was merely an *automaton* endowed with power of movement, responding to the stimuli of the sense organs and thinking and acting accordingly. The practical result of this was the art of *telautomatics* which has been so far carried out only in an imperfect manner. Its latent possibilities will, however, be eventually shown. I have been since years planning self-controlled automata and believe that mechanisms can be produced which will act as if possest of reason, to a limited degree, and will create a revolution in many commercial and industrial departments.

I was about twelve years old when I first succeeded in banishing an image from my vision by wilful effort, but I never had any control over the flashes of light to which I have referred. They were, perhaps, my strangest experience and inexplicable. They usually occurred when I found myself in a dangerous or distressing situation or when I was greatly exhilarated. In some instances I have seen all the air around me filled with tongues of living flame. Their intensity, instead of diminishing, increased with time and seemingly attained a maximum when I was about twenty-five years old. While in Paris, in 1883, a prominent French manufacturer sent me an invitation to a shooting expedition which I accepted. I had been long confined to the factory and the fresh air had a wonderfully invigorating effect on me. On my return to the city that night I felt a positive sensation that my brain had caught fire. I saw a light as tho a small sun was located in it and I past the whole night applying cold compressions to my tortured head. Finally the flashes diminished in frequency and force but it took more than three weeks before they wholly subsided. When a second invitation was extended to me my answer was an emphatic NO!

These luminous phenomena still manifest themselves from time to time, as when a new idea opening up possibilities strikes me, but they are no longer exciting, being of relatively small intensity. When I close my eyes I invariably observe first, a background of very dark and uniform blue, not unlike the sky on a clear but starless night. In a few seconds this field becomes animated with innumerable scintillating flakes of green, arranged in several layers and advancing towards me. Then there appears, to the right, a beautiful pattern of two systems of parallel and closely spaced lines, at right angles to one another, in all sorts of colors with yellow-green and gold predominating. Immediately thereafter the lines grow brighter and the whole is thickly sprinkled with dots of twinkling light. This picture moves slowly across the field of vision and in about ten seconds vanishes to the left, leaving behind a ground of rather unpleasant and inert grey which quickly gives way to a billowy sea of clouds, seemingly trying to mould themselves in living shapes. It is curious that I cannot project a form into this grey until the second phase is reached. Every time, before falling asleep, images of persons or objects flit before my view. When I see them I know that I am about to lose consciousness. If they are absent and refuse to come it means a sleepless night.

To what an extent imagination played a part in my early life I may illustrate by another odd experience. Like most children I was fond of jumping and developed an intense desire to support myself in the air. Occasionally a strong wind richly charged with oxygen blew from the mountains rendering my body as light as cork and then I would leap and float in space for a long time. It was a delightful sensation and my disappointment was keen when later I undeceived myself.

During that period I contracted many strange likes, dislikes and habits, some of which I can trace to external impressions while others are unaccountable. I had a

The Man Who *Wouldn't* Stay Down



He was putting in long hours at monotonous unskilled work. His small pay scarcely lasted from one week to the next. Pleasures were few and far between and he couldn't save a cent.

He was down—but he *wouldn't stay there!* He saw other men promoted, and he made up his mind that what they could do *he* could do. Then he found the *reason* they were promoted was because they had special training—an expert knowledge of some one line. So he made up his mind that *he* would get that kind of training.

He marked and mailed to Scranton a coupon like the one below. That was his first step upward. It brought him just the information he was looking for. He found he could get the training he needed right at home in the hours after supper. From that time on he spent part of his spare time studying.

The first reward was not long in coming—an increase in salary. Then came another. Then he was made Foreman. Now he is Superintendent with an income that means independence and all the comforts and pleasures that make life worth living.

It just shows what a man with ambition can do. And this man is only one out of hundreds of thousands who have climbed the same steps to success with the help of the International Correspondence Schools.

What about *you?*

Are you satisfied merely to hang on where you are or would you, too, like to have a real job and real money? It's entirely up to you. You don't *have* to stay down. You *can* climb to the position you want in the work you like best. Yes, you can! The I. C. S. are ready and anxious to come to you, wherever you are, with the very help you need.

Surely when you have an opportunity that means so much, you can't afford to let another priceless hour pass without at least finding out about it. And the way to do that is easy—without cost, without obligating yourself in any way, mark and mail this coupon.

TEAR OUT HERE

INTERNATIONAL CORRESPONDENCE SCHOOLS
Box 6176, SCRANTON, PA.

Explain, without obligating me, how I can qualify for the position, or in the subject, before which I mark X.

☐ ELECTRICAL ENGINEER	☐ CHEMICAL ENGINEER
☐ Electrician	☐ SALESMANSHIP
☐ Electric Wiring	☐ ADVERTISING MAN
☐ Electric Lighting	☐ Show Card Writer
☐ Electric Car Running	☐ Outdoor Sign Painter
☐ Heavy Electric Traction	☐ RAILROADER
☐ Electrical Draftsman	☐ ILLUSTRATOR
☐ Electric Machine Designer	☐ DESIGNER
☐ Telegraph Expert	☐ BOOKKEEPER
☐ Practical Telephony	☐ Stenographer and Typist
☐ MECHANICAL ENGINEER	☐ Cert. Pub. Accountant
☐ Mechanical Draftsman	☐ Traffic Management
☐ Toolmaker	☐ Commercial Law
☐ Ship Draftsman	☐ GOOD ENGLISH
☐ Machine Shop Practice	☐ Common School Subjects
☐ Gas Engineer	☐ CIVIL SERVICE
☐ CIVIL ENGINEER	☐ Railway Mail Clerk
☐ Surveying and Mapping	☐ STATIONARY ENGINEER
☐ MINE FOREM'N OR ENG'R	☐ Textile Overseer or Supt.
☐ ARCHITECT	☐ AGRICULTURE
☐ Architectural Draftsman	☐ Navigator ☐ Spanish
☐ PLUMBING AND HEATING	☐ Poultry Raising ☐ French
☐ Sheet Metal Worker	☐ Automobiles ☐ Italian

Name_____

Present Occupation_____

Street and No._____

City_____ State_____

CORE WIRE

We have been fortunate in securing thru auction several tons of guaranteed pure, double annealed **Norway Iron Core Wire** and are selling this wire to "Experimenter" readers

AT PRE-WAR PRICES 20cts LB.

This wire is just the thing for spark coils, transformers, etc., and it is, of course, a very much more superior product than the usual iron wire. We absolutely guarantee the quality.

If you ever thought of building a spark coil, transformer, or similar apparatus, now is the chance to get the right material for it. As far as we know this is the only lot of iron Norway Core Wire in the hands of any dealer at the present time, and none can be gotten until after the war.

We have only two sizes left:

26 INCHES **36 INCHES**

Thickness about No. 21 B and S

If either of these sizes should be too long we advise cutting the wire down yourself by means of shears. It will pay you to do so as real Norway Iron Wire, sold by a few dealers last year, brought from 40c to 50c a pound. American core wire now sells for from 30c upwards per pound.

As long as the supply lasts we offer this wire as described above to our customers at the very low price of 20c a pound. Order at once.

ELECTRO IMPORTING CO., 231 Fulton St., N. Y. C.

$1.00 Down
Brings You A Suit
Tailor-Made-To-Order

Greatest suit offer ever made! Think of it—for only $1.00 down we make up a suit from the fabric you select **strictly according to your own individual measurements,** and send it to you for examination and try on. If you are perfectly satisfied, keep it and pay balance in easy monthly payments so small you scarcely miss the money. If not satisfied, return suit and we will immediately refund your dollar. Send for Style Book and see how you can



Save Half

Because of our early buying in vast quantities, our enormous volume and direct selling plan you actually get your suit at **about half** what it would ordinarily cost. Don't buy ready mades—don't pay double our price for a strictly made-to-order suit—a suit that is made to fit the lines of your figure perfectly, has snap and style, gives you long wear and holds its shape. That's the kind of suit you get from Stanley-Rogers and besides you have

5 Months To Pay

Absolutely wide open credit. You wear the suit while paying for it. We trust you absolutely. **Your word is all the security we ask.** No red tape, no delay.

$1000 Reward to anyone who proves that we do not make all our men's suits tailor-made-to-order according to each customer's individual measurements. Some firms try to fool you by telling you they make clothes "to measure", and then simply sell "hand-me-downs" altered here and there. There's a big difference between "made-to-order" and "made-to-measure". Stanley-Rogers suits SHOW the difference in style, fit and long wear.

FREE Style Book Write at once for your free copy of our wonderful 1918-19 Style Book, See the actual cloth samples of most beautiful weaves and patterns. Also illustrations of latest fashions. Send postal or letter—NOW! Get free style book. Don't delay! Write today.

STANLEY-ROGERS CO.
1015 Jackson Blvd. Dept. 805 Chicago

I Earned $2200 IN FOUR MONTHS

THIS is Richard A. Oldham. He earned $2200.00 in four months with a Haywood Tire Repairing outfit. For 20 years he was telegraph operator on the Illinois Central Railway. He is now 58 years old. He answered my advertisement—quit his job—bought a plant and opened a business. He just wrote me "I have made more in eight months than 2½ years as operator." There are now 500 stations where tire repairing is neglected.

I Must Have 500 Men
To Fill These Positions

I have a Big interesting Book to send you. It tells all about tires—gives inside figures and profit. Send for it! What Oldham and others are doing *You* can do. $2500.00 to $4,000.00 per year is conservative. Like Mr. Oldham—One machine will start you. Then open a shop. You can see business all around you. Put out a Haywood Sign and business will come to you. Now get started. Send for the Big Book and start making money.

M. HAYWOOD, Pres.
Haywood Tire & Equipment Co.
1209 Capitol Ave. Indianapolis, Ind.

STAMPS

50 diff. Belgium (large bi-color), China, Jamaica, Portugal, Venezuela, etc., 10c; 100 diff., nice packet, 20c; 1,000 well mixed, 40c; 100 var. U. S., 50c; 1,000 hinges, 10c; Agts. wanted, 50%. List free. I buy stamps. L. B. Dover, Overland, Mo.

YOU CAN'T AFFORD TO BE WITHOUT THESE BOOKS:
"How to Behave." "Art of Pleasing Men." "How to Become Beautiful," 25c each. "Hypnotism," 40c. "How Gamblers Win," 50c. Satisfaction guaranteed.
W. A. Engelke, 3257 Bishop St., Cincinnati, Ohio.

violent aversion against the earrings of women but other ornaments, as bracelets, pleased me more or less according to design. The sight of a pearl would almost give me a fit but I was fascinated with the glitter of crystals or objects with sharp edges and plane surfaces. I would not touch the hair of other people except, perhaps, at the point of a revolver. I would get a fever by looking at a peach and if a piece of camphor was anywhere in the house it caused me the keenest discomfort. Even now I am not insensible to some of these upsetting impulses. When I drop little squares of paper in a dish filled with liquid, I always sense a peculiar and awful taste in my mouth. I counted the steps in my walks and calculated the cubical contents of soup plates, coffee cups and pieces of food,—otherwise my meal was unenjoyable. All repeated acts or operations I performed had to be divisible by three and if I mist I felt impelled to do it all over again, even if it took hours.

Up to the age of eight years, my character was weak and vacillating. I had neither courage or strength to form a firm resolve. My feelings came in waves and surges and vibrated unceasingly between extremes. My wishes were of consuming force and like the heads of the hydra, they multiplied. I was opprest by thoughts of pain in life and death and religious fear. I was swayed by superstitious belief and lived in constant dread of the spirit of evil, of ghosts and ogres and other unholy monsters of the dark. Then, all at once, there came a tremendous change which altered the course of my whole existence.

Of all things I liked books the best. My father had a large library and whenever I could manage I tried to satisfy my passion for reading. He did not permit it and would fly into a rage when he caught me in the act. He hid the candles when he found that I was reading in secret. He did not want me to spoil my eyes. But I obtained tallow, made the wicking and cast the sticks into tin forms, and every night I would bush the keyhole and the cracks and read, often till dawn, when all others slept and my mother started on her arduous daily task. On one occasion I came across a novel entitled "Abafi" (the Son of Aba), a Serbian translation of a well known Hungarian writer, Josika. This work somehow awakened my dormant powers of will and I began to practise self-control. At first my resolutions faded like snow in April, but in a little while I conquered my weakness and left a pleasure I never knew before—that of doing as I willed. In the course of time this vigorous mental exercise became second nature. At the outset my wishes had to be subdued but gradually desire and will grew to be identical. After years of such discipline I gained so complete a mastery over myself that I toyed with passions which have meant destruction to some of the strongest men. At a certain age I contracted a mania for gambling which greatly worried my parents. To sit down to a game of cards was for me the quintessence of pleasure. My father led an exemplary life and could not excuse the senseless waste of time and money in which I indulged. I had a strong resolve but my philosophy was bad. I would say to him, "I can stop whenever I please but is it worth while to give up that which I would purchase with the joys of Paradise?" On frequent occasions he gave vent to his anger and contempt but my mother was different. She understood the character of men and knew that one's salvation could only be brought about thru his own efforts. One afternoon, I remember, when I had lost all my money and was craving for a game, she came to me with a roll of bills and said, "Go and enjoy yourself. The sooner you lose all we possess the better it will be. I know that you will get over it." She was right. I conquered my passion

Skinderviken Transmitter Button

See what the editor of Electrical Experimenter says about the button:

New York, Oct. 22, 1918.
J. SKINDERVIKEN, National Hotel, Washington, D. C.

In writer's opinion, obtained by actual elaborate tests, your Transmitter Button is probably most efficient device of its kind on market today, due to its simplicty and other outstanding features. Should have a great future.

H. GERNSBACK.

See what a couple of Electrical Experimenter readers say about the button:

New Brighton, Pa.
Dec. 16, 1918.

Dear Sirs:
I have been using one of your Transmitter Buttons for experimental work, and it certainly lives up to all you say for it and then some.

Yours truly,
HARRY H. BRUHN.

Wash, D. C.
Dec. 18, 1918.

DEAR SIRS:
I received the Transmitter Button and I am well pleased with it. It is everything you claim it to be and more too.

Yours truly,
G. A. WICK.

We have now thousands of buttons in stock and can ship same day as order is received. Send remittance with order as per our money back guarantee. See our ad page 734.

We have large stock of necessary supplementary equipment for experimenting. Send for a complete list. Receivers $1.00. Induction Coils from $0.35. Ringers from $0.35. Generators from $1.75.

SKINDERVIKEN TELEPHONE EQUIPMENT COMPANY
2134 North Clark Street
Chicago, Illinois

Abbreviated Address STECO

The ANDERSON Steam Vulcanizer



Anderson's Flexible Conformation Device, upon which an ordinary monkey wrench exerts tons of pressure, forces thousands of little rubber rivets into the tire's fabric, to be cooked in by our superheated dry steam system.

We guarantee to make practical vulcanizers out of men from 20 to 70 years old. $235 and 5 to 10 days in one of our many State Vulcanizing Schools will start you in this profitable business.

The Anderson Steam Vulcanizer Co.
No. 23 Williams Bldg., Indianapolis, Ind.

Mfrs. of the Famous Anderson Steam Vulcanizer. Owners of the Anderson method of vulcanizing

INSYDE TYRES Inner Armor for Auto Tires. Double mileage, prevent blowouts and punctures. Easily applied in any tire. Thousands sold. Details free. Agents wanted. Amer. Accessories Co., Dept. 55, Cincinnati

then and there and only regretted that it had not been a hundred times as strong. I not only vanquished but tore it from my heart so as not to leave even a trace of desire. Ever since that time I have been as indifferent to any form of gambling as to picking teeth.

During another period I smoked excessively, threatening to ruin my health. Then my will asserted itself and I not only stopt but destroyed all inclination. Long ago I suffered from heart trouble until I discovered that it was due to the innocent cup of coffee I consumed every morning. I discontinued at once, tho I confess it was not an easy task. In this way I checked and bridled other habits and passions and have not only preserved my life but derived an immense amount of satisfaction from what most men would consider privation and sacrifice.

After finishing the studies at the Polytechnic Institute and University I had a complete nervous breakdown and while the malady lasted I observed many phenomena strange and unbelievable.

(*To be continued in our March issue*)

TEN TELEPHONE OR FORTY TELEGRAPH CURRENTS OVER ONE CIRCUIT.

POSTMASTER GENERAL BURLESON on December 12th made public a letter from Theodore N. Vail announcing the invention and development by the technical staff of the Bell system of a practical method of multiplex telephony and telegraphy, which is expected to revolutionize long-distance wire communication.

Mr. Vail, who is President of the American Telephone and Telegraph Company, explained that there can be a combination of telegraphy and telephony under this invention by which a pair of wires, i.e., one full metallic circuit, will be available either for *five simultaneous telephone conversations* (*ten voices*) or for *forty simultaneous telegraph messages,* or partly for one and partly for the other.

With this new system four telephone conversations over one pair of wires are simultaneously carried on *in addition to* the telephone conversation provided by the ordinary methods. Thus, over a single pair of wires a total of five telephone conversations are simultaneously operated, each giving service as good as that provided by the circuit working in the ordinary way.

Heretofore the best telephone methods known to the art provided only one telephone conversation at a time over a single pair of wires. A number of years ago there was developed the *phantom circuit* arrangement, by which three telephone circuits were obtained from two pairs of wires, an important improvement, of which extensive use has been made commercially. Now, by the multiplex method we are enabled to obtain *five telephone circuits* over one pair of wires, that is, *ten simultaneous telephone conversations* from the two pairs of wires which formerly could be used for only three simultaneous telephone conversations. This represents an increase of more than threefold in the telephonic capacity of the wires, as compared with the best previous state of the art.

Some proposals made by the earlier workers in this particular field have naturally proved suggestive in the successful solution of the problem, particularly a suggestion made by Maj. Gen. George O. Squier, Chief Signal Officer of the United States Army, about ten years ago, and which at the time attracted very general attention.

Furthermore, while working in entirely different fields and with a different objective, Dr. Lee deForest a number of years ago invented a wireless device known as the Audion, which by improvements and adaptation has been made an important part of the Bell telephone system.

Become an Electrician In One Year Here
Or Learn An Electrical Trade In 6 Months

THIS school teaches electricity thoroughly, from the very fundamentals, including the laws and principles of electricity and the theory of direct current—together with practical lectures and problems, actual training in laboratory work and electrical machine departments of designing, building, repairing, installing, operating, etc. And the faculty here are practical electrical engineers who know how and what to teach because they know what knowledge and ability the great field of Electricity requires.

As one example of this school's thoroughness and practical training and development, witness the picture above, showing view of armature winding department, whore students actually wind armature—D.C. and A.C.—by a most successfully practical and unique method.

The thoroughness in essentials here, the practical tralning and able faculty, together with this school's broad facilities and intensive abilities, are the reasons why you can become an Electrician here in one year, or master one of the Electrical Trades in 6 months.

If you are determined to achieve success in the Electrical Field this is your school. You will acquire and accomplish more in a shorter time at a less cost and be a fully developed, practical electrical man when you finish. Mail the coupon at the right and get complete Illustrated and descriptive details of the advantages this school affords. If interested in Electrical Engineering with B.S. degree, check same on coupon. Mail the coupon now.

A STUDENTS' Cooperative Dormitory and Boarding Club is organized here with modern and completely equipped school quarters for housing and boarding students—conducted by student committees for the athletic, social and academic welfare of the students and establishing living economy and comfort. Fully explained on request.

You Can Earn While You Learn

WE will provide you with part time employment to help defray your expenses here and give you actual outside experience — without interfering with your class hours—which is fully explained in our catalog. Mail the coupon.

School of Engineering of Milwaukee
An Electrical Technicians' Institute
Department of Practical Electricity
76-373 Broadway, Milwaukee, Wis.

Mail This Coupon NOW

School of Engineering of Milwaukee
76-373 Broadway, Milwaukee, Wis.

Without obligating me, please furnish details of ....day or ....evening course (or courses) checked below.

..Electrician
..Electro-Technician
..Electrical Engineer

Special 6 Months' Courses.

..Draftsman
..Electrical Trouble & Lineman
..Electrical Wireman
..Electrical Motor Repairman
..Telephone Trouble & Repairman
..Electrical Meterman
..Dormitory

NAME .....
ADDRESS .....
AGE .....
EMPLOYED AT .....
EDUCATION .....

TYPEWRITER SENSATION
PROMPT SHIPMENT.

$4.00 per month buys a beautifully reconstructed, latest model visible typewriter, with back spacer, decimal tabulator, two-color ribbon, etc. Every late style feature and modern operating device. Sent on approval. Catalogue and special prices free.

Harry A. Smith, 738, 218 N. Wells St., Chicago, Ill.

Captain George Frederick Campbell, Formerly Third Ace of the Royal Flying Corps. Chief Instructor of National Aero Institute.

Let Me Train YOU In
AVIATION

I want you to take up Aviation. Positions at good pay are going begging, because there are not enough trained men to fill them. LET ME TRAIN YOU for some of these big positions that pay big wages. I know the game, for I have been flying for years. My advice to you is to decide right now to take a

Home Course in Aviation

in your spare time. Send today for our **FREE BOOK** and I will write you a personal letter along with it. I will tell you some INSIDE facts about this great industry. You'll want to get right in. Address as follows:

Capt. Geo. F. Campbell, Chief Instructor, NATIONAL AERO INSTITUTE, DEPT. 7442, Morton Building, Chicago, Illinois.

Two Airplane Concerns agree to take every one of our students who have mastered our course for the big paying positions of Mechanics, Inspectors, Assemblers, Engineers, etc.

Why don't YOU quality?

Fill Out This Coupon and Mail Today

Capt. George F. Campbell, Chief Instructor
National Aero Institute, Dept. 7442,
Morton Building, Chicago, Ill.

Dear Sir: Please send me without obligation, copy of "The Science of Aviation," also particulars of Mail Course in the Principles of Aviation.

Name.....
Address .....

My Inventions

By Nikola Tesla

2. MY FIRST EFFORTS IN INVENTION

I SHALL dwell briefly on these extraordinary experiences, on account of their possible interest to students of psychology and physiology and also because this period of agony was of the greatest consequence on my mental development and subsequent labors. But it is indispensable to first relate the circumstances and conditions which preceded them and in which might be found their partial explanation.

From childhood I was compelled to concentrate attention upon myself. This caused me much suffering but, to my present view, it was a blessing in disguise for it has taught me to appreciate the inestimable value of introspection in the preservation of life, as well as a means of achievement. The pressure of occupation and the incessant stream of impressions pouring into our consciousness thru all the gateways of knowledge make modern existence hazardous in many ways. Most persons are so absorbed in the contemplation of the outside world that they are wholly oblivious to what is passing on within themselves. The premature death of millions is primarily traceable to this cause. Even among those who exercise care it is a common mistake to avoid imaginary, and ignore the real dangers. And what is true of an individual also applies, more or less, to a people as a whole. Witness, in illustration, the prohibition movement. A drastic, if not unconstitutional, measure is now being put thru in this country to prevent the consumption of alcohol and yet it is a positive fact that coffee, tea, tobacco, chewing gum and other stimulants, which are freely indulged in even at the tender age, are vastly more injurious to the national body, judging from the number of those who succumb. So, for instance, during my student years I gathered from the published necrologues in Vienna, the home of coffee drinkers, that deaths from heart trouble sometimes reached *sixty-seven per cent* of the total. Similar observations might probably be made in cities where the consumption of tea is excessive. These delicious beverages superexcite and gradually exhaust the fine fibers of the brain. They also interefere seriously with arterial circulation and should be enjoyed all the more sparingly as their deleterious effects are slow and imperceptible. Tobacco, on the other hand, is conducive to easy and pleasant thinking and detracts from the intensity and concentration necessary to all original and vigorous effort of the intellect. Chewing gum is helpful for a short while but soon drains the glandular system and inficts irreparable damage, not to speak of the revulsion it creates. Alcohol in small quantities is an excellent tonic, but is toxic in its action when absorbed in larger amounts, quite immaterial as to whether it is taken in as whiskey or produced in the stomach from sugar. But it should not be overlooked that all these are great eliminators assisting Nature, as they do, in upholding her stern but just law of the survival of the fittest. Eager reformers should also be mindful of the eternal perversity of mankind which makes the indifferent *"laissez-faire"* by far preferable to enforced restraint. The truth about this is that we need stimulants to do our best work under present living conditions, and that we must exercise moderation and control our appetites and inclinations in every direction. That is what I have been doing for many years, in this way maintaining myself young in body and mind. Abstinence was not always to my liking but I find ample reward in the agreeable experiences I am now making. Just in the hope of converting some to my precepts and convictions I will recall one or two.

A short time ago I was returning to my hotel. It was a bitter cold night, the ground slippery, and no taxi to be had. Half a block behind me followed another man, evidently as anxious as myself to get under

(*Cont. on page* 839)

BOYS will be boys, the world over. The Boy Tesla was no exception to the universal rule, as this, his second autobiographical article clearly proves.

Mr. Tesla in his own inimitable, delightful way, here paints with a literary artist's brush his own intimate boyhood in charming as well as vivid colors.

We have often heard of Tesla, the dreamer. But if he is entitled to the epithet, his early boyhood certainly fails to reveal it. Tesla did not allow much grass to grow under his feet while a boy, for he assuredly was a strenuous, red-blooded youngster.

You will wish to read all about the greatest inventor's early boyhood. It is doubly valuable because it comes from his own pen. We promise you an interesting twenty-minutes' entertainment.

—EDITOR.

This Photograph Shows in the Background the House in Which Mr. Tesla's Family Resided. The Edifice at the Right Is the "Real Gymnasium" Where He Studied. The Ecclesiastic Gentleman Is His Uncle, the Metropolitan of Bosnia, Who Was a Great Statesman and Who Thwarted the Designs of Austria Upon Serbia at a Critical Period.



An interesting study of the great inventor, contemplating the glass bulb of his famous wireless light. A full description of the invention will appear shortly in the ELECTRICAL EXPERIMENTER. *This is the only profile photograph of Mr. Tesla in existence. It was taken specially for the* ELECTRICAL EXPERIMENTER.

© 1919 by E. P. Co.

THE ROGERS UNDERGROUND WIRELESS.

(*Continued from page* 835)

thusa" at sea about 150 miles from New Orleans.

Main Antenna		Underground Antenna (500' composite)	
Sig	Static	Sig.	Static
400	5000	300	15

The "Arethusa" had been trying to get thru a naval despatch which could not be copied on elevated antenna on account of serious static interference. The despatch was taken on the underground antenna, and *every word copied correctly.*

At 9 P. M., April 7, 1917, it was possible to copy signals from Tuckerton with ease, while static on the elevated antenna made it impossible to read any arc signals.

The following results were obtained with spark signals:

Three hundred foot wires in parallel, ten feet apart, a .002 m.f. condenser in series with primary coil of a Telefunken receiver to obtain 600 meters.

Date	Station	W. L.	Sig. Aud Ground Antenna	Static Aud Ground Antenna	Sig Aud Main Antenna	Static Aud Main Antenna
Apr. 2	Point Isabel	600	15			
Apr. 2	Tampa	600	200	0		3000
Apr. 2	Port Arthur	600	150	0		3000
Apr. 2	Pensacola	1200	20	0	100	150
Apr. 2	Ft. Sam Houston		150			

Of particular interest is the fact that when static *prevents* reception on the main antenna, reception can be continued on the underground antenna. *This has even been done during a severe lightning storm, when the main antenna would have been dangerous without grounding.* Reception is also directional and permits of avoiding interference to some extent by using wire "off direction" of an interfering station.

Strays: Strays are as a rule practically absent. Occasional loud cracks widely separated are received. (Ed. note. This has since been overcome.) These isolated strays, altho frequently loud, do not interfere in the least with the reception of signals. On two occasions, strays have risen to an audibility in excess of 5,000 on these separate cracks, but even in this case, reception of signals, altho a little difficult, *was not interrupted.* On these two occasions it was necessary to *ground* both of the (elevated) aërials at the main station.

Considering the matter of strays, it can be said that on four or five occasions during one week, which was one marked by tremendous storms in the Great Lakes region, that strays rose to an audibility in excess of 10,000 at the beach station. Even in this case, however, signals from boats within 100 miles and from shore stations, such as Ludington, Milwaukee and Manitowoc, were usually readable, because the strays while very loud, were nowhere near as numerous as on the elevated aërial. Durthese periods a messenger was kept at the beach station to carry up messages to the main station, which could not receive these signals on account of the strays.

There seems to be no appreciable advantage in using more than one wire—No. 12 weather proof insulated.

The experiments at Great Lakes confirm the work of the Bureau of Standards on the importance of adequate insulation of the wire. If the wires are grounded at the ends, it does not necessarily make much difference unless they are adjusted to the optimum wire length; but if properly adjusted to this length, grounding of the wires, either intentionally or accidentally, produces a diminuation of the signals, which, however, even with the intentional grounding of the two ends, still leaves them 50% of their maximum value. Therefore, while the question of insulation is important, it does not mean that the system will fail entirely if the insulation becomes faulty.

MY INVENTIONS.

(*Continued from page* 776)

cover. Suddenly my legs went up in the air. In the same instant there was a flash in my brain, the nerves responded, the muscles contracted, I swung thru 180 degrees and landed on my hands. I resumed my walk as tho nothing had happened when the stranger caught up with me. "How old are you?" he asked, surveying me critically. "Oh, about fifty-nine," I replied. "What of it?" "Well," said he, "I have seen a cat do this but never a man." About a month since I wanted to order new eyeglasses and went to an oculist who put me thru the usual tests. He lookt at me incredulously as I read off with ease the smallest print at considerable distance. But when I told him that I was past sixty he gasped in astonishment. Friends of mine often remark that my suits fit me like gloves but they do not know that all my clothing is made to measurements which were taken nearly 35 years ago and never changed. During this same period my weight has not varied one pound.

In this connection I may tell a funny story. One evening, in the winter of 1885, Mr. Edison, Edward H. Johnson, the President of the Edison Illuminating Company, Mr. Batchellor, Manager of the works, and myself entered a little place opposite 65 Fifth Avenue where the offices of the company were located. Someone suggested guessing weights and I was induced to step on a scale. Edison felt me all over and said: "Tesla weighs 152 lbs. to an ounce," and he guest it exactly. Stript I weighed 142 lbs. and that is still my weight. I whispered to Mr. Johnson: "How is it possible that Edison could guess my weight so closely?" "Well," he said, lowering his voice, "I will tell you, confidentially, but you must not say anything. He was employed for a long time in a Chicago slaughter-house where he weighed thousands of hogs every day! That's why." My friend, the Hon. Chauncey M. Depew, tells of an Englishman on whom he sprung one of his original anecdotes and who listened with a puzzled expression but—a year later—laughed out loud. I will frankly confess it took me longer than that to appreciate Johnson's joke.

Now, my well being is simply the result of a careful and measured mode of living and perhaps the most astonishing thing is that three times in my youth I was rendered by illness a hopeless physical wreck and given up by physicians. More than this, thru ignorance and lightheartedness, I got into all sorts of difficulties, dangers and scrapes from which I extricated myself as by enchantment. I was almost drowned a dozen times; was nearly boiled alive and just mist being cremated. I was entombed, lost and frozen. I had hair-breadth escapes from mad dogs, hogs, and other wild animals. I past thru dreadful diseases and met with all kinds of odd mishaps and that I am hale and hearty today seems like a miracle. But as I recall these incidents to my mind I feel convinced that my preservation was not altogether accidental.

An inventor's endeavor is essentially life-saving. Whether he harnesses forces, improves devices, or provides new comforts and conveniences, he is adding to the safety of our existence. He is also better qualified than the average individual to protect himself in peril, for he is observant and resourceful. If I had no other evidence that I was, in a measure, possest of such qualities I would find it in these personal experiences. The reader will be able to judge for himself if I mention one or two instances. On one occasion, when about 14 years old, I wanted to scare some friends who were bathing with me. My plan was to dive under a long floating structure and slip out quietly at the other end. Swimming and diving came to me as naturally as to a

LISTEN TO ME!

Be A CERTIFICATED ELECTRICIAN

THIS IS YOUR CHANCE OF A LIFE TIME

I am Chief Engineer of the great Chicago Engineering Works. I am in close official touch with the electrical world. I know how badly we need trained electricians who can take charge of important work as experts. Right now there is such a need for executive electricians that I am making a special effort to help meet the demand. I am publishing this special announcement to secure a certain number of ambitious men whom I will personally train by mail for the wonderful opportunities that are open.

I WILL MAKE YOU a Trained Electrician

I don't care how young or old you are, just as long as you can read and write and have a spark of ambition. I don't care where you live or what you do. I don't care if you don't know a blessed thing about electricity. Just give me a little of your spare time for a short period and I'll show you the quick way to success in electricity. You can qualify to earn **$36 to $100 a week** with opportunities for greater earnings.

I Train You by Mail!

Your spare time will do. No interference with your regular duties. I understand just what you must know and I have devised a wonderful way of instructing by mail. I positively guarantee your satisfaction.

Free *Wonderful Electrical Outfit*

Absolutely free. Not a penny cost to you now or later. To those who act at once I will give a wonderful set of Electrical Equipment with my compliments. Write me at once. I have only a limited number of sets to be given free. Drop me a post card or letter.

Write! You will have to act quick to get in on this opportunity. Write me today for full particulars. Drop me a post card. ***Write Now.***

CHIEF ENGINEER COOKE,
Chicago Engineering Works,
Dept. 523
441 Cass Street, Chicago, Illinois

BE A BOY CHEMIST

Test water, foods and other things you use and wear. Make soap, ink, dye; fire-proof cloth and wood, and work hundreds of useful, fascinating experiments just like a real chemist. Perform weird, puzzling tricks of chemical magic. You can, with "CHEMCRAFT". Outfits contain all chemicals and laboratory supplies to work each experiment many times; also a Manual of Instruction. "CHEMCRAFT" is absolutely harmless; made by a practical chemist and is scientifically correct.

Chemcraft No. 1—$1.50
West of Mississippi River and in Canada—$2.00
Chemcraft No. 2—$3.00
West of Mississippi River and in Canada—$3.50
Chemcraft No. 3—$5.00
West of Mississippi River and in Canada—$6.00

Be sure you get "CHEMCRAFT," the original and most complete and scientific chemical outfit. Ask for it by name at your Toy Store, or send price and we will deliver direct prepaid.

THE PORTER CHEMICAL CO.
Industrial Bldg., W. Washington St.
Hagerstown Maryland

House Lighting Plants

$225 to $2100

Write for Catalog, giving name of your electrical dealer. Agents Wanted.

Dynamos, Motors

all sizes. Battery Chargers and Motor Generator Sets, $25. to $120. Hydro-Electric Generators. Which catalog do you want?

SPECIAL—Holtzer-Cabot 110 Volt Hand Generators, while they last, only $5. Order from this ad.

WATSON ELECTRIC CO., Dept. 13, Gas Bldg. Chicago.

SOLDIERS, CADETS & MILITARY SCHOOLS ATTENTION

Service Stripes—Gold, Silver, Red, Blue & Green (Reg.) 20c per Stripe
Gold & Silver Stars—Metal or Embroidered (Reg.) 25c Each
Over-seas Caps—Wool (Army Reg.)—$1.00 Each
Cuff Leggings—"Waterproof" 15 oz. O. D. Duck (Reg.) $1.55 pr.
Cuff Leggings—Light Color O. D. Duck, 20 oz. (Reg.) $1.75 pr.
Semaphore Flags—14x14 inches, Red & White Bunting 75c pr.

Special Caps, Uniforms, Belts and Insignia. Camping and Hiking equipment. Cadet, Military School and Boy Scout supplies.

Above sent, postpaid, upon receipt of price. Kindly mention name of school, organization or branch of service.
Cadet Equipment Co., 727 Tinton Ave., New York City

BIG BUNCH OF FUN 10c

I New Airship Game with Airships, 1 Chess and Checker Board and men, 1 Chinese Dip-se-lu-la, 1 Set Dominoes, 12 Other Games, 19 Lessons in Magic, 12 Money Making Secrets, Wireless Code, 18 Pictures Pretty Girls, 3 Puzzles, & New Ford Joke Book. All for 10c with large Catalogue.

Dept. 72
American Toy Co., Lowell, Mass., U. S. A.

Feldman's "Geyser" Electric Water Heater

Instantaneous Hot Water

FELDMAN MFG. CO.
1500 Times Bldg. New York City

BIG PROFITS

for you in HB Battery Charging



Others clear $100 to $200 a month extra profit. So can you. Write for particulars or send $15 first payment for HB 500 watt Charger on trial under absolute money-back guarantee. Balance in 9 monthly payments of $20 each. No risk. Order today.

Hobart Brothers Company,
Box 3E, Troy, Ohio.



POPULARITY FOLLOWS THE UKULELE

If you play quaint, dreamy Hawaiian music or latest songs on the Ukulele you will be wanted everywhere. We teach by mail 20 simple lessons; give you free a genuine Hawaiian Ukulele, music, everything—no extras. Ask us to send the story of Hawaiian music. You will love it. No obligation—absolutely free.

The Hawaiian Institute of Music
1400 Broadway, Suite 1103, New York

duck and I was confident that I could perform the feat. Accordingly I plunged into the water and, when out of view, turned around and proceeded rapidly towards the opposite side. Thinking that I was safely beyond the structure, I rose to the surface but to my dismay struck a beam. Of course, I quickly dived and forged ahead with rapid strokes until my breath was beginning to give out. Rising for the second time, my head came again in contact with a beam. Now I was becoming desperate. However, summoning all my energy, I made a third frantic attempt but the result was the same. The torture of suppressed breathing was getting unendurable, my brain was reeling and I felt myself sinking. At that moment, when my situation seemed absolutely hopeless, I experienced one of those flashes of light and the structure above me appeared before my vision. I either discerned or guest that there was a little space between the surface of the water and the boards resting on the beams and, with consciousness nearly gone, I floated up, prest my mouth close to the planks and managed to inhale a little air, unfortunately mingled with a spray of water which nearly choked me. Several times I repeated this procedure as in a dream until my heart, which was racing at a terrible rate, quieted down and I gained composure. After that I made a number of unsuccessful dives, having completely lost the sense of direction, but finally succeeded in getting out of the trap when my friends had already given me up and were fishing for my body.

That bathing season was spoiled for me thru recklessness but I soon forgot the lesson and only two years later I fell into a worse predicament. There was a large flour mill with a dam across the river near the city where I was studying at that time. As a rule the height of the water was only two or three inches above the dam and to swim out to it was a sport not very dangerous in which I often indulged. One day I went alone to the river to enjoy myself as usual. When I was a short distance from the masonry, however, I was horrified to observe that the water had risen and was carrying me along swiftly. I tried to get away but it was too late. Luckily, tho, I saved myself from being swept over by taking hold of the wall with both hands. The pressure against my chest was great and I was barely able to keep my head above the surface. Not a soul was in sight and my voice was lost in the roar of the fall. Slowly and gradually I became exhausted and unable to withstand the strain longer. Just as I was about to let go, to be dashed against the rocks below, I saw in a flash of light a familiar diagram illustrating the hydraulic principle that the pressure of a fluid in motion is proportionate to the area exposed, and automatically I turned on my left side. As if by magic the pressure was reduced and I found it comparatively easy in that position to resist the force of the stream. But the danger still confronted me. I knew that sooner or later I would be carried down, as it was not possible for any help to reach me in time, even if I attracted attention. I am ambidextrous now but then I was left-handed and had comparatively little strength in my right arm. For this reason I did not dare to turn on the other side to rest and nothing remained but to slowly push my body along the dam. I had to get away from the mill towards which my face was turned as the current there was much swifter and deeper. It was a long and painful ordeal and I came near to failing at its very end for I was confronted with a depression in the masonry. I managed to get over with the last ounce of my force and fell in a swoon when I reached the bank, where I was found. I had torn virtually all the skin from my left side and it took several weeks before the fever subsided and I was well. These are only two

HEL-MET THE KAISER

Send one to your boy in camp; all the boys will want them. Anyone against the Kaiser or Germany should wear this pin. Same size as picture. Handsome metal, black letters. Will wear for years. Men and women wear them — causes laughter wherever seen.

Price 10 Cents

Voice Thrower 10c

Learn to throw your voice into a TRUNK, under the bed, out in the hall or anywhere. Lots of FUN fooling the Teacher, Janitor, Policeman, Parents, Neighbors, or Friends.

THE VENTRILO

is a little instrument that fits into the mouth out of sight. BOYS or GIRLS can use it. NEVER FAILS! A 32-page book on Ventriloquism sent with the VENTRILO for TEN Cents.

NEW FORD JOKE BOOK 1919

All the latest jokes on the Ford auto. Hundreds of them, and all good ones. Spring a new one on your neighbors.

Large book with colored cover by mail, 10c.

Devil Resigns to the Kaiser

Everyone who reads this book is wild over it. Contains the following:—The Kaiser's Dream, A Letter from the Devil to the Kaiser, Kaiser's Prayer, How Satan Resigns to the King of Devils, The Kaiser, etc. Many other stories, jokes, etc., about the German Emperor. Book mailed 10 cents, postage 2 cents extra.

ROGEN X-RAY

Price 10 Cents

HERE, BOYS, is just what you want. With this instrument you can apparently see through clothes, see the bones in your fingers. Think of the fun you can have with it. Sample, by mail, TEN CENTS.

SKULL RING



Here is a handsome, up-to-date Ring, representing a Skull and Cross-bones. Has stones in the eyes and looks something frightful. Women won't like it, but for men or boys it is a great novelty. Sample, by mail, 15c.

Gee! What a Wad!

This is STAGE MONEY

Looks like the GENUINE STUFF. Some Green backs and some Yellow backs. Create a BIG sensation among your friends. The girls will all be after you when they see the wad. BIG roll of 15 pieces by mail, 10 cents.

Boys Own Toy Maker

and Nine Other Books for 10c

Tells how to make a Telephone, Magic Lantern, Kites, Sail Boat, Stilts, Electric Telegraph, Pop Gun, Red Fire, Galvanic Battery and many other things. This book, with nine other interesting books, mailed for 10c.

ENCHANTED BARREL

The Most Wonderful Pocket Trick Made

CHANGE A CENT INTO A DIME



Ask your friend to drop a dime in the barrel. When he takes it out, Behold! It is a CENT. You make 9 cents every time you fool them. Never fails. They cannot get on to it. Sample barrel, with directions, only.... **10c**

Any three of the above articles for 25c or any six for 50c

Royal Novelty Co. 250 EAST AVENUE SOUTH NORWALK, CONN.

Better Your Position

Prepare for a permanent position. Railway Traffic Inspectors are always in line for advancement. No age limit—only common school education. Mighty good salary and expenses. A Railway Traffic Inspector safeguards the lives of the public and protects his company's interests—an important position. He's paid to travel and observe. Works only with railroad officials—that's why he's bound to gain a position of trust. Hundreds needed right now—thousands later. Study for only three months—we'll arrange for the position. Delay never secured anyone a better position—so act immediately. Booklet D 21 tells all—write today. Address

Through the Standard Business Training Inst. BUFFALO, N. Y.

of many instances but they may be sufficient to show that had it not been for the inventor's instinct I would not have lived to tell this tale.

Interested people have often asked me how and when I began to invent. This I can only answer from my present recollection in the light of which the first attempt I recall was rather ambitious for it involved the invention of an *apparatus* and a *method*. In the former I was anticipated but the latter was original. It happened in this way. One of my playmates had come into the possession of a hook and fishing-tackle which created quite an excitement in the village, and the next morning all started out to catch frogs. I was left alone and deserted owing to a quarrel with this boy. I had never seen a real hook and pictured it as something wonderful, endowed with peculiar qualities, and was despairing not to be one of the party. Urged by necessity, I somehow got hold of a piece of soft iron wire, hammered the end to a sharp point between two stones, bent it into shape, and fastened it to a strong string. I then cut a rod, gathered some bait, and went down to the brook where there were frogs in abundance. But I could not catch any and was almost discouraged when it occurred to me to dangle the empty hook in front of a frog sitting on a stump. At first he collapsed but by and by his eyes bulged out and became bloodshot, he swelled to twice his normal size and made a vicious snap at the hook. Immediately I pulled him up. I tried the same thing again and again and the method proved infallible. When my comrades, who in spite of their fine outfit had caught nothing, came to me they were green with envy. For a long time I kept my secret and enjoyed the monopoly but finally yielded to the spirit of Christmas. Every boy could then do the same and the following summer brought disaster to the frogs.

In my next attempt I seem to have acted under the first instinctive impulse which later dominated me—to harness the energies of nature to the service of man. I did this thru the medium of May-bugs—or June-bugs as they are called in America—which were a veritable pest in that country and sometimes broke the branches of trees by the sheer weight of their bodies. The bushes were black with them. I would attach as many as four of them to a cross-piece, rotably arranged on a thin spindle, and transmit the motion of the same to a large disc and so derive considerable "power." These creatures were remarkably efficient, for once they were started they had no sense to stop and continued whirling for hours and hours and the hotter it was the harder they worked. All went well until a strange boy came to the place. He was the son of a retired officer in the Austrian Army. That urchin ate May-bugs alive and enjoyed them as tho they were the finest blue-point oysters. That disgusting sight terminated my endeavors in this promising field and I have never since been able to touch a May-bug or any other insect for that matter.

After that, I believe, I undertook to take apart and assemble the clocks of my grandfather. In the former operation I was always successful but often failed in the latter. So it came that he brought my work to a sudden halt in a manner not too delicate and it took thirty years before I tackled another clockwork again. Shortly thereafter I went into the manufacture of a kind of pop-gun which comprised a hollow tube, a piston, and two plugs of hemp. When firing the gun, the piston was prest against the stomach and the tube was pushed back quickly with both hands. The air between the plugs was comprest and raised to high temperature and one of them was expelled with a loud report. The art consisted in selecting a tube of the proper taper from the hollow stalks which were

(*Continued on page* 843)



Moving Picture Machine

A REAL moving picture machine that uses the same films as the big movie theaters all over the country and you can get it ***absolutely free*** with a box of film besides.

FREE

Have a movie show right in your own home. Entertain your friends and relatives. Charge admission and make easy spending money. You never had a chance like this before and it may not be repeated again. Send your name on the coupon NOW!

Boys! Girls! Act Quick!

Send your name on the coupon below or a post card will do—but you must do this right now, this very minute. I will send you 12 beautifully colored patriotic pictures. Every one who sees them wants them. Full of action, showing our brave soldiers and sailors performing their heroic duties in the trenches and at home. All you have to do is distribute these pictures on a special 35c offer among the people you know. This will take you just a few hours. They go like hot cakes, everybody wants them. When you have distributed the 12 pictures I will immediately send you FREE and Prepaid this Genuine Moving Picture Machine Complete with a box of film. Don't miss this wonderful offer.

Send This Coupon Right NOW!

Don't wait another minute. It may be too late if you wait. Send your name on a postal card if you want to—but do it right now—AT ONCE!

Movie Man 180 No. Wabash Ave. Dept 7443 Chicago

To Mr. Movie Man
Dept 7443 -180 N. Wabash Ave., Chicago

I want to get a Moving Picture Machine FREE by your easy plan. Please send me the Patriotic Pictures and full details of your Big Offer.

Name.....

St. or R. F. D......

Town..... *State*.....

The House of Taylor



400 Baths
600 Rooms

HOTEL MARTINIQUE

BROADWAY, 33D STREET, NEW YORK
One Block from Pennsylvania Station.

Equally Convenient for Amusements, Shopping or Business

157 Pleasant Rooms, with Private Bath, $2.50 PER DAY.

257 Excellent Rooms, with Private Bath, facing street, southern exposure, $3.00 PER DAY.

Also Attractive Rooms from $1.50.
The Restaurant Prices Are Most Moderate.



1-50 H. P. Motor $4.00 complete as shown

If you are in need of a small motor for experimental purposes, this is your chance to get one at a very low price. Wound for 110 volt A. C. or D. C. Built exactly the same as a large motor; twenty-two section commutator, laminated field and armature construction, drum wound armature.

We have only a limited quantity to offer at this price which means that you must act quick if you wish to secure one at this low price.

BODINE ELECTRIC COMPANY
2254 WEST OHIO STREET CHICAGO, ILLINOIS

MY INVENTIONS

(*Continued from page* 841)

did very well with that gun but my activities interfered with the window panes in our house and met with painful discouragement. If I remember rightly, I then took to carving swords from pieces of furniture which I could conveniently obtain. At that time I was under the sway of the Serbian national poetry and full of admiration for the feats of the heroes. I used to spend hours in mowing down my enemies in the form of corn-stalks which ruined the crops and netted me several spankings from my mother. Moreover these were not of the formal kind but the genuine article.

I had all this and more behind me before I was six years old and had past thru one year of elementary school in the village of Smiljan where I was born. At this juncture we moved to the little city of Gospic nearby. This change of residence was like a calamity to me. It almost broke my heart to part from our pigeons, chickens and sheep, and our magnificent flock of geese which used to rise to the clouds in the morning and return from the feeding grounds at sundown in battle formation, so perfect that it would have put a squadron of the best aviators of the present day to shame. In our new house I was but a prisoner, watching the strange people I saw thru the window blinds. My bashfulness was such that I would rather have faced a roaring lion than one of the city dudes who strolled about. But my hardest trial came on Sunday when I had to dress up and attend the service. There I met with an accident, the mere thought of which made my blood curdle like sour milk for years afterwards. It was my second adventure in a church. Not long before I was entombed for a night in an old chapel on an inaccessible mountain which was visited only once a year. It was an awful experience, but this one was worse. There was a wealthy lady in town, a good but pompous woman, who used to come to the church gorgeously painted up and attired with an enormous train and attendants. One Sunday I had just finished ringing the bell in the belfry and rushed downstairs when this grand dame was sweeping out and I jumped on her train. It tore off with a ripping noise which sounded like a salvo of musketry fired by raw recruits. My father was livid with rage. He gave me a gentle slap on the cheek, the only corporal punishment he ever administered to me but I almost feel it now. The embarrassment and confusion that followed are indescribable. I was practically ostracised until something else happened which redeemed me in the estimation of the community.

An enterprising young merchant had organized a fire department. A new fire engine was purchased, uniforms provided and the men drilled for service and parade. The engine was, in reality, a pump to be worked by sixteen men and was beautifully painted red and black. One afternoon the official trial was prepared for and the machine was transported to the river. The entire population turned out to witness the great spectacle. When all the speeches and ceremonies were concluded, the command was given to pump, but not a drop of water came from the nozzle. The professors and experts tried in vain to locate the trouble. The fizzle was complete when I arrived at the scene. My knowledge of the mechanism was nil and I knew next to nothing of air pressure, but instinctively I felt for the suction hose in the water and found that it had collapsed. When I waded in the river and opened it up the water rushed forth and not a few Sunday clothes were spoiled. Archimedes running naked thru the streets of Syracuse and shouting Eureka at the top of his voice did not make a greater impression than myself. I was carried on the shoulders and was the hero of the day.

Upon settling in the city I began a four-years' course in the so-called Normal School preparatory to my studies at the College or *Real-Gymnasium*. During this period my boyish efforts and exploits, as well as troubles, continued. Among other things I attained the unique distinction of champion crow catcher in the country. My method of procedure was extremely simple. I would go in the forest, hide in the bushes, and imitate the call of the bird. Usually I would get several answers and in a short while a crow would flutter down into the shrubbery near me. After that all I needed to do was to throw a piece of cardboard to detract its attention, jump up and grab it before it could extricate itself from the undergrowth. In this way I would capture as many as I desired. But on one occasion something occurred which made me respect them. I had caught a fine pair of birds and was returning home with a friend. When we left the forest, thousands of crows had gathered making a frightful racket. In a few minutes they rose in pursuit and soon enveloped us. The fun lasted until all of a sudden I received a blow on the back of my head which knocked me down. Then they attacked me viciously. I was compelled to release the two birds and was glad to join my friend who had taken refuge in a cave.

In the schoolroom there were a few mechanical models which interested me and turned my attention to water turbines. I constructed many of these and found great pleasure in operating them. How extraordinary was my life an incident may illustrate. My uncle had no use for this kind of pastime and more than once rebuked me. I was fascinated by a description of Niagara Falls I had perused, and pictured in my imagination a big wheel run by the Falls. I told my uncle that I would go to America and carry out this scheme. Thirty years later I saw my ideas carried out at Niagara and marveled at the unfathomable mystery of the mind.

I made all kinds of other contrivances and contraptions but among these the arbalists I produced were the best. My arrows, when shot, disappeared from sight and at close range traversed a plank of pine one inch thick. Thru the continuous tightening of the bows I developed skin on my stomach very much like that of a crocodile and I am often wondering whether it is due to this exercise that I am able even now to digest cobble-stones! Nor can I pass in silence my performances with the sling which would have enabled me to give a stunning exhibit at the Hippodrome. And now I will tell of one of my feats with this antique implement of war which will strain to the utmost the credulity of the reader. I was practicing while walking with my uncle along the river. The sun was setting, the trout were playful and from time to time one would shoot up into the air, its glistening body sharply defined against a projecting rock beyond. Of course any boy might have hit a fish under these propitious conditions but I undertook a much more difficult task and I foretold to my uncle, to the minutest detail, what I intended doing. I was to hurl a stone to meet the fish, press its body against the rock, and cut it in two. It was no sooner said than done. My uncle looked at me almost scared out of his wits and exclaimed *"Vade retro Satanas!"* and it was a few days before he spoke to me again. Other records, however great, will be eclipsed but I feel that I could peacefully rest on my laurels for a thousand years.

(In the April issue Mr. Tesla will describe in detail how he conceived one of his most important and far reaching inventions: "The Rotary Magnetic Field."—Editor.)

He's Winning!

Because He Followed His BENT.

Age 28—Salary $2500 a year—General Manager of the Company—his own boss—owns his home—married and happy and prosperous—there's the success of Wallace H. Rohrschneider, General Manager and Secretary and Treasurer of the Hustisford Light, Power and Manufacturing Company of Hustisford, Wisconsin.

"I followed my bent," says Mr. Rohrschneider. That's all. "I followed my bent." In these crisp words he sums up his success. Young—unknown—of humble birth—reared on the farm and deprived of scholastic advantages, he entered this school in 1907 and took up the study of Electricity. And today—at 28—in the work he felt he was fitted for—he's well on the road to success. Simply because he **answered his instincts.** Simply because he **followed his bent.**

Is Electricity YOUR "BENT"?

If it is—if you like to tinker with dry cells—if you like to experiment with "wireless"—if you're keen for the columns of "How To Make It" and each new edition of Electrical Experimenter is a fresh revelation to you—**then tackle the job in earnest. Study** electricity. Make a real start. **And do it now right on the eve of the big coming era of reconstruction when thousands of trained electrical experts will be needed at home and abroad.**

Earn While You Learn If You Wish—½ day of classes—½ day of paid employment—that is the basis of our "Earn-While-You-Learn" plan.

Hundreds of young men of ambition are taking advantage of the opportunities afforded by electricity to insure for themselves a sound, successful future. Why not decide now to join them? Why not take the first step today? Filling out and mailing this coupon will help you decide. Do it now and get the facts. No obligation whatever.

Spring Term Opens April 1st

— — — — —Tear Out Here— — — — —

SCHOOL OF ENGINEERING OF MILWAUKEE

"America's Most Democratic Electrical Institute"

79-373 Broadway, Milwaukee, Wis.

Without obligating me, please send me catalog and tell me how I can qualify in the subject I have checked below:
[ ] **Electrical Engineering** [ ] **Electrotechnician**

[ ] **Electrician**

Six Months' Trade Course

[ ] **Electrical Trouble and Lineman**
[ ] **Electrical Meterman**
[ ] **Electrical Wireman**
[ ] **Motor and Generator Repairman** (Course includes Armature and Transformer Winding)
[ ] **Telephone Trouble and Repairman**
[ ] **Electrical Draftsman**
[ ] **Home Study Department** (Special Preliminary Home Study Course for those who cannot at first come to Milwaukee)

NAME.....

ADDRESS.....

CITY.....STATE.....

AGE.....EDUCATION.....

My Inventions

By Nikola Tesla

III. MY LATER ENDEAVORS

The Discovery of the Rotating Magnetic Field

AT the age of ten I entered the Real Gymnasium which was a new and fairly well equipt institution. In the department of physics were various models of classical scientific apparatus, electrical and mechanical. The demonstrations and experiments performed from time to time by the instructors fascinated me and were undoubtedly a powerful incentive to invention. I was also passionately fond of mathematical studies and often won the professor's praise for rapid calculation. This was due to my acquired facility of visualizing the figures and performing the operations, not in the usual intuitive manner, but as in actual life. Up to a certain degree of complexity it was absolutely the same to me whether I wrote the symbols on the board or conjured them before my mental vision. But free-hand drawing, to which many hours of the course were devoted, was an annoyance I could not endure. This was rather remarkable as most of the members of the family excelled in it. Perhaps my aversion was simply due to the predilection I found in undisturbed thought. Had it not been for a few exceptionally stupid boys, who could not do anything at all, my record would have been the worst. It was a serious handicap as under the then existing educational regime, drawing being obligatory, this deficiency threatened to spoil my whole career and my father had considerable trouble in railroading me from one class to another.



Nikola Tesla at 60. A Very Recent Portrait of the Great Inventor. An Excellent Likeness.

In the second year at that institution I became obsest with the idea of producing continuous motion thru steady air pressure. The pump incident, of which I have told, had set afire my youthful imagination and imprest me with the boundless possibilities of a vacuum. I grew frantic in my desire to harness this inexhaustible energy but for a long time I was groping in the dark. Finally, however, my endeavors crystallized in an invention which was to enable me to achieve what no other mortal ever attempted. Imagine a cylinder freely rotatable on two bearings and partly surrounded by a rectangular trough which fits it perfectly. The open side of the trough is closed by a partition so that the cylindrical segment within the enclosure divides the latter into two compartments entirely separated from each other by air-tight sliding joints. One of these compartments being sealed and once for all exhausted, the other remaining open, a perpetual rotation of the cylinder would result, at least, I thought so. A wooden model was constructed and fitted with infinite care and when I applied the pump on one side and actually observed that there was a tendency to turning, I was delirious with joy. Mechanical flight was the one thing I wanted to accomplish altho still under the discouraging recollection of a bad fall I sustained by jumping with an umbrella from the top of a building. Every day I used to transport myself thru the air to distant regions but could not understand just how I managed to do it. Now I had something concrete—a flying machine with nothing more than a rotating shaft, flapping wings, and—a vacuum of, unlimited power! From that time on I made my daily aërial excursions in a vehicle of comfort and luxury as might have befitted King Solomon. It took years before I understood that the atmospheric pressure acted at right angles to the surface of the cylinder and that the slight rotary effort I observed was due to a leak. Tho this knowledge came gradually it gave me a painful shock.

I had hardly completed my course at the Real Gymnasium when I was prostrated with a dangerous illness or rather, a score of them, and my condition became so desperate that I was given up by physicians. During this period I was permitted to read constantly, obtaining books from the Public Library which had been neglected and entrusted to me for classification of the works and preparation of the catalogues. One day I was handed a few volumes of new literature unlike anything I had ever read before and so captivating as to make me utterly forget my hopeless state. They were the earlier works of Mark Twain and to them might have been due the miraculous recovery which followed. Twenty-five years later, when I met Mr. Clements and we formed a friendship between us, I told

Copyright, 1919, by E. P. Co. All rights reserved

Mr. Tesla's articles started in our February issue

him of the experience and was amazed to see that great man of laughter burst into tears.

My studies were continued at the higher Real Gymnasium in Carlstadt, Croatia, where one of my aunts resided. She was a distinguished lady, the wife of a Colonel who was an old war-horse having participated in many battles. I never can forget the three years I past at their home. No fortress in time of war was under a more rigid discipline. I was fed like a canary bird. All the meals were of the highest quality and deliciously prepared but short in quantity by a thousand percent. The slices of ham cut by my aunt were like tissue paper. When the Colonel would put something substantial on my plate she would snatch it away and say excitedly to him: "Be careful, Niko is very delicate." I had a voracious appetite and suffered like Tantalus. But I lived in an atmosphere of refinement and artistic taste quite unusual for those times and conditions. The land was low and marshy and malaria fever never left me while there despite of the enormous amounts of quinin I consumed. Occasionally the river would rise and drive an army of rats into the buildings, devouring everything even to the bundles of the fierce paprika. These pests were to me a welcome diversion. I thinned their ranks by all sorts of means, which won me the unenviable distinction of rat-catcher in the community. At last, however, my course was completed, the misery ended, and I obtained the certificate of maturity which brought me to the cross-roads.

THIS installment, no doubt the most interesting of the three published so far, reveals many extraordinary occurrences and experiences in the world's greatest inventor's life—experiences such as do not fall to the lot of ordinary mortals. And Tesla, the many sided, aside of inventing, knows the rare art of painting word-pictures. He does so here in a masterly fashion. He tells us how he finally conceived the induction motor—perhaps his greatest discovery—the invention which changed the face of the globe, the invention which made possible the street car, the subway, the electric train, power transmission, the harnessing of water falls and countless others. But let Tesla tell you himself how it all came about. It is a classic worth reading. *EDITOR.*

During all those years my parents never wavered in their resolve to make me embrace the clergy, the mere thought of which filled me with dread. I had become intensely interested in electricity under the stimulating influence of my Professor of Physics, who was an ingenious man and often demonstrated the principles by apparatus of his own invention. Among these I recall a device in the shape of a freely rotatable bulb, with tinfoil coatings, which was made to spin rapidly when connected to a static-machine. It is impossible for me to convey an adequate idea of the intensity of feeling I experienced in witnessing his exhibitions of these mysterious phenomena. Every impression produced a thousand echoes in my mind. I wanted to know more of this wonderful force; I longed for experiment and investigation and resigned myself to the inevitable with aching heart.

Just as I was making ready for the long journey home I received word that my father wished me to go on a shooting expedition. It was a strange request as he had been always strenuously opposed to this kind of sport. But a few days later I learned that the cholera was raging in that district and, taking advantage of an opportunity, I returned to Gospic in disregard of my parents' wishes. It is incredible how absolutely ignorant people were as to the causes of this scourge which visited the country in intervals of from fifteen to twenty years. They thought that the deadly agents were transmitted thru the air and filled it with pungent odors and smoke. In the meantime they drank the infected water and died in heaps. I contracted the awful disease on the very day of my arrival and altho surviving the crisis, I was confined to bed for nine months with scarcely any ability to move. My energy was completely exhausted and for the second time I found myself at death's door. In one of the sinking spells which was thought to be the last, my father rushed into the room. I still see his pallid face as he tried to cheer me in tones belying his assurance. "Perhaps," I said, "I may get well if you will let me study engineering." "You will go to the best technical institution in the world." he solemnly replied, and I knew that he meant it. A heavy weight was lifted from my mind but the relief would have come too late had it not been for a marvelous cure brought about thru a bitter decoction of a peculiar bean. I came to life like another Lazarus to the utter amazement of everybody. My father insisted that I spend a year in healthful physical outdoor exercises to which I reluctantly consented. For most of this term I roamed in the mountains, loaded with a hunter's outfit and a bundle of books, and this contact with nature made me stronger in body as well as in mind. I thought and planned, and conceived many ideas almost as a rule delusive. The vision was clear enough but the knowledge of principles was very limited. In one of my inventions I proposed to convey letters and packages across the seas, thru a submarine tube, in spherical containers of sufficient strength to resist the hydraulic pressure. The pumping plant, intended to force the water thru the tube, was accurately figured and designed and all other particulars carefully worked out. Only one trifling detail, of no consequence, was lightly dismist. I assumed an arbitrary velocity of the water and, what is more, took pleasure in making it high, thus arriving at a stupendous performance supported by faultless calculations. Subsequent reflections, however, on the resistance of pipes to fluid flow determined me to make this invention public property.

Another one of my projects was to construct a ring around the equator which would, of course, float freely and could be arrested in its spinning motion by reactionary forces, thus enabling

(*Continued on page* 905)



Tesla's First Induction Motor. This Historic Model is One of the Two First Presented Before the American Institute of Electrical Engineers.

WHAT IS THE INDUCTION MOTOR?

The induction motor operates on alternating current. It has no commutator like a direct current motor, nor slip rings like an alternating current motor. Contrary to the two types just cited the "field" current is not steady, but the current itself rotates constantly pulling around with it—by induction—the only moving part of the motor—the rotor—or armature. Having no armature nor slip rings, the induction motor never sparks. It consequently knows no "brush" trouble. It needs no attention because of its ruggedness. Only the bearings wear out. Its efficiency too is higher. On account of all this the induction motor is used in a prepondering proportion in street cars, electric trains, factories, etc.

teresting incident. He wished to make the apparition of a young lady appear to a lieutenant living several miles away. At the time of the experiment a visitor happened to be with the lieutenant, who is said to have seen the apparition also. Many instances are recorded in which persons were hypnotized at some distance. All of these phenomena can be easily explained by the *brain wave* theory.

Besides the transference of thought, both sympathy and affection may be the outgrowth of these radiations from the brain. Whether our capacity for the reception of these impulses is increasing with the evolution of man, cannot be ascertained directly. It would seem probable, however, that with our increase in education and civilization that a conscious use of this *thought language* may be found. Who knows but that the man of the future may find a practical application for this radiation from the brain, and a higher and more delicately made creature may result who would effect mutual understanding by means of this marvelous and as yet but little understood *psychical activity.*

MY INVENTIONS

(*Continued from page* 865)

travel at a rate of about one thousand miles an hour, impracticable by rail. The reader will smile. The plan was difficult of execution, I will admit, but not nearly so bad as that of a well-known New York professor, who wanted to pump the air from the torrid to the temperate zones, entirely forgetful of the fact that the Lord had provided a gigantic machine for this very purpose.

Still another scheme, far more important and attractive, was to derive power from the rotational energy of terrestrial bodies. I had discovered that objects on the earth's surface, owing to the diurnal rotation of the globe, are carried by the same alternately in and against the direction of translatory movement. From this results a great change in momentum which could be utilized in the simplest imaginable manner to furnish motive effort in any habitable region of the world. I cannot find words to describe my disappointment when later I realized that I was in the predicament of Archimedes, who vainly sought for a fixt point in the universe.

At the termination of my vacation I was sent to the Polytechnic School in Gratz, Styria, which my father had chosen as one of the oldest and best reputed institutions. That was the moment I had eagerly awaited and I began my studies under good auspices and firmly resolved to succeed. My previous training was above the average, due to my father's teaching and opportunities afforded. I had acquired the knowledge of a number of languages and waded thru the books of several libraries, picking up information more or less useful. Then again, for the first time, I could choose my subjects as I liked, and free-hand drawing was to bother me no more. I had made up my mind to give my parents a surprise, and during the whole first year I regularly started my work at three o'clock in the morning and continued until eleven at night, no Sundays or holidays excepted. As most of my fellow-students took things easily, naturally enough I eclipsed all records. In the course of that year I past thru nine exams and the professors thought I deserved more than the highest qualifications. Armed with their flattering certificates, I went home for a short rest, expecting a triumph, and was mortified when my father made light of these hard-won honors. That almost killed my ambition; but later, after he had died, I was pained to find a package of letters which

(*Continued on page* 907)


The STARRETT DATA BOOK for MACHINISTS
STARRETT BOOKS VOLUME II
The STARRETT BOOK for MACHINISTS' APPRENTICES
STARRETT BOOKS VOLUME I

Volume II 180 pages
Volume I 184 pages

both bound in red Athol-leather, gold title, good paper, handy size, 4½" x 7".

You Will Want Both Books

These handy reference books are of exceptional value to you, whether you are an apprentice or a highly skilled mechanic. Both books are edited by men prominent in the machinery field—men who know exactly what is most helpful to the beginner as well as the experienced man.

Volume II for Practical Machinists
Sequel to Volume I

180 pages of important technical data, tables relating to machine speeds, power transmission, drilling, turning and milling, materials, etc.

Volume I for Machinists' Apprentices
Now in 4th Edition

184 pages of material that shows "how to do it." Essential to the beginner, valuable to the experienced machinist. It deals with the layout and precise measurement of work.

Ask Your Hardware Dealer to show them to you, or write direct—50c. each

Catalog No. 21LE of Starrett Tools on request

STARRETT TOOLS — TRADE MARK REG. U.S. PAT. OFF.

THE L. S. STARRETT COMPANY

The World's Greatest Toolmakers, Manufacturers of Hack Saws Unexcelled

ATHOL, MASS.

NEW YORK LONDON CHICAGO

42-900

MAKE MONEY
REPAIRING TIRES

The high cost and limited supply of tires makes it necessary for motorists to conserve their tires and get maximum mileage. Present conditions offer tire repair men a big opportunity to make money. Experienced help not necessary.

With this Shaler Electric Vulcanizer you can make money easy. It heats from city electric light current —*has automatic heat control*—no danger of fire or explosions.

Will mend any style or size of tire—both casing and inner tube. Handles 12 casings and 200 tubes a day. Anybody can operate it, and turn out perfect work. Price $65.00 complete —Subject to Trade Discount.

Write at once for catalog of our complete line of Shaler Vulcanizers, Steam or Electric for Repair Shops and quick selling models for motorists.

C. A. SHALER CO., 2203 Fourth St., Waupun, Wis.

SHALER Electric Shop Vulcanizer



What 15c will bring You from the Nation's Capital

Washington, the home of the Pathfinder, is the nerve center of civilization; history is being made at this world capital. The Pathfinder's illustrated weekly review gives you a clear, impartial and correct diagnosis of public affairs during these strenuous, epoch-making days.

The little matter of **15c** in stamps or coin will bring you the Pathfinder **13** weeks on trial. The Pathfinder is an illustrated weekly, published at the Nation's center, for the Nation; a paper that prints all the news of the world and tells the truth and only the truth; now in its **26th** year. This paper fills the bill without emptying the purse; it costs but **$1** a year. If you want to keep posted on what is going on in the world, at the least expense of time or money, this is your means. If you want a paper in your home which is sincere, reliable, entertaining, wholesome, the Pathfinder is yours. If you would appreciate a paper which puts everything clearly, fairly, briefly—here it is. Send **15c** to show that you might like such a paper, and we will send the Pathfinder on probation **13** weeks. The 15c does not repay us, but we are glad to invest in new friends. **The Pathfinder, Box 576, Washington, D.C.**

MY INVENTIONS.

(*Continued from page* 905)

the professors had written him to the effect that unless he took me away from the Institution I would be killed thru overwork. Thereafter I devoted myself chiefly to physics, mechanics and mathematical studies, spending the hours of leisure in the libraries. I had a veritable mania for finishing whatever I began, which often got me into difficulties. On one occasion I started to read the works of Voltaire when I learned, to my dismay, that there were close on one hundred large volumes in small print which that monster had written while drinking seventy-two cups of black coffee per diem. It had to be done, but when I laid aside the last book I was very glad, and said, "Never more!"

My first year's showing had won me the appreciation and friendship of several professors. Among these were Prof. Rogner, who was teaching arithmetical subjects and geometry; Prof. Poeschl, who held the chair of theoretical and experimental physics, and Dr. Allé, who taught integral calculus and specialized in differential equations. This scientist was the most brilliant lecturer to whom I ever listened. He took a special interest in my progress and would frequently remain for an hour or two in the lecture room, giving me problems to solve, in which I delighted. To him I explained a flying machine I had conceived, not an illusionary invention, but one based on sound, scientific principles, which has become realizable thru my turbine and will soon be given to the world. Both Professors Rogner and Poeschl were curious men. The former had peculiar ways of expressing himself and whenever he did so there was a riot, followed by a long and embarrassing pause. Prof. Poeschl was a methodical and thoroly grounded German. He had enormous feet and hands like the paws of a bear, but all of his experiments were skillfully performed with clock-like precision and without a miss.

It was in the second year of my studies that we received a Gramme dynamo from Paris, having the horseshoe form of a laminated field magnet, and a wire-wound armature with a commutator. It was connected up and various effects of the currents were shown. While Prof. Poeschl was making demonstrations, running the machine as a motor, the brushes gave trouble, sparking badly, and I observed that it might be possible to operate a motor without these appliances. But he declared that it could not be done and did me the honor of delivering a lecture on the subject, at the conclusion of which he remarked: "Mr. Tesla may accomplish great things, but he certainly never will do this. It would be equivalent to converting a steadily pulling force, like that of gravity, into a rotary effort. It is a perpetual motion scheme, an impossible idea." But instinct is something which transcends knowledge. We have, undoubtedly, certain finer fibers that enable us to perceive truths when logical deduction, or any other willful effort of the brain, is futile. For a time I wavered, imprest by the professor's authority, but soon became convinced I was right and undertook the task with all the fire and boundless confidence of youth.

I started by first picturing in my mind a direct-current machine, running it and following the changing flow of the currents in the armature. Then I would imagine an alternator and investigate the processes taking place in a similar manner. Next I would visualize systems comprising motors and generators and operate them in various ways. The images I saw were to me perfectly real and tangible. All my remaining term in Gratz was past in intense but fruitless efforts of this kind, and I almost came to the conclusion that the problem was insolvable. In 1880 I went to Prague, Bohemia, carrying out my father's wish to complete my education at the University there. It was in that city that I made a decided advance, which consisted in detaching the commutator from the machine and studying the phenomena in this new aspect, but still without result. In the year following there was a sudden change in my views of life. I realized that my parents had been making too great sacrifices on my account and resolved to relieve them of the burden. The wave of the American telephone had just reached the European continent and the system was to be installed in Budapest, Hungary. It appeared an ideal opportunity, all the more as a friend of our family was at the head of the enterprise. It was here that I suffered the complete breakdown of the nerves to which I have referred. What I experienced during the period of that illness surpasses all belief. My sight and hearing were always extraordinary. I could clearly discern objects in the distance when others saw no trace of them. Several times in my boyhood I saved the houses of our neighbors from fire by hearing the faint crackling sounds which did not disturb their sleep, and calling for help.

In 1899, when I was past forty and carrying on my experiments in Colorado, I could hear very distinctly thunderclaps at a distance of 550 miles. The limit of audition for my young assistants was scarcely more than 150 miles. My ear was thus over thirteen times more sensitive. Yet at that time I was, so to speak, stone deaf in comparison with the acuteness of my hearing while under the nervous strain. In Budapest I could hear the ticking of a watch with three rooms between me and the time-piece. A fly alighting on a table in the room would cause a dull thud in my ear. A carriage passing at a distance of a few miles fairly shook my whole body. The whistle of a locomotive twenty or thirty miles away made the bench or chair on which I sat vibrate so strongly that the pain was unbearable. The ground under my feet trembled continuously. I had to support my bed on rubber cushions to get any rest at all. The roaring noises from near and far often produced the effect of spoken words which would have frightened me had I not been able to resolve them into their accidental components. The sun's rays, when periodically intercepted, would cause blows of such force on my brain that they would stun me. I had to summon all my will power to pass under a bridge or other structure as I experienced a crushing pressure on the skull. In the dark I had the sense of a bat and could detect the presence of an object at a distance of twelve feet by a peculiar creepy sensation on the forehead. My pulse varied from a few to two hundred and sixty beats and all the tissues of the body with twitchings and tremors which was perhaps the hardest to bear. A renowned physician who gave me daily large doses of Bromid of Potassium pronounced my malady unique and incurable. It is my eternal regret that I was not under the observation of experts in physiology and psychology at that time. I clung desperately to life, but never expected to recover. Can anyone believe that so hopeless a physical wreck could ever be transformed into a man of astonishing strength and tenacity, able to work thirty-eight years almost without a day's interruption, and find himself still strong and fresh in body and mind? Such is my case. A powerful desire to live and to continue the work, and the assistance of a devoted friend and athlete accomplished the wonder. My health returned and with it the vigor of mind. In attacking the problem again I almost regretted that the struggle was soon to end. I had so much energy to spare. When I undertook the task it was not with a resolve such as men often make. With me it was a sacred vow, a question of life and death. I knew that I would perish if I failed. Now I felt that the battle

(*Continued on page* 909)

HIGH SCHOOL COURSE IN TWO YEARS

Are you one of the 98% who didn't finish High School? If so you are **badly handicapped.** Without this training you are barred from a successful business career, from the leading professions, from well-paid civil service jobs, from teaching and college entrance, in fact from all worthwhile positions.

GET THIS TRAINING NOW! You don't want to be handicapped nor do you have to be. Let the American School give you the training you missed. Our High School Course covers every subject taught in a resident school. It will broaden your knowledge, make you keen, alert and capable and fit you to earn a higher salary. You can complete the entire course in two years.

TAKE 10 LESSONS AT OUR EXPENSE

Test this Course at our expense. Take ten full examinations, then if you don't feel satisfied **you are not out one cent.** Training alone will make you master of your work, able to think and act for yourself, and competent enough to secure and hold the position you want. Whether you lack High School training or specialized instruction NOW is the time to get it.

BIG DEMAND FOR SKILLED WORKERS

The demand was never greater for skilled workers in every trade and profession. The pay was never higher—the opportunities never greater. Train and get into the game for all it is worth. **We guarantee satisfaction.** You do not risk one cent. Check and mail Coupon NOW. We will promptly send you full details and Free Bulletin.

AMERICAN SCHOOL OF CORRESPONDENCE
Dept. H-7444 Chicago, Illinois

TRAINING THE KEY TO SUCCESS

Tell me how I can fit myself for the position marked X:

.....High School Graduate	.....Shop Superintendent
.....Electrical Engineer	.....Lawyer
.....Telephone Engineer	.....Business Manager
.....Architect	.....Auditor
.....Draftsman	.....Certified Public Accountant
.....Building Contractor	.....Stenographer
.....Structural Engineer	.....Bookkeeper
.....Mechanical Engineer	.....Fire Insurance Adjuster
.....Civil Engineer	.....Sanitary Engineer
.....Steam Engineer	.....Automobile Engineer

Name .....

Address.....

GO INTO MOVING PICTURE BUSINESS

Small Capital Starts You

Our Catalog FREE. Show you how to earn $25.00 to $50.00 per day

on our easy payment plan. Begin now and get your share. We sell everything. Write today.

Atlas Moving Picture Co.
Dept. 49 538 S. Dearborn St., Chicago



The Purpose of This Analog Is to Portray, As Faithfully As Possible, the Phenomena of Tesla's Rotating Magnetic Field So As to Make Them Easily Understandable to the Average Reader. The Two Alternating Fluxes Are Represented By Streams of Water Having the Same Relation As to Phase, Amplitude and Direction. The Magnetic Polarity of the Rotor Is Imitated By the Employment of a Body So Shaped As to Behave, With Respect to the Streams, Exactly As the Rotor With Respect to the Poles. Moreover, the Corresponding Rotating and Stationary Parts Are Given a Similar Appearance and Are Disposed In Like Manner. To Make the Analog Complete, It May Further Be Assumed That the Liquid Is Compressible So That There Will Be a Phase Displacement Between Pressure and Flow As That Existing Between Electro-Motive Force and Current.

MY INVENTIONS.

(*Continued from page 907*)

was won. Back in the deep recesses of the brain was the solution, but I could not yet give it outward expression. One afternoon, which is ever present in my recollection, I was enjoying a walk with my friend in the City Park and reciting poetry. At that age I knew entire books by heart, word for word. One of these was Göethe's "Faust." The sun was just setting and reminded me of the glorious passage:

"Sie rückt und weicht, der Tag ist überlebt,
Dort eilt sie hin und fördert neues Leben.
Oh, dass kein Flügel mich vom Boden hebt
*Ihr nach und immer nach zu streben!"**

* * * * * * *

Ein schöner Traum indessen sie entweicht,
Ach, zu des Geistes Flügeln wird so leicht
Kein körperlicher Flügel sich gesellen!"†

As I uttered these inspiring words the idea came like a flash of lightning and in an instant the truth was revealed. I drew with a stick on the sand the diagrams shown six years later in my address before the American Institute of Electrical Engineers, and my companion understood them perfectly. The images I saw were wonderfully sharp and clear and had the solidity of metal and stone, so much so that I told him: "See my motor here; watch me reverse it." I cannot begin to describe my emotions. Pygmalion seeing his statue come to life could not have been more deeply moved. A thousand secrets of nature which I might have stumbled upon accidentally I would have given for that one which I had wrested from her against all odds and at the peril of my existence.

* "The glow retreats, done is the day of toil;
It yonder hastes, new fields of life exploring;
Ah, that no wing can lift me from the soil,
Upon its track to follow, follow soaring!"

† A glorious dream! though now the glories fade.
Alas! the wings that lift the mind no aid
Of wings to lift the body can bequeath me."

TESLA ON HIGH FREQUENCY GENERATORS.

Editor, ELECTRICAL EXPERIMENTER:

It is to be regretted that a letter addrest to me by Mr. J. Harris Rogers, in your care, was published in the march number of the ELECTRICAL EXPERIMENTER, altho the concurrence of our views in some wireless features might have made this desirable to so wide-awake and enterprising a periodical as yours.

Mr. Rogers seems to be a very appreciative gentleman and nothing would be farther from my thoughts than to detract anything from his merit, but in a separate contribution, which I expect to prepare for your next issue, I shall express myself on this subject without prejudice and in the interest of truth. However, the article by your Mr. H. Winfield Secor on "America's Greatest War Invention—The Rogers Underground Wireless" contains a reference to "a novel and original high frequency generator" of Mr. Rogers' invention. May I not —to use the President's elegant expression —call attention to the fact that this device was described by me years ago, as will be evident from the following excerpt of a communication which appeared in the *Electrical Review* of March 15, 1899. In speaking of circuit controllers, I said: "I may mention here, based on a different principle, which is incomparably more effective, more efficient, and also simpler on the whole. It comprises a fine stream of conducting fluid which is made to issue, with any desired speed, from an orifice connected with one pole of a generator, thru the primary of the induction coil, against the other terminal of the generator placed at a small distance. This device gives discharges of a remarkable suddenness, and the frequency may be

(*Continued on page 914*)

Foremen and Superintendents $1800 to $5000 Yearly

Office Manager or Auditor $1800 to $5000 Yearly



Engineers (all kinds) $2000 to $5000 Yearly

Learn to Fill Bigger Shoes

NO matter what kind of work you are doing now, a set of these great home study books will quickly fit you for a bigger and better paying job. We will send any set you select for one week's FREE examination, and if you want to keep them you pay only the special reduced price—at the rate of 50 cents a week. This is your opportunity to make more money—grasp it NOW. Use these books and a little spare time and LEARN TO FILL BIGGER SHOES.

Carpentry and Contracting
Five volumes, 2138 pages and more than 400 illustrations. Prepares for Contractor, Building Superintendent and Carpenter Foreman. Regular price, $25.00. Special price, $17.80.

Civil Engineering
Nine volumes, 3900 pages and 3000 illustrations, plates and diagrams. Prepares for Civil or Structural Engineer, Transitman, Estimator, Designer or Chief Draftsman. Regular price, $45.00. Special price, $29.80.

Telephony and Telegraphy
Four volumes, 1728 pages and 2000 illustrations, plates and diagrams. Prepares for Telephone Engineer, Wire Chief, Exchange Manager, Trouble Man or Telegrapher. Regular price, $20.00. Special price, $12.80.

Steam and Gas Engineering
Seven volumes, 3300 pages and 2500 illustrations, plates, diagrams, etc. Prepares for Stationary, Marine or Locomotive Engineer or Fireman. Regular price, $35.00. Special price, $21.80.

Law and Practice
(with Reading Course in 25 bound pamphlets). Thirteen volumes, 6000 pages and 24 illustrations. Prepares for all Bar Examinations. A wonderful aid to business men. Regular price, $72.00. Special price, $39.80.

Practical Accounting
Four volumes, 1840 pages and 800 illustrations, plates and diagrams. C. P. A. questions and practical problems. Prepares for Accountant, Bookkeeper or Cost Clerk. Regular price, $20.00. Special price, $12.80.

Pay Raisers

These books are written by well known authorities — the top-notchers in each line. They will help you make more money. You can't fail to understand them, because they are written in plain, everyday language. Thousands of photographs, diagrams, charts, etc., help to make difficult points as simple as A-B-C.

See our Free Examination—no money down offer below

Ask Our Experts

With these books goes free of all charge a $12.00 Consulting Membership in the American Technical Society. If any question puzzles you—write us. Our corps of experts and engineers will solve any problem. Ask all the questions you want for a whole year. This service is absolutely FREE.

Automobile Engineering
Five volumes, 2400 pages and 2000 illustrations. Prepares for Garage Foreman, Automobile Mechanic or Chauffeur. Invaluable to car owners. Regular price, $25.00. Special price, $17.80.

Machine Shop Practice
Six volumes, 2300 pages and 2500 illustrations. Prepares for Machine Shop Superintendent or Foreman, Foundryman, Pattern Maker, Tool Designer or Tool Maker. Regular price, $30.00. Special price, $19.80.

Sanitary, Heating and Ventilating Engin'ring
Four volumes, 1454 pages and more than 1400 illustrations, etc. Prepares for Sanitary Engineer, Heating and Ventilating Engineer, Master Plumber or Plumber. Regular price, $20.00. Special price, $13.80.

Mechanical and Architectural Drawing
Four volumes, 1578 pages and more than one thousand illustrations. Prepares for Architectural or Mechanical Draftsman. Regular price, $20.00. Special price, only $13.80.

Electrical Engineering
Seven volumes, 3000 pages and 2600 illustrations, plates and diagrams. Prepares for Electrical Engineer, Power Plant Superintendent, Substation Operator or Electrician. Regular price, $35.00. Special price, $19.80.

Accountancy and Business Management
Ten volumes, 3680 pages and 1987 illustrations, forms, etc. Prepares for Certified Public Accountant, Auditor, Office Manager, Accountant, Credit Man or Bookkeeper. Regular price, $50.00. Special price, $24.80.

DON'T SEND ANY MONEY!

Write the name of the books you want on the coupon and mail it today. We will send the books at once, express collect, and you can use them just as if they were your own for a whole week. If you decide you don't want to keep them, send them back at our expense. If you like the books, as thousands of other men have after examination, just send us $2.00. You can send the balance of the special reduced price the same way—$2.00 each month (50 cents a week).

Start right now and learn to fill bigger shoes. There will be a better job looking for you if you do. Be ready to meet it when it comes. *Send the coupon now.*

American Technical Society, Dept. T3384, Chicago, Ill.

American Technical Society, Dept. T3384, Chicago, Illinois

Please send me set of ——— for 7 days' examination, shipping charges collect. I will examine the books thoroughly and, if satisfied, will send $2 within 7 days and $2 each month until I have paid the special price of ——— If I decide not to keep the books, I will return them by express at your expense. Title not to pass to me until the set is fully paid for.

Name ———

Address ———

Reference ———

SEND THE COUPON NOW

My Inventions

By Nikola Tesla

IV. The Discovery of the Tesla Coil and Transformer

FOR a while I gave myself up entirely to the intense enjoyment of picturing machines and devising new forms. It was a mental state of happiness about as complete as I have ever known in life. Ideas came in an uninterrupted stream and the only difficulty I had was to hold them fast. The pieces of apparatus I conceived were to me absolutely real and tangible in every detail, even to the minutest marks and signs of wear. I delighted in imagining the motors constantly running, for in this way they presented to the mind's eye a more fascinating sight. When natural inclination develops into a passionate desire, one advances towards his goal in seven-league boots. In less than two months I evolved virtually all the types of motors and modifications of the system which are now identified with my name. It was, perhaps, providential that the necessities of existence commanded a temporary halt to this consuming activity of the mind. I came to Budapest prompted by a premature report concerning the telephone enterprise and, as irony of fate willed it, I had to accept a position as draftsman in the Central Telegraph Office of the Hungarian Government at a salary which I deem it my privilege not to disclose! Fortunately, I soon won the interest of the Inspector-in-Chief and was thereafter employed on calculations, designs and estimates in connection with new installations, until the Telephone Exchange was started, when I took charge of the same. The knowledge and practical experience I gained in the course of this work was most valuable and the employment gave me ample opportunities for the exercise of my inventive faculties. I made several improvements in the Central Station apparatus and perfected a telephone repeater or amplifier which was never patented or publicly described but would be creditable to me even today. In recognition of my efficient assistance the organizer of the undertaking, Mr. Puskas, upon disposing of his business in Budapest, offered me a position in Paris which I gladly accepted.



Fig. 1—Tesla Oscillation Transformer (Tesla Coil) Presented by Lord Kelvin Before the British Association in August, 1897. This Small and Compact Instrument, Only 8 Inches High, Developed Two Square Feet of Streamers With Twenty-Five Watts From the 110 Volt D. C. Supply Circuit. The Instrument Contains a Tesla Primary and Secondary, Condenser, and a Circuit Controller.

I never can forget the deep impression that magic city produced on my mind. For several days after my arrival I roamed thru the streets in utter bewilderment of the new spectacle. The attractions were many and irresistible, but, alas, the income was spent as soon as received. When Mr. Puskas asked me how I was getting along in the new sphere, I described the situation accurately in the statement that "the last twenty-nine days of the month are the toughest!" I led a rather strenuous life in what would now be termed "Rooseveltian fashion." Every morning, regardless of weather, I would go from the Boulevard St. Marcel, where I resided, to a bathing house on the Seine, plunge into the water, loop the circuit twenty-seven times and then walk an hour to reach Ivry, where the Company's factory was located. There I would have a woodchopper's breakfast at half-past seven o'clock and then eagerly await the lunch hour, in the meanwhile cracking hard nuts for the Manager of the Works, Mr. Charles Batchellor, who was an intimate friend and assistant of Edison. Here I was thrown in contact with a few Americans who fairly fell in love with me because of my proficiency in—billiards. To these men I explained my invention and one of them, Mr. D. Cunningham, Foreman of the Mechanical Department, offered to form a stock company. The proposal seemed to me comical in the extreme. I did not have the faintest conception of what that meant except that it was an American way of doing things. Nothing came of it, however, and during the next few months I had to travel from one to another place in France and Germany to cure the ills of the power plants. On my return to Paris I submitted to one of the administrators of the Company, Mr. Rau, a plan for improving their dynamos and was given an opportunity. My success was complete and the delighted directors accorded me the privilege of developing automatic regulators which were much desired. Shortly after there was some trouble with the lighting plant which has been installed at the new rail-

Copyright, 1919, by E. P. Co. All rights reserved

Mr. Tesla's articles started in our February issue

road station in Strassburg, Alsace. The wiring was defective and on the occasion of the opening ceremonies a large part of a wall was blown out thru a short-circuit right in the presence of old Emperor William I. The German Government refused to take the plant and the French Company was facing a serious loss. On account of my knowledge of the German language and past experience, I was entrusted with the difficult task of straightening out matters and early in 1883 I went to Strassburg on that mission.

The First Induction Motor Is Built.

Some of the incidents in that city have left an indelible record on my memory. By a curious coincidence, a number of men who subsequently achieved fame, lived there about that time. In later life I used to say, "There were bacteria of greatness in that old town. Others caught the disease but I escaped!" The practical work, correspondence, and conferences with officials kept me preoccupied day and night, but as soon as I was able to manage I undertook the construction of a simple motor in a mechanical shop opposite the railroad station, having brought with me from Paris some material for that purpose. The consummation of the experiment was, however, delayed until the summer of that year when I finally had the satisfaction of *seeing rotation effected by alternating currents of different phase, and without sliding contacts or commutator,* as I had conceived a year before. It was an exquisite pleasure but not to compare with the delirium of joy following the first revelation.

Among my new friends was the former Mayor of the city, Mr. Bauzin, whom I had already in a measure acquainted with this and other inventions of mine and whose support I endeavored to enlist. He was sincerely devoted to me and put my project before several wealthy persons but, to my mortification, found no response. He wanted to help me in every possible way and the approach of the first of July, 1919, happens to remind me of a form of "assistance" I received from that charming man, which was not financial but none the less appreciated. In 1870, when the Germans invaded the country, Mr. Bauzin had buried a good sized allotment of St. Estèphe of 1801 and he came to the conclusion that he knew no worthier person than myself to consume that precious beverage. This, I may say, is one of the unforgettable incidents to which I have referred. My friend urged me to return to Paris as soon as possible and seek support there. This I was anxious to do but my work and negotiations were protracted owing to all sorts of petty obstacles I encountered so that at times the situation seemed hopeless.

Fig. 2—This Illustrates Tests With Spark Discharges From a Ball of Forty Centimeters Radius in Tesla's Wireless Plant Erected at Colorado Springs in 1899. The Ball Is Connected to the Free End of a Grounded Resonant Circuit Seventeen Meters in Diameter. The Disruptive Potential of a Ball, Is, According to Tesla, in Volts Approximatelly V = 75,400 r (r Being in Centimeters), That Is, in This Case 75,400 x 40 = 3,016,000 Volts. The Gigantic Tesla Coil Which Produced These Bolts of Thor Was Capable of Furnishing a Current of 1,100 Amperes in the High Tension Secondary. The Primary Coil Had a Diameter of 51 Feet! This Tesla Coil Produced Discharges Which Were the Nearest Approach to Lightning Ever Made by Man.

THE proverbial trials and tribulations known to every inventor were not spared Tesla, the world's greatest inventor of all times. In this article we see him, arrived at young manhood, struggling along in a cold world. Already his fame has spread far and wide and his genius is recognized. But converting genius and fame into dollars and cents is quite a different matter, and the world is full of unappreciative and unscrupulous men. Tesla, the idealist, cared little for money and thus was promptly taken advantage of. But let Tesla himself tell you in his own inimitable style. It is a wonderful story.

In this month's installment Tesla also tells us how he made one of his most important as well as sensational discoveries—the Tesla Coil. Few inventions have caused such a sensation as this one which culminated in the only man-made lightning ever produced. The Tesla coil has so many uses and has been built in so many styles that it would take a catalog to list them all. From the spectacular high frequency stunts on the stage down to the "violet" ray machine in your home; all are Tesla coils in one form or another.

Wireless without the Tesla Coil would not be possible today. Without an oscillation transformer, spark gap and condenser—which is a Tesla Coil—the sending station would be crippled.

But it is for industrial purposes where the Tesla Coil will shine brightest in the future. The production of Ozone, the extraction of Nitrogen from the air in huge quantities—all are children of Tesla's fertile brain. His coil is the key to them all.

EDITOR.

German "Efficiency".

Just to give an idea of German thoroness and "efficiency," I may mention here a rather funny experience. An incandescent lamp of 16 c.p. was to be placed in a hallway and upon selecting the proper location I ordered the *monteur* to run the wires. After working for a while he concluded that the engineer had to be consulted and this was done. The latter made several objections but ultimately agreed that the lamp should be placed two inches from the spot I had assigned, whereupon the work proceeded. Then the engineer became worried and told me that Inspector Averdeck should be notified. That important person called, investigated, debated, and decided that the lamp should be shifted back two inches, which was the place I had marked. It was not long, however, before Averdeck got cold feet himself and advised me that he had informed *Ober-Inspector* Hieronimus of the matter and that I should await his decision. It was several days before the *Ober-Inspector* was able to free himself of other pressing duties but at last he arrived and a two-hour debate followed, when he decided to move the lamp two inches farther. My hopes that this was the final act were shattered when the *Ober-Inspector* returned and said to me: *"Regierungsrath* Funke is so particular that I would not dare to give an order for placing this lamp without his explicit approval." Accordingly arrangements for a visit from that great man were made. We started cleaning up and polishing early in the morning. Everybody brushed up, I put on my gloves and when Funke came with his retinue he was ceremoniously received. After two hours' deliberation he suddenly exclaimed: "I must be going," and pointing to a place on the ceiling, he ordered me to put the

(*Continued on page* 64)

Pour Red, White and Blue from a Glass of Water

You can mystify your friends with puzzling chemical tricks; write secret letters with invisible ink; make your own magic writing paper, and your own blue ink or ink powder. Write with water and have it turn blue. You can pour seemingly plain water into three glasses and have it turn red in one, white in another and blue in the third. Send twenty-five cents in stamps and get your outfit by mail, postpaid. If you send right away, we will enter your name to receive a copy of "The Chemcraft Chemist." It's an interesting magazine for boys. Regular "CHEMCRAFT" Outfits at $1.50, $3.00 and $5.00. **"Chemcraft" Junior 25c.**

THE PORTER CHEMICAL CO., Arcade Building Hagerstown, Md. Postp'd

Build Your Own PHONOGRAPH,

It's Easy With Our Help

A few hours interesting work saves many dollars and gives you a machine exactly to suit your ideals. We furnish motors, tone arms, case material, blue prints and full instructions. Plays any record. You can make fine profit building phonographs for your friends.

Write Today for Our Free Blue Print Offer. Agents wanted for our ready built Choraleons.

SAVE OVER HALF

Choraleon Phonograph Co.
705 Monger Bldg., Elkhart, Ind.



ZIP-ZIP Patented Sept. 3rd, 1918

The Greatest 50 Ct. Article on the Market. Shipped right from the factory the same day we receive your order. The Prong is made of beautiful metal; never break or wear out; scientifically made and best workmanship. The rubbers are elastic and lasting, with plenty of pep and force. Zip-Zip, complete, only **50c** prepaid. Be sure the name Zip-Zip and our address appear on the article you buy. Order from us or any Sporting Goods Store in your city. Send Stamps, Coin or Money Order.

AUTOMATIC RUBBER CO.
COLUMBIA, S. C.

$50 PAID for ONE DRAWING

Illustrators—Cartoonists—Commercial Artists make big money. Learn N.W. at home in spare time by our new instruction method. Handsome booklet free explains everything. Write for it today. Get our Special Free Outfit offer.

Washington School of Art, Inc.
1407 H St., N.W. Washington, D.C.

NATIONAL TRADE DENTAL SCHOOL

506 S. Wabash Ave., Chicago, Ill.

LEARN MECHANICAL DENTISTRY—DEMAND UNLIMITED

A paying professional trade: You will be a trained dental mechanic and receive our diploma when competent. Students given advantage of thoroughly up to date laboratory, and services of graduate Dental Surgeons on practical cases. No effort spared to place graduates advantageously. No age limit. Day or Evening. Individual instruction. No educational requirements. No book or home study. Easy terms. Highest references. Especially attractive proposition to those who write at once for catalog H.

You Can *RENT* This Phongraph

on our new plan! $10 puts this **Young's Superior Phonograph** in your home on 30 Days' Trial! Plays all makes of disc records. Cabinet size, 47 ins. high. *Rental applies on purchase.* $125 Value for $62.50. Write for details of greatest phonograph bargain ever offered. Offer Limited. Write Today.

YOUNG'S SUPERIOR PHONOGRAPH
62 W. Madison St. Dept. U Chicago, Ill.

GO INTO MOVING PICTURE BUSINESS

Small Capital Starts You

Our Catalog FREE. Shows you how to earn $25.00 to $50.00 per day

on our easy payment plan. Begin now and get your share. We sell everything. Write today.

Atlas Moving Picture Co.
Dept. 49 538 S. Dearborn St., Chicago

You can be quickly cured, if you

STAMMER

Send 10 cents coin or stamps for 70-page book on Stammering and Stuttering, "Its Cause and Cure." It tells how I cured myself after stammering for 20 years.

Benjamin N. Bogue, 754 Bogue Building, Indianapolis

A WONDERFUL NEW INVENTION The Q. S. Target Pistol shoots shot 100 feet, wooden arrows 20 to 30 feet, with surprising power and accuracy. Boys go wild over it, grown people find it most interesting. Send 10c. (silver) for sample, terms, etc. Our Q. S. Special, 25c., for the older boy and grown people. Send 3c. extra for postage and packing on single order. (Agents wanted.)



THE Q. S. NOVELTY PISTOL CO., - - Delanson, N. Y.



EARN MONEY

Stamping Names on Key Tags. Either sex. Spare time. Some make $50. Send 25c for Tag with your name on and instructions. Returned if required. Exp. Key Tag Co., Cohoes, N. Y.

My Inventions

(*Continued from page 17*)

lamp there. It was the exact spot which I had originally chosen.

So it went day after day with variations, but I was determined to achieve at whatever cost and in the end my efforts were rewarded. By the spring of 1884 all the differences were adjusted, the plant formally accepted, and I returned to Paris with pleasing anticipations. One of the administrators had promised me a liberal compensation in case I succeeded, as well as a fair consideration of the improvements I had made in their dynamos and I hoped to realize a substantial sum. There were three administrators whom I shall designate as A, B and C for convenience. When I called on A *he* told me that B had the say. This gentleman thought that only C could decide and the latter was quite sure that A alone had the power to act. After several laps of this *circulus viciosus*, it dawned upon me that my reward was a castle in Spain. The utter failure of my attempts to raise capital for development was another disappointment and when Mr. Batchellor prest me to go to America with a view of redesigning the Edison machines, I determined to try my fortunes in the Land of Golden Promise. But the chance was nearly mist. I liquefied my modest assets, secured accommodations and found myself at the railroad station as the train was pulling out. At that moment I discovered that my money and tickets were gone. What to do was the question. Hercules had plenty of time to deliberate but I had to decide while running alongside the train with opposite feelings surging in my brain like condenser oscillations. Resolve, helped by dexterity, won out in the nick of time and upon passing thru the usual experiences, as trivial as unpleasant, I managed to embark for New York with the remnants of my belongings, some poems and articles I had written, and a package of calculations relating to solutions of an unsolvable integral and to my flying machine. During the voyage I sat most of the time at the stern of the ship watching for an opportunity to save somebody from a watery grave, without the slightest thought of danger. Later when I had absorbed some of the practical American sense I shivered at the recollection and marvelled at my former folly.

Tesla in America

I wish that I could put in words my first impressions of this country In the Arabian Tales I read how genii transported people into a land of dreams to live thru delightful adventures. My case was just the reverse. The genii had carried me from a world of dreams into one of realities. What I had left was beautiful, artistic and fascinating in every way; what I saw here was machined, rough and unattractive. A burly policeman was twirling his stick which looked to me as big as a log. I approached him politely with the request to direct me. "Six blocks down, then to the left," he said, with murder in his eyes. "Is this America?" I asked myself in painful surprise. "It is a century behind Europe in civilization." When I went abroad in 1889—five years having elapsed since my arrival here—I became convinced that *it was more than one hundred years AHEAD of Europe* and nothing has happened to this day to change my opinion.

Tesla Meets Edison

The meeting with Edison was a memorable event in my life. I was amazed at this wonderful man who, without early advantages and scientific training, had accomplished so much. I had studied a dozen languages, delved in literature and art, and had spent my best years in libraries reading all sorts of stuff that fell into my hands, from Newton's *"Principia"* to the novels of Paul de Kock, and felt that most of my life had been squandered. But it did not take long before I recognized that it was the best thing I could have done. Within a few weeks I had won Edison's confidence and it came about in this way.

The S. S. *Oregon*, the fastest passenger steamer at that time, had both of its lighting machines disabled and its sailing was delayed. As the superstructure had been built after their installation it was impossible to remove them from the hold. The predicament was a serious one and Edison was much annoyed. In the evening I took the necessary instruments with me and went aboard the vessel where I stayed for the night. The dynamos were in bad condition, having several short-circuits and breaks, but with the assistance of the crew I succeeded in putting them in good shape. At five o'clock in the morning, when passing along Fifth Avenue on my way to the shop, I met Edison with Batchellor and a few others as they were returning home to retire. "Here is our Parisian running around at night," he said. When I told him that I was coming from the *Oregon* and had repaired both machines, he looked at me in silence and walked away without another word. But when he had gone some distance I heard him remark: "Batchellor, this is a d—n good man," and from that time on I had full freedom in directing the work. For nearly a year my regular hours were from 10.30 A. M. until 5 o'clock the next

MY NEW BOOK

"Muscular Development"

will tell you how to get a wonderful muscular development like mine, perfect health, abundance of vitality and great strength as I have.

EARLE E. LIEDERMAN
Why not look as healthy and be as strong as I am?

The results of my system are shown on my own person and that is recommendation enough. To give every one the opportunity to profit by what I have learned, I will mail my book, for a limited time only, on receipt of

10c Stamps or Coin

This wonderful book will help you. It is profusely illustrated and contains pictures of many of the world's strongest men whom I have trained. Send for it **to-day.** Right now, while it is on your mind.

EARLE LIEDERMAN, Dept. 208, 203 Broadway, N. Y.



Mechanics' Utility MOTOR GRINDER

A Time-Saver and Money-Maker For Shop, Factory, Garage or Home

Attach to any electric light socket and you have a power unit which will do grinding of all descriptions as well as drive small machinery. Can be furnished with chuck end buff for buffing.

Type B—Complete with 6 in. by one-half in. Emery Wheel, **$15.50.** Order today.

RACINE UNIVERSAL MOTOR CO.
53 W. Jackson Blvd. Chicago, Ill.

FRENCH WIRELESS

FROG made of steel with large clicker inside, used to learn telegraphy. **10c**
GREAT FUN. SEND YOUR FRIENDS WIRELESS MESSAGES. SENT complete with code, and to make a big bundle we will send a Ford joke book, Parlor games, etc., all for 10c.

Dept. 72, American Toy Co., Lowell, Mass., U.S.A.

INDEX TO ELECTRICAL EXPERIMENTER

FOR VOLUME 1, 2, 3, 4, 5

Price 15c. Postpaid

EXPERIMENTER PUBLISHING CO.
Book Dept. 231 Fulton St., N.Y.

morning without a day's exception. Edison said to me: "I have had many hard-working assistants but you take the cake." During this period I designed twenty-four different types of standard machines with short cores and of uniform pattern which replaced the old ones. The Manager had promised me fifty thousand dollars on the completion of this task but it turned out to be a practical joke. This gave me a painful shock and I resigned my position.

Immediately thereafter some people approached me with the proposal of forming an arc light company under my name, to which I agreed. Here finally was an opportunity to develop the motor, but when I broached the subject to my new associates they said: "No, we want the arc lamp. We don't care for this alternating current of yours." In 1886 my system of arc lighting was perfected and adopted for factory and municipal lighting, and I was free, but with no other possession than a beautifully engraved certificate of stock of hypothetical value. Then followed a period of struggle in the new medium for which I was not fitted, but the reward came in the end and in April, 1887, the Tesla Electric Company was organized, providing a laboratory and facilities. The motors I built there were exactly as I had imagined them. I made no attempt to improve the design, but merely reproduced the pictures as they appeared to my vision and the operation was always as I expected.

In the early part of 1888 an arrangement was made with the Westinghouse Company for the manufacture of the motors on a large scale. But great difficulties had still to be overcome. My system was based on the use of low frequency currents and the Westinghouse experts had adopted 133 cycles with the object of securing advantages in the transformation. They did not want to depart from their standard forms of apparatus and my efforts had to be concentrated upon adapting the motor to these conditions. Another necessity was to produce a motor capable of running efficiently at this frequency on two wires which was not easy of accomplishment.

At the close of 1889, however, my services in Pittsburg being no longer essential, I returned to New York and resumed experimental work in a laboratory on Grand Street, where I began immediately the design of high frequency machines. The problems of construction in this unexplored field were novel and quite peculiar and I encountered many difficulties. I rejected the inductor type, fearing that it might not yield perfect sine waves which were so important to resonant action. Had it not been for this I could have saved myself a great deal of labor. Another discouraging feature of the high frequency alternator seemed to be the inconstancy of speed which threatened to impose serious limitations to its use. I had already noted in my demonstrations before the American Institution of Electrical Engineers that several times the tune was lost, necessitating readjustment, and did not yet foresee, what I discovered long afterwards, a means of operating a machine of this kind at a speed constant to such a degree as not to vary more than a small fraction of one revolution between the extremes of load.

The Invention of the Tesla Coil

From many other considerations it appeared desirable to invent a simpler device for the production of electric oscillations. In 1856 Lord Kelvin had exposed the theory of the condenser discharge, but no practical application of that important knowledge was made. I saw the possibilities and undertook the development of induction apparatus on this principle. My progress was so rapid as to enable me to exhibit at my lecture in 1891 a coil giving sparks of *five inches*. On that occasion I frankly told the

(*Continued on page* 89)

Don't Commit A Crime Against The Woman You Love

LIONEL STRONGFORT

"Dr. Sargent of Harvard, declared that Strongfort is unquestionably the finest specimen of physical development ever seen."

NO AMOUNT of love will ever atone for the crime you will commit, if you make some pure, trusting young girl your wife when you are UNFIT to assume the duties and responsibilities of a husband and a father. Her whole future life, her body and soul, will be in YOUR keeping; no one will be able to help her if YOU prove faithless to her trust in you. *Don't put the matter aside*, you can't get away from it; you can't make any girl happy, if you are weak, impotent, sickly; grouchy with dyspepsia or biliousness, poisoned by constipation, or suffering from any other devitalizing ailment. Stop and think, right now, for HER sake, if not for your own. What CAN her marriage to you bring her, but lifelong regret and sorrow, if you are only an apology for a man, with your muscles flabby, your blood like water and your brain woozy as a result of your condition.

She Thinks You Are a Man

She trusts, admires and loves what she THINKS you are—a real MAN, mentally, morally and physically, whom she can *respect* as well as love. She believes you to be a man who can look any other man in the eye and hold your own with him; who is able to protect her under any circumstances; who can make his way in the world and give her the comforts she has a right to expect from her husband; and finally who will ultimately make her the mother of healthy, happy children, a blessing to you both. Think of the kind of children you will make her the mother of if you are one of the great UNFIT! Think of the weak, ailing, rickety, defective boys and girls such men bring into the world—pitiable little creatures, with no chance in life, living reproaches to the father who begot them. Don't close your eyes to these things. They are *facts;* facts thoroughly understood by every breeder of dogs, cattle and horses; facts recognized by the legislators of several states, who would make it a LEGAL, as well as a MORAL, crime to marry when unfit.

Make Yourself 100 Per Cent Fit

Put your past behind you. What if you have led a gay life and sowed a big crop of wild oats? Start NOW to root them out. What if you have burned the candle at both ends and feel now like a human wreck, with your strength of body and mind dissipated and your vitality ebbing away? All the more reason why you should begin *now, TODAY*, to stop that steady loss, build up your strength again, regain your lost vitality and make a manly, red-blooded man of yourself. It's the ONLY thing to do—the only way to have any more happiness in life—the only way to keep from slipping down into the scrap heap of the hopelessly down-and-out—*and you can do it, if you go about it the right way.*

Strongfort Will Show You How

No matter what your work or business or occupation, you can build yourself up in my way without interfering with it in the least. I'll help you strengthen your heart, lungs, stomach and every other vital organ; I'll help you free yourself from dyspepsia, biliousness, constipation, catarrh or other chronic ailments; I'll help you steady your nerves and clear your brain and send the rich, red blood of life and vital energy coursing through your arteries again, so that you will be THE man your wife believes and expects you to be. I haven't any patented dope or bottled physic to sell you. I haven't any iron-bound, muscle-fatiguing, tiresome routine of exercises or straitlaced, ascetic living to recommend. I am a Builder Up of Men, and I build them up in Nature's way—the way that was successful in making me the strongest man in the world; the way that is succeeding with my pupils, thousands of them, in every country of the civilized world.

Don't Be Discouraged

Never mind how low down you have fallen; I don't care a rap what your present condition is or what brought you to it—*I know I can improve you* 100 per cent in a few short months. I am doing it every day for men who had given up all hope; bringing back their health and strength; making them respected members of society again; filling them with life, and ambition, pep and ginger, and enabling them to make a success in the world. I can do for *you* what I have done and am doing for others, and I WILL DO IT, if you will mark NOW, on the coupon below the trouble or troubles that are affecting you, or the points you are most interested in, and MAIL IT TO ME TODAY. My free book, "**Promotion and Conservation of Health, Strength and Mental Energy,**" will show you the quick, easy, sensible, *manly* way out of your difficulties; the way that has brought renewed hope and confidence and joy of living to thousands of other men; it will show you how to make yourself FIT to live; FIT to marry; or, if you are married already, it will help you become the father of healthy, happy, laughing children who will be a joy to you and your wife as long as you live. YOU WANT THAT BOOK.

Do Your Part Now

Do YOUR part, and I'll do MINE—I guarantee it. Fill out and send me the coupon, with three 2c stamps for postage and packing on the free book, "**Promotion and Conservation of Health, Strength and Mental Energy,**" and I'll send you with it, without charge, helpful, *personal* information on the conditions that are troubling you. DON'T DELAY—here's the coupon—Do your part NOW.

LIONEL STRONGFORT

Health and Strength Specialist

883 Strongfort Institute Newark, N. J.

FREE CONSULTATION COUPON

Mr. Lionel Strongfort, Newark N. J.—Please send me your book, "**PROMOTION AND CONSERVATION OF HEALTH, STRENGTH AND MENTAL ENERGY,**" for postage of which I enclose three 2-cent stamps. I have marked (X) before the subject in which I am interested.

..Colds	..Flat Feet	..Heartweakness
..Catarrh	..Stomach Disorders	..Poor Circulation
..Asthma	..Constipation	..Skin Disorders
..Obesity	..Biliousness	..Despondency
..Headache	..Torpid Liver	..Round Shoulders
..Thinness	..Indigestion	..Lung Troubles
..Rupture	..Nervousness	..Increased Height
..Lumbago	..Poor Memory	..Stoop Shoulders
..Neuritis	..Rheumatism	..Muscular Development
..Neuralgia	..Youthful Errors	
..Flat Chest	..Vital Losses	
..Deformity (describe)	..Impotency	
..Insomnia	..Gastritis	
..Short Wind		

(883)

Name .....

Age .....Occupation .....

Street .....

City .....State .....

My Inventions

(*Continued from page 65*)

engineers of a defect involved in the transformation by the new method, namely, the loss in the spark gap. Subsequent investigation showed that no matter what medium is employed, be it air, hydrogen, mercury vapor, oil or a stream of electrons, the efficiency is the same. It is a law very much like that governing the conversion of mechanical energy. We may drop a weight from a certain height vertically down or carry it to the lower level along any devious path, it is immaterial insofar as the amount of work is concerned. Fortunately however, this drawback is not fatal as by proper proportioning of the resonant circuits an *efficiency of* 85 *per cent* is attainable. Since my early announcement of the invention it has come into universal use and wrought a revolution in many departments. But a still greater future awaits it. When in 1900 I obtained powerful discharges of 100 feet and flashed a current around the globe, I was reminded of the first tiny spark I observed in my Grand Street laboratory and was thrilled by sensations akin to those I felt when I discovered the *rotating magnetic field.*



This revolutionary improvement was exhibited and explained by Tesla for the first time in his lecture before the American Institute of Electrical Engineers May 20, 1891. It has made possible to generate automatically damped or undamped oscillations of any desired frequency and, what is equally important, of perfectly constant period. It has been instrumental in many great achievements and its use has become universal. The underlying principle may be briefly stated as follows: A source of electricity is made to charge a condenser and when the difference of potential at the terminals of the latter has reached a predetermined value, an air-gap is bridged, permitting the accumulated energy to be discharged through a circuit under resonant conditions, this resulting in a long series of isochronous impulses. These are either directly used or converted to any desired volume or pressure by means of a second circuit inductively linked with the first and tuned to the same. The above diagram is taken from Tesla's lecture before the Franklin Institute and National Electric Light Association in 1893 and shows more elaborate arrangements of circuits, now quite familiar, for the conversion of ordinary direct or alternating currents into high frequency oscillations by this general method. In the mechanical apparatus illustrated, an attempt is made to convey an idea of the electrical operations as closely as practicable. The reciprocating and centrifugal pumps, respectively, represent an alternating and a direct current generator. The water takes the place of the electric fluid. The cylinder with its elastically restrained piston represents the condenser. The inertia of the moving parts corresponds to the self-induction of the electric circuit and the wide ports around the cylinder, through which the fluid can escape, perform the function of the air-gap. The operation of this apparatus will now be readily understood. Suppose first that the water is admitted to the cylinder from the centrifugal pump, this corresponding to the action of a continuous current generator. As the fluid is forced into the cylinder, the piston moves upward until the ports are uncovered, when a great quantity of the fluid rushes out, suddenly reducing the pressure so that the force of the compressed spring asserts itself and sends the piston down, closing the ports, whereupon these operations are repeated in as rapid succession as it may be desired. Each time the system, comprising the piston, rod, weights and adjustable spring, receives a blow, it quivers at its own rate which is determined by the inertia of the moving parts and the pliability of the spring exactly as in the electrical system the period of the circuit is determined by the self-induction and capacity. Under the best conditions the natural period of the elastic system will be the same as that of the primarily impressed oscillations, and then the energy of the movement will be greatest. If, instead of the centrifugal, the reciprocating pump is employed, the operation is the same in principle except that the periodic impulses of the pump impose certain limitations. The best results are again obtained when synchronism is maintained between these and the natural oscillations of the system.



Fig. 3—Scheme of Circuit Connections In Tesla's Oscillation Transformer Shown in Fig. 1. The Secondary Circuit Which Slips Into the Primary Is Omitted.

Typewriter Sensation

FREE TRIAL

Use as You Pay

Only $4.00 a month until the low total price of $53.15 is paid, and the machine is yours.

This is absolutely the most generous typewriter offer ever made. Do not rent a machine when you can pay $4.00 a month and own one. Think of it—Buying a $100.00 machine for $53.15. Cash price, $50.35. Never before has anything like this been attempted.

Standard Visible No. 10 Smith Premier

Perfect machines, Standard size, full 84 character one motion keyboard. The entire line of writing completely visible at all times, has the tabulator, the two-color ribbon, with automatic reverse, the back spacer, ball bearing type bars, ball bearing carriage action, in fact every late style feature and modern operating convenience. **Comes to you with everything complete; tools, cover, operating book and instructions, ribbon, practice paper—nothing extra to buy. You cannot imagine the perfection of this beautiful reconstructed typewriter until you have seen it.** I have sold several thousand of these perfect latest style Model No. 10 machines at this bargain price and every one of these thousands of satisfied customers had this beautiful, strictly up to date machine on five days' free trial before deciding to buy it. I will send it to you F. O. B. Chicago for five days' free trial. It will sell itself, but if you are not satisfied that this is the greatest typewriter you ever saw, you can return it at my expense. You won't want to return it after you try it—you cannot equal this wonderful value anywhere.

You Take No Risk—Put in Your Order *Now*

When the typewriter arrives deposit with the express agent $9.15 and take the machine for five days' trial. If you are convinced that it is the best typewriter you ever saw, keep it and send me $4.00 a month until our bargain price of $53.15 is paid. If you don't want it, return it to the express agent, receive your $9.15 and return the machine to me. I will pay the return express charges. This machine is guaranteed just as if you paid $100.00 for it. It is standard. Over one hundred thousand people own and use these typewriters and think them the best ever manufactured.

The supply at this price is very limited, the price will probably be raised when my next advertisement appears, so don't delay. Fill in the coupon today—mail to me—the typewriter will be shipped promptly. There is no red tape. I employ no solicitors—no collectors—no chattel mortgage. It is simply understood that I retain title to the machine until the full $53.15 is paid. You cannot lose. It is the greatest typewriter opportunity you will ever have. **Do not send me one cent. Get the coupon in the mails today—sure.**

Harry A. Smith, 758, 218 N. Wells St., Chicago

H. A. SMITH, 758, 218 N. Wells St., Chicago, Ill.

Ship me a No. 10 Smith Premier F.O.B. Chicago, as described in this advertisement. I will pay you the $44.00 balance of the special $53.15 purchase price, at the rate of $4.00 per month. The title to remain in you until fully paid for. It is understood that I have five days in which to examine and try the typewriter. If I choose not to keep it I will carefully repack it and return it to the express agent. It is understood that you give the standard guarantee for one year.

Name .....

Address .....

.....

BE A C.P.A. **ACCOUNTANCY** The Highest Paid Profession taught thoroughly in a few months of home study by new system. **FREE BOOK** International Accountants Society Dept. 39E, 2626 S. Mich. Ave. Chicago

My Inventions

By Nikola Tesla

V. The Magnifying Transmitter

AS I review the events of my past life I realize how subtle are the influences that shape our destinies. An incident of my youth may serve to illustrate. One winter's day I managed to climb a steep mountain, in company with other boys. The snow was quite deep and a warm southerly wind made it just suitable for our purpose. We amused ourselves by throwing balls which would roll down a certain distance, gathering more or less snow, and we tried to outdo one another in this exciting sport. Suddenly a ball was seen to go beyond the limit, swelling to enormous proportions until it became as big as a house and plunged thundering into the valley below with a force that made the ground tremble. I looked on spellbound, incapable of understanding what had happened. For weeks afterward the picture of the avalanche was before my eyes and I wondered how anything so small could grow to such an immense size. Ever since that time the magnification of feeble actions fascinated me, and when, years later, I took up the experimental study of mechanical and electrical resonance, I was keenly interested from the very start. Possibly, had it not been for that early powerful impression, I might not have followed up the little spark I obtained with my coil and never developed my best invention, the true history of which I will tell here for the first time.



This Photograph Shows the Famous Tesla Tower Erected at Shoreham, L. I., N. Y. The Tower Was Dismantled at the Outbreak of the War. It Was 187 Feet High. The Spherical Top Was 68 Feet in Diameter.

Note the Huge Size of the Structure by Comparing the Two-story Power Plant in the Rear. The Tower Which Was to be Used by Tesla in His "World Wireless," Was Never Finished. Illustration Opposite Shows It Completed.

Scrapping the World's Engines.

"Lionhunters" have often asked me which of my discoveries I prize most. This depends on the point of view. Not a few technical men, very able in their special departments, but dominated by a pedantic spirit and near-sighted, have asserted that excepting the induction motor I have given to the world little of practical use. This is a grievous mistake. A new idea must not be judged by its immediate results. My alternating system of power transmission came at a psychological moment, as a long-sought answer to pressing industrial questions, and altho considerable resistance had to be overcome and opposing interests reconciled, as usual, the commercial introduction could not be long delayed. Now, compare this situation with that confronting my turbine, for example. One should think that so simple and beautiful an invention, possessing many features of an ideal motor, should be adopted at once and, undoubtedly, it would under similar conditions. But the prospective effect of the rotating field was not to render worthless existing machinery; on the contrary, it was to give it additional value. The system lent itself to new enterprise as well as to improvement of the old. My turbine is an advance of a character entirely different. It is a radical departure in the sense that its success would mean the abandonment of the antiquated types of prime movers on which billions of dollars have been spent. Under such circumstances the progress must needs be slow and perhaps the greatest impediment is encountered in the prejudicial opinions created in the minds of experts by organized opposition. Only the other day I had a disheartening experience when I met my friend and former assistant, Charles F. Scott, now professor of Electrical Engineering at Yale. I had not seen him for a long time and was glad to have an opportunity for a little chat at my office. Our conversation naturally enough drifted on my turbine and I became heated to a high degree. "Scott," I exclaimed, carried away by the vision of a glorious future, "my turbine will scrap all the heat-engines in the world." Scott stroked his chin and looked away thoughtfully, as though making a mental calculation. "That will make quite a pile of scrap," he said, and left without another word!

IMAGINE a man a century ago, bold enough to design and actually build a huge tower with which to transmit the human voice, music, pictures, press news and even power, thru the earth to any distance whatever without wires! He probably would have been hung or burnt at the stake. So when Tesla built his famous tower on Long Island he was a hundred years ahead of his time. And foolish ridicule by our latter day arm-chair "savants," does not in the least mar Tesla's greatness.

The titanic brain of Tesla has hardly produced a more amazing wonder than this "magnifying transmitter." Contrary to popular belief his tower was not built to radiate Hertzian waves into the ether. Tesla's system sends out thousands of horsepower thru the earth—he has shown experimentally how power can be sent without wires over distances from a central point. Nor is there any mystery about it how he accomplishes the result. His historic U. S. patents and articles describe the method used. Tesla's Magnifying Transmitter is truly a modern lamp of Aladdin.

EDITOR.

"Aladdin's Lamp".

These and other inventions of mine, however, were nothing more than steps forward in certain directions. In evolving them I simply followed the inborn instinct to improve the present devices without

(*Continued on page* 148)

Copyright, 1919, by E. P. Co. All rights reserved

Mr. Tesla's articles started in our February issue

Copyright, 1919, by E. E. Co.

THIS PHOTOGRAPH OF A MODEL SHOWS HOW THE TESLA TOWER BUILT ON LONG ISLAND, EIGHTEEN YEARS AGO, WOULD HAVE LOOKED COMPLETED. FROM ITS APPEARANCE NOBODY WOULD INFER THAT IT WAS TO BE USED FOR THE GREAT PURPOSES WHICH ARE SET FORTH IN HIS ACCOMPANYING ARTICLE.



They replace steel phonograph needles!

SONORA Semi-Permanent Silvered Needles are for use on ALL MAKES of steel needle records. They play 50 to 100 times, mellow the tone, are more economical, more convenient, save constant needle changing, and increase the life of the records.

THE INSTRUMENT OF QUALITY
Sonora
CLEAR AS A BELL

Semi-Permanent Silvered
NEEDLES

Study these microphotographs, Fig. A shows an ordinary steel needle after playing one record. Notice that the point is worn off. Fig. B shows Sonora Needle after playing one record. No wear is perceptible. Fig. C shows Sonora Needle after playing over 50 records. Needle has worn down, but is still in splendid playing condition.

3 Grades: Loud—Medium—Soft
30c per card of 5. In Canada 40c.

FREE Sample Sonora Needle will be sent FREE on request. Write for it *today*. Note how many times it plays.

Sonora Phonograph Sales Company, Inc.
GEORGE E. BRIGHTSON, PRESIDENT
279 Broadway, *Dept. G*, New York
Toronto: Ryrie Building
CAUTION! Beware of similarly constructed needles of inferior quality

Send Only 12c
(Stamps or Coin)

And I will send you a copy of my valuable booklet.

"Hints to Music Loving Owners of Talking Machines"

Tells you how to take care of your machine and records, preserve the life of both, and gives many pointers to improve the tone of your instrument and increase your enjoyment of it. Instructs on the care of the motor, cleaning, speed adjusment, care of the needles—in fact every thing you should know. Send 12c today and the booklet will come by return mail.

J. H. ELLIS, Box 882, Milwaukee, Wis.
Patentee & Manufacturer. Ellis Harmonious Reproducer

You Can *RENT* This Phonograph

on our new plan! $10 puts this Young's Superior Phonograph in your home on 30 Days' Trial! Plays all makes of disc records. Cabinet size, 47 ins. high. *Rental applies on purchase.* $125 Value for $62.50. Write for details of greatest phonograph bargain ever offered. Offer Limited. Write Today.
YOUNG'S SUPERIOR PHONOGRAPH
62 W. Madison St. Dept. P26. Chicago, Ill.

Get This Car
And the AGENCY In YOUR Territory

Drive a new 1919 Birch SUPER-FOUR and make good money selling Birch cars to your friends and neighbors. They are fully guaranteed. Prompt shipments. Write quick for full information.
36 h.p., 115 inch W.B., 32x3½ tires
BIRCH MOTOR CARS Dept. 625 81 E. Madison St. CHICAGO - ILLINOIS

The Oracle

(*Continued from page* 146)

as the diagram shows. Those you show in your letter are not correct, for they give like polarity on each pole, which is wrong. We have no data on the starting coil dimensions, but you can arrive at this by experiment, or else by getting in touch with the manufacturers of a similar sized motor.



Proper Connection of Poles Composing Starting Winding of Induction Motor.

SPECIAL 110 VOLT TO 12 VOLT A. C. TRANSFORMER.

(1010) August Kling, Mobile, Ala., writes:

Q. 1. Asking for data on building a small step-down transformer to give 12 volts at the secondary, which he desires split into two coils. Total output 50 watts.

A. 1. We give herewith data on double wound closed core transformer to step-down 110 volts 60 cycle A. C. to a maximum secondary voltage of 12 volts.

The laminated sheet iron core for this transformer may measure 5 inches wide by 6 inches long, and have a cross-section of 1 inch by ½ inch. At either end of the two longer legs, as the diagram herewith shows, two primary windings may be placed, each of them consisting of 200 turns of No. 18 D. C. C. magnet wire. At either end of the two long legs, the two secondary windings may be placed, as the diagram shows, each of these developing about 12 volts and about 2 amperes, or giving 12 volts and 4 amperes or 50 watts, the total output you request for both secondaries connected in parallel. It is understood that both primaries in this design are to be connected in series on 110 volt 60 cycle A. C. at all times, i.e., whenever the transformer is used. The secondary windings each consist of 45 turns No. 12 B. & S. gage D. C. C. magnet wire, the secondary being wound on either leg beside the primary coil.



Details of 110-Volt to 12-Volt A. C. Transformer. Secondary Coils May Be Connected in Parallel or in Series.

With respect to taking off taps on the secondary for different voltages, you can easily divide up the total number of turns on the secondary yourself by means of a small battery voltmeter. You can readily test the potential by experiment. The voltage in any case is directly proportionate to the number of turns in use.

100-WATT, 32 TO 8-VOLT STEP-DOWN TRANSFORMER.

(1011) Claude Carefoot, Pasqua, Sask., Canada, inquires:

Q. 1. For data on step-down transformer to reduce 32 volts to 8 volts, A. C.

A. 1. We do not of course know how many watts you wish the transformer to carry, but we give you herewith data on a 100-watt transformer. The laminated sheet iron core may be about 8" long by 6" wide and thickness of 1". The core should have a cross-section of 1 square inch. The primary winding, on one leg of the transformer, should consist of 230 turns of No. 11 D.C.C. magnet wire.

The secondary winding should have 58 turns of No. 5 D.C.C. magnet wire.

My Inventions

By Nikola Tesla

(*Continued from page* 112)

any special thought of our far more imperative necessities. The "Magnifying Transmitter" was the product of labors extending through years, having for their chief object the solution of problems which are infinitely more important to mankind than mere industrial development.

If my memory serves me right, it was in November, 1890, that I performed a laboratory experiment which was one of the most extraordinary and spectacular ever recorded in the annals of science. In investigating the behaviour of high frequency currents I had satisfied myself that an electric field of sufficient intensity could be produced in a room to light up electrodeless vacuum tubes. Accordingly, a transformer was built to test the theory and the first trial proved a marvelous success. It is difficult to appreciate what those strange phenomena meant at that time. We crave for new sensations but soon become indifferent to them. The wonders of yesterday are today common occurrences. When my tubes were first publicly exhibited they were viewed with amazement impossible to describe. From all parts of the world I received urgent invitations and numerous honors and other flattering inducements were offered to me, which I declined.

In Faraday's Chair

But in 1892 the demands became irresistible and I went to London where I delivered a lecture before the Institution of Electrical Engineers. It had been my intention to leave immediately for Paris in compliance with a similar obligation, but Sir James Dewar insisted on my appearing before the Royal Institution. I was a man of firm resolve but succumbed easily to the forceful arguments of the great Scotchman. He pushed me into a chair and poured out half a glass of a wonderful brown fluid which sparkled in all sorts of iridescent colors and tasted like nectar. "Now," said he, "you are sitting in Faraday's chair and you are enjoying whiskey he used to drink." In both aspects it was an enviable experience. The next evening I gave a demonstration before that Institution, at the termination of which Lord Rayleigh addressed the audience and his generous words gave me the first start in these endeavors. I fled from London and later from Paris to escape favors

(*Continued on page* 173)

My Inventions

By Nikola Tesla

(Continued from page 148)

showered upon me, and journeyed to my home where I passed through a most painful ordeal and illness. Upon regaining my health I began to formulate plans for the resumption of work in America. Up to that time I never realized that I possessed any particular gift of discovery but Lord Rayleigh, whom I always considered as an ideal man of science, had said so and if that was the case I felt that I should concentrate on some big idea.

Nature's Trigger.

One day, as I was roaming in the mountains, I sought shelter from an approaching storm. The sky became overhung with heavy clouds but somehow the rain was delayed until, all of a sudden, there was a lightning flash and a few moments after a deluge. This observation set me thinking. It was manifest that the two phenomena were closely related, as cause and effect, and a little reflection led me to the conclusion that the electrical energy involved in the precipitation of the water was inconsiderable, the function of lightning being much like that of a sensitive trigger. Here was a stupendous possibility of achievement. If we could produce electric effects of the required quality, this whole planet and the conditions of existence on it could be transformed. The sun raises the water of the oceans and winds drive it to distant regions where it remains in a state of most delicate balance. If it were in our power to upset it when and wherever desired, this mighty life-sustaining stream could be at will controlled. We could irrigate arid deserts, create lakes and rivers and provide motive power in unlimited amounts. This would be the most efficient way of harnessing the sun to the uses of man. The consummation depended on our ability to develop electric forces of the order of those in nature. It seemed a hopeless undertaking, but I made up my mind to try it and immediately on my return to the United States, in the summer of 1892, work was begun which was to me all the more attractive, because a means of the same kind was necessary for the successful transmission of energy without wires.

Four Million Volts.

The first gratifying result was obtained in the spring of the succeeding year when I reached tensions of about 1,000,000 volts with my conical coil. That was not much in the light of the present art, but it was then considered a feat. Steady progress was made until the destruction of my laboratory by fire in 1895, as may be judged from an article by T. C. Martin which appeared in the April number of the *Century Magazine*. This calamity set me back in many ways and most of that year had to be devoted to planning and reconstruction. However, as soon as circumstances permitted, I returned to the task. Although I knew that higher electro-motive forces were attainable with apparatus of larger dimensions, I had an instinctive perception that the object could be accomplished by the proper design of a comparatively small and compact transformer. In carrying on tests with a *secondary in the form of a flat spiral*, as illustrated in my patents, the absence of streamers surprised me, and it was not long before I discovered that this was due to the position of the turns and their mutual action. Profiting from this observation I resorted to the use of a high tension conductor with turns of considerable diameter sufficiently separated to keep down the distributed capacity, while at the

(Continued on page 176)

Brandes "Superior" Head Set, complete with head band, $6. A professional set within the means of every amateur. 2000 ohms.

Uncle Sam Said:

"Go ahead with amateur wireless receiving stations." You will be prepared to get the messages the other fellow misses if you have one of

BRANDES Wireless Headsets

They enable you to "hear with both ears" because Brandes diaphragms are perfectly matched for tone, and both receivers are perfectly tuned together. Handsome, well made, fine quality.

Send for Your Set Today

Your money back if Brandes Headsets don't prove *better* than any you've used in clearness, sensitiveness and range.

Booklet "E" will be sent upon receipt of 4c *in stamps.*

C. BRANDES, INC.

Wireless Receiver Specialists

ROOM 814 32 UNION SQUARE NEW YORK CITY

Complete line of Brandes receivers for those in Western States and Pacific Coast. Catalogue "E" on request.

Balboa Building **FORD KING** **San Francisco, Cal.**

Universal Radio Apparatus

The Universal Radio Manufacturing Corporation has taken over the business previously conducted by the Mignon Wireless Corporation and is prepared to furnish all of the Mignon system instruments, built according to the original Mignon specifications. In addition to these, the Corporation has recently perfected a series of new type instruments which for efficient work and real service have never been equalled.



Regerative Receiver, 200-2500 meters

The Universal complete line of High Quality Radio Apparatus now includes

Cabinet Receiving Sets
Transmission Sets
Loose Couplers
Undamped Wave Receivers
Time Signal Sets
Detectors, etc.

These **"Universal"** instruments embody the very latest advances in the art of radio communication and are far in advance of other instruments of this type. Every detail in their design has been carefully worked out, and the circuit constants have been computed with scientific accuracy to give maximum results when properly used. Materials and workmanship are of the highest quality.

Every piece of **"Universal"** apparatus must pass a series of rigid tests before being allowed to leave the factory, and we unconditionally guarantee every piece of **"Universal"** apparatus to be exactly as represented, and **will cheerfully refund the purchase price** if the instrument fails to make good for any reason.

Write To-day for Free Catalog

UNIVERSAL RADIO MFG. CORPORATION

SUCCESSOR TO MIGNON WIRELESS CORPORATION

ELMIRA, NEW YORK

Wireless Receiving Ban Raised

MESCO WIRELESS PRACTICE SET



The Practice Set comprises a regular telegraph key, without circuit breaker, a special high pitch buzzer, one cell Red Seal Dry Battery, and four feet of green silk covered flexible cord.

The key and buzzer are mounted on a highly finished wood base, and three nickel plated binding posts are so connected that the set may be used for five different purposes.

List No. Price

342 Telegraph Practice Set, with Battery and Cord $3.24

Weighs 4 lbs. packed.
Price does not include postage.

MESCO Combination Practice Set for Learning the Morse and Continental Visual and Audible Codes

This outfit is the only reliable instrument which will enable students to become proficient operators in the U. S. Naval Service, because it is equipped with a buzzer and miniature lamp enabling the user to master both the visual and audible signals quickly.



List No. 52—Practice Set with Red Seal Battery and Cord $4.05

Weighs 4 lbs. packed. Price does not include postage.

MESCO RADIO BUZZER



This buzzer maintains a constant note and is recommended as an exciter for checking wavemeters where pure note and ample energy are required.

It consists of practically a closed circuit field of low reluctance, having a steel armature to which is riveted a strap supporting a movable contact. The armature tension is adjustable by means of a screw with a milled head large enough to be easily and permanently adjusted with the fingers. The stationary contact is adjusted by means of a similar screw. The magnet coils are connected in series with a total D. C. resistance of 3.9 ohms. Shunted across these coils is a resistance having a D. C. value of 3 ohms. This shunt eliminates all sparking such as occurs at the break on ordinary radio buzzers and the energy saved thereby is transferred into any oscillating circuit connected to it, the result being that this buzzer as constructed radiates five times more energy than any other existing type. All connecting wires liable to be broken are eliminated. Contacts are of genuine platinum, which is essential in order to maintain a constant note. The parts are mounted on a Condensate base to insure constancy in operation.

Diameter 2 in., height 1¼ in. The cap is attached to the base by a bayonet joint.

List No. Price

55 Mesco Radio Buzzer $2.05

We carry a Large and Complete Line of Standard Wireless Material Recognized by Experts as such with Competent Experienced Wireless Attendants in Charge

Send for the New Edition of Our Catalog W28

It is pocket size, contains 264 pages, with over 1,000 illustrations, and describes in plain, clear language all about Bells, Push Buttons, Batteries, Telephone and Wireless Telegraph Material, Electric Toys, Burglar and Fire Alarm Contrivances, Electric Call Bells, Electric Alarm Clocks, Medical Batteries, Motor Boat Horns, Electrically Heated Apparatus, Battery Connectors, Switches, Battery Gauges, Wireless Telegraph Instruments, Ignition Supplies, etc.

Manhattan Electrical Supply Co., Inc.

NEW YORK: 17 Park Place

CHICAGO: 114 S. Wells St.

ST. LOUIS: 1106 Pine St.

San Francisco Office: 604 Mission St.

A New Bulletin of Experimental Radio Apparatus

That embodies the most modern principles of radio engineering and design, backed by the reliability of twelve years experience in the manufacture of Radio Instruments, will be mailed upon request.

CLAPP-EASTHAN COMPANY

143 Main Street **Cambridge, Mass.**

My Inventions

By Nikola Tesla

(*Continued from page* 173)

same time preventing undue accumulation of the charge at any point. The application of this principle enabled me to produce pressures of 4,000,000 volts, which was about the limit obtainable in my new laboratory at Houston Street, as the discharges extended through a distance of 16 feet. A photograph of this transmitter was published in the *Electrical Review* of November, 1898. In order to advance further along this line I had to go into the open, and in the spring of 1899, having completed preparations for the erection of a wireless plant, I went to Colorado where I remained for more than one year. Here I introduced other improvements and refinements which made it possible to generate currents of any tension that may be desired. Those who are interested will find some information in regard to the experiments I conducted there in my article, "The Problem of Increasing Human Energy" in the *Century Magazine* of June, 1900, to which I have referred on a previous occasion.

The Magnifying Transmitter.

I have been asked by the ELECTRICAL EXPERIMENTER to be quite explicit on this subject so that my young friends among the readers of the magazine will clearly understand the construction and operation of my "Magnifying Transmitter" and the purposes for which it is intended. Well, then, in the first place, it is a *resonant transformer* with a secondary in which the parts, charged to a high potential, are of considerable area and arranged in space along ideal enveloping surfaces of very large radii of curvature, and at proper distances from one another thereby insuring a *small electric surface density everywhere* so that *no leak can occur even if the conductor is bare*. It is suitable for any frequency, from a few to many thousands of cycles per second, and can be used in the production of currents of tremendous volume and moderate pressure, or of smaller amperage and immense electro-motive force. The maximum electric *tension is merely dependent on the curvature of the surfaces* on which the charged elements are situated and the area of the latter.

100 Million Volts Possible.

Judging from my past experience, as much as 100,000,000 volts are perfectly practicable. On the other hand currents of many thousands of amperes may be obtained in the antenna. A plant of but very moderate dimensions is required for such performances. Theoretically, a terminal of less than 90 feet in diameter is sufficient to develop an electro-motive force of that magnitude while for antenna currents of from 2,000-4,000 amperes at the usual frequencies it need not be larger than 30 feet in diameter.

In a more restricted meaning this wireless transmitter is one in which the Hertz-wave radiation is an entirely negligible quantity as compared with the whole energy, under which condition the damping factor is extremely small and an enormous charge is stored in the elevated capacity. Such a circuit may then be excited with impulses of any kind, even of low frequency and it will yield sinusoidal and continuous oscillations like those of an alternator.

Taken in the narrowest significance of the term, however, it is a resonant transformer which, besides possessing these qualities, is accurately proportioned to fit the globe and its electrical constants and properties, by virtue of which design it becomes highly efficient and effective in the

wireless transmission of energy. Distance is then absolutely eliminated, there being *no diminution in the intensity of the transmitted impulses.* It is even possible to make the actions *increase with the distance from the plant* according to an exact mathematical law.

This invention was one of a number comprised in my "World-System" of wireless transmission which I undertook to commercialize on my return to New York in 1900. As to the immediate purposes of my enterprise, they were clearly outlined in a technical statement of that period from which I quote:

"The 'World-System' has resulted from a combination of several original discoveries made by the inventor in the course of long continued research and experimentation. It makes possible not only the instantaneous and precise wireless transmission of any kind of signals, messages or characters, to all parts of the world, but also the inter-connection of the existing telegraph, telephone, and other signal stations without any change in their present equipment. By its means, for instance, a telephone subscriber here may call up and talk to any other subscriber on the Globe. An inexpensive receiver, not bigger than a watch, will enable him to listen anywhere, on land or sea, to a speech delivered or music played in some other place, however distant. These examples are cited merely to give an idea of the possibilities of this great scientific advance, which annihilates distance and makes that perfect natural conductor, the Earth, available for all the innumerable purposes which human ingenuity has found for a line-wire. One far-reaching result of this is that any device capable of being operated thru one or more wires (at a distance obviously restricted) can likewise be actuated, without artificial conductors and with the same facility and accuracy, at distances to which there are no limits other than those imposed by the physical dimensions of the Globe. Thus, not only will entirely new fields for commercial exploitation be opened up by this ideal method of transmission but the old ones vastly extended.

"The 'World-System' is based on the application of the following important inventions and discoveries:

"1. *The 'Tesla Transformer.'* This apparatus is in the production of electrical vibrations as revolutionary as gunpowder was in warfare. Currents many times stronger than any ever generated in the usual ways, and sparks over one hundred feet long, have been produced by the inventor with an instrument of this kind.

"2. *The 'Magnifying Transmitter.'* This is Tesla's best invention—a peculiar transformer specially adapted to excite the Earth, which is in the transmission of electrical energy what the telescope is in astronomical observation. By the use of this marvelous device he has already set up electrical movements of greater intensity than those of lightning and passed a current, sufficient to light more than two hundred incandescent lamps, around the Globe.

"3. *The 'Tesla Wireless System.'* This system comprises a number of improvements and is the only means known for transmitting economically electrical energy to a distance without wires. Careful tests and measurements in connection with an experimental station of great activity, erected by the inventor in Colorado, have demonstrated that power in any desired amount can be conveyed, clear across the Globe if necessary, with a loss not exceeding a few per cent.

"4. *The 'Art of Individualization.'* This invention of Tesla is to primitive 'tuning' what refined language is to unarticulated expression. It makes possible the transmission of signals or messages absolutely secret and exclusive both in the active and passive aspect, that is, non-interfering as well as non-interferable. Each signal is like an individual of unmistakable identity and there is virtually no limit to the number of stations or instruments which can be simultaneously operated without the slightest mutual disturbance.

"5. *The terrestial Stationary Waves."* This wonderful discovery, popularly explained, means that the Earth is responsive to electrical vibrations of definite pitch just as a tuning fork to certain waves of sound. These particular electrical vibrations, capable of powerfully exciting the Globe, lend themselves to innumerable uses of great importance commercially and in many other respects.

"The first 'World-System' power plant can be put in operation in nine months. With this power plant it will be practicable to attain electrical activities up to ten million horsepower and it is designed to serve for as many technical achievements as are possible without due expense. Among these the following may be mentioned:

"(1) The inter-connection of the existing telegraph exchanges or offices all over the world;

"(2) The establishment of a secret and non-interferable government telegraph service;

"(3) The inter-connection of all the present telephone exchanges or offices on the Globe;

"(4) The universal distribution of general news, by telegraph or telephone, in connection with the Press;

"(5) The establishment of such a 'World-System' of intelligence transmission for exclusive private use;

"(6) The inter-connection and operation of all stock tickers of the world;

$15,000.00
COMPLETE WIRELESS OUTFIT
For Sale

General Description

15 KVA Motor Generator set. Motor is 440 volt, 120 cycle, 4000 R P M type, built to stand heavy overloads for indefinite lengths of time. Generator same specifications. Set is No. 3 phase, complete with all controls, starters, meters, etc.

Three transformers, Discharger of Rotary Type, condenser, etc.

Induction transformer of sufficient size to be used on any wave length up to 2000 meters with a 650 foot antennae.

Capacity of apparatus without extending:—

800 miles at day.
2800 miles at night.

Installed at a cost of over $15,000.00

The equipment comprising this outfit was the very highest type that could be bought; it is complete—ready to erect and operate without the purchase of other apparatus. Was in daily use when ordered sealed for the duration of the war. The outfit has been completely overhauled and is guaranteed to be in first class operating condition.

For further information, price, etc., address

Box 100, care of Electrical Experimenter

YOU can BUILD this PHONOGRAPH easily!
TREMENDOUS SAVING IN COST



You don't need to be a cabinet maker. We have made it an easy and a pleasant job with

Our Simplified Plans We furnish blue prints, diagrams, motor, and all metal parts complete. You build the cabinet and assemble. A few hours' work, and you will have as fine a type of phonograph as any produced, and at a price away below what you would pay in a store.

Keep the Savings in Your Pocket

Your machine will play all records, will have a wonderful tonal quality, excelled by none. No need now for any family to be without a phonograph because of the cost. THE MAKAFONE solves the problem. BUILD IT YOURSELF AT LESS THAN ONE-FOURTH REGULAR COST, but equal to the high priced cabinet machines. Free Records with each outfit. SEND TODAY FOR FREE CATALOG and full particulars of our wonderful offer. *Many a manufacturer got his start in this way. Why not you? Build machines and sell to your friends. Ask us about this.*

AGENTS ATTENTION

You can make and sell this machine from our plans at a profit of $50 to $75 each. Others are selling two and three a week. Here is your opportunity to make big money and become independent. Pleasant and profitable work. START TODAY.

MODERN PHONOGRAPH SUPPLY CO.
104 Springer Bldg., 313 So. Clinton St., Chicago, Ill.

WRITE TODAY!

MODERN PHONOGRAPH SUPPLY CO.
104 Springer Bldg., 313 So. Clinton St., Chicago, Ill.

Gentlemen: Please send me full particulars of your Makafone proposition, without obligation to me.

Name .....

Street Address .....

City or Town .....

Boys! You Can Make Your Own Electrical Apparatus with the aid of these wonderful books

Home-made Electrical Apparatus

By A. M. Powell

Three wonderful big books, chuck full of just the sort of information you have been looking for and at a price within reach of your pocket book. Each volume is printed on heavy paper, contains **75 pages and over 60 illustrations, complete working drawings for making every sort of electrical apparatus.** Written so you can understand them. **The price is only 25 cents per copy**—practically the cost of publication. See partial table of contents below and order now. The supply is limited.

Vol. I Contains *working drawings* and directions for making all sorts of Static Machines, Static Apparatus, Home-made Batteries, Storage Cells, Transformers, Rectifiers, etc.

Vol. II contains *working drawings* and directions for all sorts of Voltmeters, Ammeters, Galvanometers, Switches, Rheostats, Telegraph Keys, Sounders, Telephones, Shocking Coils, Spark Coils, Experiments, etc., etc.

Vol. III contains *working drawings* and directions for making all sorts of Dynamos, Motors, Electric Engines, Miniature Lighting Plants, Wireless Telegraph Apparatus, Tesla Coils, Wireless Telephone, Electroplating, Experiments, etc., etc.

Any of these wonderful books will be sent to you *postpaid* for 25 cents.

COLE & MORGAN, Inc., *Publishers and Booksellers*
P. O. Box 473, C. H. Sta., New York City

INDEX to ELECTRICAL EXPERIMENTER SCIENCE & INVENTION

For Vol. 1, 2, 3, 4, 5
15c
EXPERIMENTER PUBL. CO.
Book Dept. 231 Fulton St., N. Y.



DUCK'S BIG 300 PP. Wireless & Electrical

Catalog is now as it always has been, the largest and most complete and dependable Wireless Catalog published. Mailed for 12c in stamps or coin which may be deducted on first order of one dollar. Catalog not sent otherwise. This catalog costs us twice the price of other catalogs.

Everything in wireless *worth while* is listed in this catalog. The experienced amateur will tell you to see our catalog before buying. You are thereby insured against an unwise purchase. It is the *Beacon Light* to guide you right in the selection of your wireless apparatus. No bigger or better values are obtainable elsewhere. Send for revised price list. It is yours for the asking.

THE WILLIAM B. DUCK CO., 230-232 Superior St., Toledo, Ohio

RADIO BULLETIN

The great impetus given to radio development during the war is fully symbolized by our new line of high grade radio apparatus. Electrically and mechanically modern and distinctive.

Send for free bulletin

A. H. GREBE & COMPANY

RICHMOND HILL NEW YORK



The JOVE is the Best, Cheapest and Most Reliable Detector.
Sample by mail for $1.44.

"BUNNELL" Goods are ALWAYS RELIABLE

Send for our **Wireless Manual No. 40 E.** *JUST OUT*

Our Condensers, Transformers, Head Sets, etc., are the acknowledged standard of **High Grade** Radio Apparatus.

J. H. BUNNELL & Co., Inc., 32 Park Place, New York

→ Radio Amateurs ←

Write us today for a Free Copy of our New Bulletin of latest Radio Apparatus. We handle the products of fifty-three manufacturers of Radio Supplies and can take your order for any piece of Wireless Apparatus on the amateur market. Buying your radio apparatus through us will be as much to your benefit as to our profit. One order and one stamp will cover your entire needs.

Take Advantage of Our Free Information Department

where our Radio Expert is at your service.

Our Bulletins are now ready for Free distribution and supplements will be issued at frequent intervals. A postcard will bring you our Latest Bulletin and put your name on our Mailing List.

NATIONAL RADIO SUPPLY CO.

Dept. 100, 1405 U Street :: Washington, D. C.

"THERE'S MONEY IN IT"

AT HOME LEARN TELEGRAPHY AT HOME

MORSE AND WIRELESS

TEACH YOURSELF



In half the usual time, at trifling cost, with the wonderful Automatic Transmitter, **THE OMNIGRAPH.** Sends unlimited Morse or Continental messages, at any speed, just as an expert operator would.

Adopted by U. S. Gov't. 4 styles. Catalogue free.

OMNIGRAPH MFG. CO.

39L Cortlandt St. New York

"(7) The establishment of a 'World-System' of musical distribution, etc.;

"(8) The universal registration of time by cheap clocks indicating the hour with astronomical precision and requiring no attention whatever;

"(9) The world transmission of typed or hand-written characters, letters, checks, etc.;

"(10) The establishment of a universal marine service enabling the navigators of all ships to steer perfectly without compass, to determine the exact location, hour and speed, to prevent collisions and disasters, etc.;

"(11) The inauguration of a system of world-printing on land and sea;

"(12) The world reproduction of photographic pictures and all kinds of drawings or records."

I also proposed to make demonstrations in the wireless transmission of power on a small scale but sufficient to carry conviction. Besides these I referred to other and incomparably more important applications of my discoveries which will be disclosed at some future date.

A plant was built on Long Island with a tower 187 feet high, having a spherical terminal about 68 feet in diameter. These dimensions were adequate for the transmission of virtually any amount of energy. Originally only from 200 to 300 K.W. were provided but I intended to employ later several thousand horsepower. The transmitter was to emit a wave-complex of special characteristics and I had devised a unique method of telephonic control of any amount of energy.

The tower was destroyed two years ago but my projects are being developed and another one, improved in some features, will be constructed. On this occasion I would contradict the widely circulated report that the structure was demolished by the Government which owing to war conditions, might have created prejudice in the minds of those who may not know that the papers, which thirty years ago conferred upon me the honor of American citizenship, are always kept in a safe, while my orders, diplomas, degrees, gold medals and other distinctions are packed away in old trunks. If this report had a foundation I would have been refunded a large sum of money which I expended in the construction of the tower. On the contrary it was in the interest of the Government to preserve it, particularly as it would have made possible—to mention just one valuable result—the location of a submarine in any part of the world. My plant, services, and all my improvements have always been at the disposal of the officials and ever since the outbreak of the European conflict I have been working at a sacrifice on several inventions of mine relating to aerial navigation, ship propulsion and wireless transmission which are of the greatest importance to the country. Those who are well informed know that my ideas have revolutionized the industries of the United States and I am not aware that there lives an inventor who has been, in this respect, as fortunate as myself especially as regards the use of his improvements in the war. I have refrained from publicly expressing myself on this subject before as it seemed improper to dwell on personal matters while all the world was in dire trouble. I would add further, in view of various rumors which have reached me, that Mr. J. Pierpont Morgan did not interest himself with me in a business way but in the same large spirit in which he has assisted many other pioneers. He carried out his generous promise to the letter and it would have been most unreasonable to expect from him anything more. He had the highest regard for my attainments and gave me every evidence of his complete faith in my ability to ultimately achieve what I had set out to do. I am unwilling to accord to some small-minded and jealous individuals the satisfaction of having thwarted my efforts. These men are to me nothing more than microbes of a nasty disease. My project was retarded by laws of nature. The world was not prepared for it. It was too far ahead of time. But the same laws will prevail in the end and make it a triumphal success.

My Inventions

By Nikola Tesla

VI. THE ART OF TELAUTOMATICS

How Tesla's Mind Recuperates.

NO subject to which I have ever devoted myself has called for such concentration of mind and strained to so dangerous a degree the finest fibers of my brain as the system of which the Magnifying Transmitter is the foundation. I put all the intensity and vigor of youth in the development of the rotating field discoveries, but those early labors were of a different character. Although strenuous in the extreme, they did not involve that keen and exhausting discernment which had to be exercised in attacking the many puzzling problems of the wireless. Despite my rare physical endurance at that period the abused nerves finally rebelled and I suffered a complete collapse, just as the consummation of the long and difficult task was almost in sight. Without doubt I would have paid a greater penalty later, and very likely my career would have been prematurely terminated, had not providence equipt me with a safety device, which has seemed to improve with advancing years and unfailingly comes into play when my forces are at an end. So long as it operates I am safe from danger, due to overwork, which threatens other inventors and, incidentally, I need no vacations which are indispensable to most people. When I am all but used up I simply do as the darkies, who "naturally fall asleep while white folks worry." To venture a theory out of my sphere—the body probably accumulates little by little a definite quantity of some toxic agent and I sink into a nearly lethargic state which lasts half an hour to the minute. Upon awakening I have the sensation as though the events immediately preceding had occurred very long ago, and if I attempt to continue the interrupted train of thought I feel a veritable mental nausea. Involuntarily I then turn to other work and am surprised at the freshness of the mind and ease with which I overcome obstacles that had baffled me before. After weeks or months my passion for the temporarily abandoned invention returns and I invariably find answers to all the vexing questions with scarcely any effort. In this connection I will tell of an extraordinary experience which may be of interest to students of psychology. I had produced a striking phenomenon with my grounded transmitter and was endeavoring to ascertain its true significance in relation to the currents propagated through the earth. It seemed a hopeless undertaking, and for more than a year I worked unremittingly, but in vain. This profound study so entirely absorbed me that I became forgetful of everything else, even of my undermined health. At last, as I was at the point of breaking down, nature applied the preservative inducing lethal sleep. Regaining my senses, I realized with consternation that I was unable to visualize scenes from my life except those of infancy, the very first ones that had entered my consciousness. Curiously enough, these appeared before my vision with startling distinctness and afforded me welcome relief. Night after night, when retiring, I would think of them and more and more of my previous existence was revealed. The image of my mother was always the principal figure in the spectacle that slowly unfolded, and a consuming desire to see her again gradually took possession of me. This feeling grew so strong that I resolved to drop all work and satisfy my longing. But I found it too hard to break away from the laboratory, and several months elapsed during which I had succeeded in reviving all the impressions of my past life up to the spring of 1892. In the next picture that came out of the mist of oblivion, I saw myself at the *Hotel de la Paix* in Paris just coming to from one of my peculiar sleeping spells, which had been caused by prolonged exertion of the brain. Imagine the pain and distress I felt when it flashed upon my mind that a dispatch was handed to me at that very moment bearing the sad news that my mother was dying; I remembered how I made the long journey home without an hour of rest and how she passed away after weeks of agony! It was especially remarkable that during all this period of partially obliterated memory I was fully

IN this article, Dr. Tesla dwells on the future possibilities of his magnifying transmitter, especially in connection with the art of Telautomatics, which was first conceived by him and doubtless constitutes one of his most brilliant gifts to the world.

Tesla was the first to build and successfully operate Automata in the form of boats steered and otherwise controlled by tuned wireless circuits and agents ensuring reliable action despite of all attempts to interfere.

But this was only the first step in the evolution of his invention. What he wanted, was to produce machines capable of acting as though possessed of intelligence. It will be readily perceived that if Dr. Tesla has practically realized his conception, the world will witness a revolution in every field of endeavor. In particular will his inventions affect the art of warfare and the peace of the world.

Dr. Tesla dwells eloquently on a number of topics agitating the public mind, and this article of his is perhaps the most brilliant and absorbing he has written.



One of the Telautomatic Boats (Submersible) Constructed By Tesla and Exhibited By Him in 1898. Controlled By Wireless Without Aerials.



Copyright, 1919, by E. P. Co.

Tesla's New Self-Propelled Aerial Tel-Automaton. Devoid of Propeller, Sustaining Wings and All Other Means of External Control. Can Attain a Speed of 350 Miles Per Hour, and Will Reach a Predetermined Point a Thousand Miles Away Accurately Within a Few Feet.

alive to everything touching on the subject of my research. I could recall the smallest details and the least insignificant observations in my experiments and even recite pages of text and complex mathematical formulae.

My belief is firm in a law of compensation. The true rewards are ever in proportion to the labor and sacrifices made. This is one of the reasons why I feel certain that of all my inventions, the Magnifying Transmitter will prove most important and valuable to future generations. I am prompted to this prediction not so much by thoughts of the commercial and industrial revolution which it will surely bring about, but of the humanitarian consequences of the many achievements it makes possible. Considerations of mere utility weigh little in the balance against the higher benefits of civilization. We are confronted with portentous problems which can not be solved just by providing for our material existence, however abundantly. On the contrary, progress in this direction is fraught with hazards and perils not less menacing than those born from want and suffering. If we were to release the energy of atoms or discover some other way of developing cheap and unlimited power at any point of the globe this accomplishment, instead of being a blessing, might bring disaster to mankind in giving rise to dissension and anarchy which would ultimately result in the enthronement of the hated regime of force. The greatest good will come from technical improvements tending to unification and harmony, and my wireless transmitter is preeminently such. By its means the human voice and likeness will be reproduced everywhere and factories driven thousands of miles from waterfalls furnishing the power; aerial machines will be propelled around the earth without a stop and the sun's energy controlled to create lakes and rivers for motive purposes and transformation of arid deserts into fertile land. Its introduction for telegraphic, telephonic and similar uses will automatically cut out the statics and all other interferences which at present impose narrow limits to the application of the wireless. This is a timely topic on which a few words might not be amiss.

Dr. Tesla is Rapidly Becoming Younger. Judge for Yourself from His Latest Photograph.

Tesla Raps "Static" Men Vigorously.

During the past decade a number of people have arrogantly claimed that they had succeeded in doing away with this impediment. I have carefully examined all of the arrangements described and tested most of them long before they were publicly disclosed, but the finding was uniformly negative. A recent official statement from the U. S. Navy may, perhaps, have taught some beguilable news editors how to appraise these announcements at their real worth. As a rule the attempts are based on theories so fallacious that whenever they come to my notice I can not help thinking in a lighter vein. Quite recently a new discovery was heralded, with a deafening flourish of trumpets, but it proved another case of a mountain bringing forth a mouse. This reminds me of an exciting incident which took place years ago when I was conducting my experiments with currents of high frequency. Steve Brodie had just jumped off the Brooklyn Bridge. The feat has been vulgarized since by imitators, but the first report electrified New York. I was very impressionable then and frequently spoke of the daring printer. On a hot afternoon I felt the necessity of refreshing myself and stepped into one of the popular thirty thousand institutions of this great city where a delicious twelve per cent beverage was served which can now be had only by making a trip to the poor and devastated countries of Europe. The attendance was large and not over-distinguished and a matter was discussed which gave me an admirable opening for the careless remark: "This is what I said when I jumped off the bridge." No sooner had I uttered these words than I felt like the companion of Timotheus in the poem of Schiller. In an instant there was a pandemonium and a dozen voices cried: "It is Brodie!" I threw a quarter on the counter and bolted for the door but the crowd was at my heels with yells: "Stop, Steve!" which must have been misunderstood for many persons tried to hold me up as I ran frantically for my haven of refuge. By darting around corners I fortunately managed—through the medium of a fire-escape—to reach the laboratory, where I threw off my coat, camouflaged myself as a hard-working blacksmith, and started the forge. But these precautions proved unnecessary; I had eluded my pursuers. For many years afterward, at night, when imagination turns into spectres the trifling troubles of the day, I often thought, as I tossed on the bed, what my fate would have been had that mob caught me and found out that I was not Steve Brodie!

Now the engineer, who lately gave an account before a technical body of a novel remedy against statics based on a "heretofore unknown law of nature," seems to have been as reckless as myself when he contended that these disturbances propagate up and down, while those of a transmitter proceed along the earth. It would mean that a condenser, as this globe, with its gaseous envelope, could be charged and discharged in a manner quite contrary to the fundamental teachings propounded in every elemental text-book of physics. Such a supposition would have been condemned as erroneous, even in Franklin's time, for the facts bearing on this were then well known and the identity between atmospheric electricity and that developed by machines was fully established. Obviously, natural and artificial disturbances propagate through the earth and the air in exactly the same way, and both set up electro-motive forces in the horizontal, as well as vertical, sense. Interference can not be overcome by any such methods as were proposed. The truth is this: In the air the potential increases at the rate of about fifty volts per foot of elevation, owing to which there may be a difference of pressure amounting to twenty, or even forty thousand volts between the upper and lower ends of the antenna. The masses of the charged atmosphere are constantly in motion and give up electricity to the conductor, not continuously but rather disruptively, this producing a grinding noise in a sensitive telephonic

(*Continued on page* 550)

One pupil says, "It's the best money I ever invested. The lessons would be cheap at double the price."

Who wants to learn boxing?

Would you like to know how to protect yourself against a bully? To be able to outbox someone bigger than you? To know the eight most effective blows to use, and the best guards against violent attack, not only against blows, but kicks and wrestling holds? Do you know that you can learn these things easily and quickly by the new "shorthand" system of boxing instruction, the Marshall Stillman Method, making your daily exercise interesting as well as beneficial?

Marshall Stillman teaches boxing by science. By this new method he has taught a novice in 15 minutes the difficult scientific left hand lead. It often takes 20 lessons to learn it by the old method. In 40 minutes Marshall Stillman taught 46 new members of the New York State Guard the principles of the hit, guard, and duck. Boxing professors in the Army say that it took them weeks to teach a group those fundamentals by the old method.

This system is so simple that it is taught by mail. You learn the fundamentals right in front of your own mirror. When you face your first opponent, you know how to hit him, what to expect in return, and how to guard against it. Two weeks after receiving it pupils have been able to outbox bigger and stronger opponents. Even boys of 15 have learned to hit and to protect themselves. Men of 50 and 60 have taken it, not only to learn boxing, but for the interesting and beneficial daily exercise.

The new complete Home Study Edition is only $5—less than you would pay for a few lessons by the old method. Besides the 5 "shorthand" lessons on the hit, guard, duck, feinting and clinching and footwork with 25 illustrations, it includes one lesson on daily exercise, 8 illustrations; 3 rounds of shadow boxing, 8 bone-breaking holds and releases (Jiu Jitsu) and 8 holds in standing wrestling, with 69 illustrations; and a complimentary copy, specially bound for home study, of Mike Donovan's famous book "The Science of Boxing," including 70 illustrations.

Send no money

Frankly, you don't believe boxing can be taught by mail, do you? All right, we'll take you on your own ground—we will mail the complete course to you on 5-day approval. Use the coupon below.

Marshall Stillman Association, Suite E-10, No. 461 Fourth Ave., New York.

You may send me on free 5-day approval your new complete Home Study Course in Boxing, including 5 "Shorthand" or Sub-conscious Boxing Lessons, one lesson for daily exercise, 3 rounds of shadow boxing, 8 bone-breaking holds and releases, 8 holds in standing wrestling, and a complimentary copy of Mike Donovan's Book, "The Science of Boxing." I will either return the course or remit $5 in full payment within 5 days after its arrival.

Name.....

Address.....

BE AN EXPERT
Auto and Tractor Mechanic
Earn $100 to $400 a Month
Young man, are you mechanically inclined? Come to the Sweeney School. Learn to be an expert. I teach with tools not hooks. Do the work yourself, that's the secret of the
SWEENEY SYSTEM
of practical training by which 5,000 soldiers were trained for U. S. Government and over 20,000 expert mechanics. Learn in a few weeks; no previous experience necessary.
FREE Write today for illustrated free catalog showing hundreds of pictures men working in new Million Dollar Trade School.
LEARN A TRADE
Sweeney
SCHOOL OF AUTO-TRACTOR-AVIATION
66 SWEENEY BLDG. KANSAS CITY, MO.


INSYDE TYRES Inner Armor
for Auto Tires. Double mileage, prevent blowouts and punctures. Easily applied in any tire. Thousands sold. Details free. Agents wanted.
Amer. Accessories Co., Dept. 53, Cincinnati

"Piped Cold" — Prof. Bell Has It

(*Continued from page* 517)

our radiators and pipes. But we prefer not only to let our babies and our feeble old folk die unnecessarily every summer, but we actually lose untold millions of dollars thru non-production when the "dog-days" are upon us. No one can work at his best when the mercury climbs to dizzy heights. Production, whether mental or physical, slows down anywhere between forty and eighty per cent. Statistics prove it. Factories as well as offices slow down and just barely creep along. Think of this enormous, incalculable loss alone, not to mention all the physical suffering due to the heat.

Ah, yes, we *do* have our brave fans—which, however, do not cool at all, but only remind us how hot our bodies are the minute we are not in the immediate vicinity of one of these spinning monuments to our stupidity.

For our dear fans only stir up the hot air *and* the dust. Our skin, wet or moist from perspiration, meets this stirred up air and due to a well-known physical phenomenon, *surface evaporation*, we experience a *sense of coolness*, but the air itself is *not* cooled. It is true that surface evaporation produces cold, but in order to have it, it is necessary to let the fans blow upon us, or nearly so, and everyone knows this is far from healthy, frequently producing severe colds. Besides, as soon as we leave the fan our suffering from the heat is all the more acute.

Where is the practical genius who will "study up" on refrigeration and sell us a cheap refrigerating machine which we can connect to our already existing steam or hot water radiators? For the same money which we now spend on fans we ought to be able to buy the machine. And for the money it costs to run the fans we can run the refrigerator, too.

Hundreds of refrigerators have been invented, but the simplest and best no doubt for our purpose is the *cold-air process*. It is based on the principle that the compression of air generates heat and in its subsequent expansion absorbs heat. The air is first comprest, is then past thru a cooler under pressure, after which it is expanded in a cylinder. No chemicals are used with this system and it possesses the very distinct advantage that extremely low temperatures are readily obtainable.



What H. A. Daake, of Salamanca, N. Y., Thought of Mr. Gernsback's Editorial "Piped Cold."

My Inventions

By Nikola Tesla

(*Continued from page* 508)

receiver. The higher the terminal and the greater the space encompast by the wires, the more pronounced is the effect, but it must be understood that it is purely local and has little to do with the real trouble. In 1900, while perfecting my wireless system, one form of apparatus comprised four antennae. These were carefully calibrated to the same frequency and connected in multiple with the object of magnifying the action, in receiving from any direction. When I desired to ascertain the origin of the transmitted impulses, each diagonally situated pair was put in series with a primary coil energizing the detector circuit. In the former case the sound was loud in the telephone; in the latter it ceased, as expected, the two antennae neutralizing each other, but the true statics manifested themselves in both instances and I had to devise special preventives embodying different principles.

The Remedy for Static.

By employing receivers connected to two points of the ground, as suggested by me long ago, this trouble caused by the charged air, which is very serious in the structures as now built, is nullified and besides, the liability of all kinds of interference is reduced to about one-half, because of the directional character of the circuit. This was perfectly self-evident, but came as a revelation to some simple-minded wireless folks whose experience was confined to forms of apparatus that could have been improved with an axe, and they have been disposing of the bear's skin before killing him. If it were true that strays performed such antics, it would be easy to get rid of them by receiving without aerials. But, as a matter of fact, a wire buried in the ground which, conforming to this view, should be absolutely immune, is more susceptible to certain extraneous impulses than one placed vertically in the air. To state it fairly, a slight progress has been made, but not by virtue of any particular

(*Continued on page* 552)

Boys! Win an Auto-Wheel

In This Interesting Contest

TO THE BOY who can think of the most interesting uses for the popular AUTO-WHEEL COASTER, for earning money and for play, we shall award one of our large models absolutely FREE. It's a mighty generous prize for a few minutes' work. And the following eleven valuable prizes will be given to those sending in the next best uses: **Camera, Camping Tent, Mess Kit, Scout Knife, Fleetwing Steering Sled, Compass, Ingersoll Watch, Axe, Bank, Electric Flashlight, Poncho.**

INFORMATION ABOUT CONTEST

1. Any boy or girl not over 15 years may compete.
2. Contest will be judged by three men well-known in the Boy Scout organization.
3. Write to Business Idea Dept., Buffalo Sled Co., for pamphlet explaining the Contest, and colored catalog telling all about Auto-Wheel.
4. At end of letter write names of three Coaster Wagon Dealers in your town. If any carry the Auto-Wheel put an "x" after name.

YOU CAN DO IT. Any live boy who knows how to get fun and earn money out of a good, strong coaster wagon, has a fine chance to get the Auto-Wheel as a prize. **Here are a few pointers:** The Auto-Wheel is a wagon for work or play. It's built for strength and speed. Has roller bearings, steel axles and tires, body white ash, maple gear.

If there's an Auto-Wheel dealer near you, he'll gladly let you see the Auto-Wheel Coaster in his store, and he'll give you some good ideas for your letter. CONTEST CLOSES NOVEMBER 30, 1919.

HERE'S YOUR CHANCE. GET BUSY.

Buffalo Sled Co.,
163 Schenck Street,
N. Tonawanda, N. Y.

In Canada:
Preston,
Ontario.

ONLY $5.00
A MONTH PAYS FOR THIS SPLENDID DIAMOND RING

SPECIAL VALUE

SWEET'S Cluster; 7 fine Diamonds set in Platinum. Looks like $225 Solitaire.

Seven perfectly matched, blue-white Diamonds, skilfully mounted in Platinum to resemble one magnificent Solitaire. The Diamonds were selected for their perfect cut, their blue-white color, their superior quality and wonderful brilliancy, by one of our most skilful Diamond experts; together they look like one large, single stone. A most handsome and showy ring for the least amount of money.

SEND NO MONEY—we will send the ring, all charges prepaid—you are sure to be pleased. Pay only $12.50 on delivery—the balance in ten months: $5.00 EACH MONTH, until entire price, $62.50 has been paid.

OUR PROFIT-SHARING PLAN

Our customers have the benefit of a 7½% increased re-purchase value. Write for particulars—know the House of Sweet.

FREE DE LUXE CATALOG. Learn of our great values—our easy terms of payment—our big variety. Ask for catalog **No. 579R** and be sure to address **Dept. 579R, Liberty**

Bonds accepted at face value.

THE HOUSE OF QUALITY
L.W. SWEET & CO. INC.
2-4 MAIDEN LANE, NEW YORK

Build Your Own PHONOGRAPH

It's Easy With Our Help

A few hours interesting work saves many dollars and gives you a machine exactly to suit your ideals. We furnish motors, tone arms, case material, blue prints and full instructions. Plays any record. You can make fine profit building phonographs for your friends.

Write Today for Our Free Blue Print Offer. Agents wanted for our ready built Choraleons.

Choraleon Phonograph Co.
710 Monger Bldg., Elkhart, Ind.

SAVE OVER HALF

My Inventions

By Nikola Tesla

(*Continued from page* 550)

method or device. It was achieved simply by discarding the enormous structures, which are bad enough for transmission but wholly unsuitable for reception, and adopting a more appropriate type of receiver. As I pointed out in a previous article, to dispose of this difficulty for good, a radical change must be made in the system, and the sooner this is done the better.

Radio Government Control Not Wanted.

It would be calamitous, indeed, if at this time when the art is in its infancy and the vast majority, not excepting even experts, have no conception of its ultimate possibilities, a measure would be rushed through the legislature making it a government monopoly. This was proposed a few weeks ago by Secretary Daniels, and no doubt that distinguished official has made his appeal to the Senate and House of Representatives with sincere conviction. But universal evidence unmistakably shows that the best results are always obtained in healthful commercial competition. There are, however, exceptional reasons why wireless should be given the fullest freedom of development. In the first place it offers prospects immeasurably greater and more vital to betterment of human life than any other invention or discovery in the history of man. Then again, it must be understood that this wonderful art has been, in its entirety, evolved here and can be called "American" with more right and propriety than the telephone, the incandescent lamp or the aeroplane. Enterprising press agents and stock jobbers have been so successful in spreading misinformation that even so excellent a periodical as the *Scientific American* accords the chief credit to a foreign country. The Germans, of course, gave us the Hertz-waves and the Russian, English, French and Italian experts were quick in using them for signaling purposes. It was an obvious application of the new agent and accomplished with the old classical and unimproved induction coil—scarcely anything more than another kind of heliography. The radius of transmission was very limited, the results attained of little value, and the Hertz oscillations, as a means for conveying intelligence, could have been advantageously replaced by sound-waves, which I advocated in 1891. Moreover, all of these attempts were made three years after the basic principles of the wireless system, which is universally employed to-day, and its potent instrumentalities had been clearly described and developed in America. No trace of those Hertzian appliances and methods remains today. We have proceeded in the very opposite direction and what has been done is the product of the brains and efforts of citizens of this country. The fundamental patents have expired and the opportunities are open to all. The chief argument of the Secretary is based on interference. According to his statement, reported in the New York *Herald* of July 29th, signals from a powerful station can be intercepted in every village of the world. In view of this fact, which was demonstrated in my experiments of 1900, it would be of little use to impose restrictions in the United States.

America First.

As throwing light on this point, I may mention that only recently an odd looking gentleman called on me with the object of enlisting my services in the construction of world transmitters in some distant land. "We have no money," he said, "but carloads of solid gold and we will give you a liberal amount." I told him that I wanted to see first what will be done with my inventions in America, and this ended the interview. But I am satisfied that some dark forces are at work, and as time goes on the maintenance of continuous communication will be rendered more difficult. The only remedy is a system immune against interruption. It has been perfected, it exists, and all that is necessary is to put it in operation.

The terrible conflict is still uppermost in the minds and perhaps the greatest importance will be attached to the Magnifying Transmitter as a machine for attack and defense, more particularly in connection with *Telautomatics*. This invention is a logical outcome of observations begun in my boyhood and continued thruout my life. When the first results were publisht the *Electrical Review* stated editorially that it would become one of the "most potent factors in the advance and civilization of mankind." The time is not distant when this prediction will be fulfilled. In 1898 and 1900 it was offered to the Government and might have been adopted were I one of those who would go to Alexander's shepherd when they want a favor from Alexander. At that time I really thought that it would abolish war, because of its unlimited destructiveness and exclusion of the personal element of combat. But while I have not lost faith in its potentialities, my views have changed since.

The Road to Permanent Peace.

War can not be avoided until the physical cause for its recurrence is removed and this, in the last analysis, is the vast extent of the planet on which we live. Only thru annihilation of distance in every respect as, the conveyance of intelligence, transport of passengers and supplies and transmission of energy will conditions be brought about some day, insuring permanency of friendly relations. What we now want most is closer contact and better understanding between individuals and communities all over the earth, and the elimination of that fanatic devotion to exalted ideals of national egoism and pride which is always prone to plunge the world into primeval barbarism and strife. No league or parliamentary act of any kind will ever prevent such a calamity. These are only new devices for putting the weak at the mercy of the strong. I have exprest myself in this regard fourteen years ago, when a combination of a few leading governments—a sort of Holy Alliance—was advocated by the late Andrew Carnegie, who may be fairly considered as the father of this idea, having given to it more publicity and impetus than anybody else prior to the efforts of the President. While it can not be denied that such a pact might be of material advantage to some less fortunate peoples, it can not attain the chief object sought. Peace can only come as a natural consequence of universal enlightenment and merging of races, and we are still far from this blissful realization. As I view the world of today, in the light of the gigantic struggle we have witnest, I am filled with conviction that the interests of humanity would be best served if the United States remained true to its traditions and kept out of "entangling alliances." Situated as it is, geographically, remote from the theaters of impending conflicts, without incentive to territorial aggrandizement, with inexhaustible resources and immense population thoroly imbued with the spirit of liberty and right, this country is placed in a unique and privileged position. It is thus able to exert, independently, its colossal strength and moral force to the benefit of all, more judiciously and effectively, than as member of a league.

(*Continued on page* 554)



Make your records last longer and play better!

AFTER an ordinary steel needle plays one record the needle point is worn off. (Illustration A.) After playing one record there is no perceptible wear if you use (Illustration B.)

THE INSTRUMENT OF QUALITY
Sonora
CLEAR AS A BELL

Semi-Permanent Silvered PHONOGRAPH NEEDLES

These Sonora Needles *play 50 to 100 times*, are more economical, more convenient, save constant needle changing and mellow the tone. These needles give the maximum of satisfaction and are the most economical ultimately.

FREE! A sample needle will be given FREE so that you can prove its merit for yourself. Write for yours today.

Three Grades
Loud, Medium, Soft.
30c per card of 5. In Canada 40c

Sonora Phonograph Sales Company, Inc.
GEORGE E. BRIGHTSON, President
279 Broadway, *Dept. G*, New York
Toronto: Ryrie Bldg.

CAUTION! Beware of similarly constructed needles of inferior quality

$446 BUYS THIS "PRESTO-UP" Bolt-Together House

The Wonder Buildings of the Age

GUARANTEED

Purchased after most rigid inspection by some of the largest Steel, Coal and Industrial Corporations in the United States. You are not experimenting. "PRESTO-UP" Bolt-Together Houses are patented, manufactured exclusively by us and sold at money saving prices.
Seven different types of walls to choose from. Wind and weather proof. Invisible joints inside and out. Extremely simple to bolt together. Wonderful strength. Better construction than regularly constructed houses. Exceptionally good lumber. Cement coated nails. Fifteen Year Guaranteed Slate Coated Roofing. Well painted, and best of all, neat in appearance and so simple to bolt together that it is a pleasure to do the work.

Send for **CATALOG FX-412 TODAY**

Houses—Garages—Barns—Out Buildings, etc. Also Harris Fresh Air Canvas Houses

HARRIS BROTHERS CO., Chicago

My Inventions

By Nikola Tesla

(*Continued from page* 552)

The Mechanistic Theory of Life.

In one of these biographical sketches, published in the ELECTRICAL EXPERIMENTER, I have dwelt on the circumstances of my early life and told of an affliction which compelled me to unremitting exercise of imagination and self-observation. This mental activity, at first involuntary under the pressure of illness and suffering, gradually became second nature and led me finally to recognize that I was but an automaton devoid of free will in thought and action and merely responsive to the forces of the environment. Our bodies are of such complexity of structure, the motions we perform are so numerous and involved, and the external impressions on our sense organs to such a degree delicate and elusive that it is hard for the average person to grasp this fact. And yet nothing is more convincing to the trained investigator than the mechanistic theory of life which had been, in a measure, understood and propounded by Descartes three hundred years ago. But in his time many important functions of our organism were unknown and, especially with respect to the nature of light and the construction and operation of the eye, philosophers were in the dark. In recent years the progress of scientific research in these fields has been such as to leave no room for a doubt in regard to this view on which many works have been published. One of its ablest and most eloquent exponents is, perhaps, Felix Le Dantec, formerly assistant of Pasteur. Prof. Jacques Loeb has performed remarkable experiments in heliotropism, clearly establishing the controlling power of light in lower forms of organisms, and his latest book, "Forced Movements," is revelatory. But while men of science accept this theory simply as any other that is recognized, to me it is a truth which I hourly demonstrate by every act and thought of mine. The consciousness of the external impression prompting me to any kind of exertion, physical or mental, is ever present in my mind. Only on very rare occasions, when I was in a state of exceptional concentration, have I found difficulty in locating the original impulses.

Lack of Observation a Form of Ignorance.

The by far greater number of human beings are never aware of what is passing around and within them, and millions fall victims of disease and die prematurely just on this account. The commonest, every-day occurrences appear to them mysterious and inexplicable. One may feel a sudden wave of sadness and rake his brain for an explanation when he might have noticed that it was caused by a cloud cutting off the rays of the sun. He may see the image of a friend dear to him under conditions which he construes as very peculiar, when only shortly before he has passed him in the street or seen his photograph somewhere. When he loses a collar button he fusses and swears for an hour, being unable to visualize his previous actions and locate the object directly. Deficient observation is merely a form of ignorance and responsible for the many morbid notions and foolish ideas prevailing. There is not more than one out of every ten persons who does not believe in telepathy and other psychic manifestations, spiritualism and communion with the dead, and who would refuse to listen to willing or unwilling deceivers. Just to illustrate how deeply rooted this tendency has become even among the clear-headed American population, I may mention a comical incident.

Psychic Phenomena in the Manufacture of Flivvers.

Shortly before the war, when the exhibition of my turbines in this city elicited widespread comment in the technical papers, I anticipated that there would be a scramble among manufacturers to get hold of the invention, and I had particular designs on that man from Detroit who has an uncanny faculty for accumulating millions. So confident was I that he would turn up some day, that I declared this as certain to my secretary and assistants. Sure enough, one fine morning a body of engineers from the Ford Motor Company presented themselves with the request of discussing with me an important project. "Didn't I tell you?" I remarked triumphantly to my employees, and one of them said, "You are amazing, Mr. Tesla; everything comes out exactly as you predict." As soon as these hard-headed men were seated I, of course, immediately began to extol the wonderful features of my turbine, when the spokesmen interrupted me and said, "We know all about this, but we are on a special errand. We have formed a psychological society for the investigation of psychic phenomena and we want you to join us in this undertaking." I suppose those engineers never knew how near they came to being fired out of my office.

Confuting Spiritism.

Ever since I was told by some of the greatest men of the time, leaders in science whose names are immortal, that I am possesst of an unusual mind, I bent all my thinking faculties on the solution of great problems regardless of sacrifice. For many years I endeavored to solve the enigma of death, and watched eagerly for every kind of spiritual indication. But only once in the course of my existence have I had an experience which momentarily impressed me as supernatural. It was at the time of my mother's death. I had become completely exhausted by pain and long vigilance, and one night was carried to a building about two blocks from our home. As I lay helpless there, I thought that if my mother died while I was away from her bedside she would surely give me a sign. Two or three months before I was in London in company with my late friend, Sir William Crookes, when spiritualism was discussed, and I was under the full sway of these thoughts. I might not have paid attention to other men, but was susceptible to his arguments as it was his epochal work on radiant matter, which I had read as a student, that made me embrace the electrical career. I reflected that the conditions for a look into the beyond were most favorable, for my mother was a woman of genius and particularly excelling in the powers of intuition. During the whole night every fiber in my brain was strained in expectancy, but nothing happened until early in the morning, when I fell in a sleep, or perhaps a swoon, and saw a cloud carrying angelic figures of marvelous beauty, one of whom gazed upon me lovingly and gradually assumed the features of my mother. The appearance slowly floated across the room and vanished, and I was awakened by an indescribably sweet song of many voices. In that instant a certitude, which no words can express, came upon me that my mother had just died. And that was true. I was unable to understand the tremendous weight of the painful knowledge I received in advance, and wrote a letter to Sir William Crookes while still under the domination of these impressions and in poor bodily health. When I recovered I sought for a long time the ex-

(*Continued on page* 556)

DETROIT

the Automobile Center of the World is the Logical Place to

LEARN AUTOMOBILE ELECTRICS

Training for Head and Hand

Auto Electricians are in big demand everywhere. Interesting work—big salaries—exceptional opportunities for advancement. Every garage, factory and service station needs one or more good men. Also splendid opportunities to open electrical service stations and make big money. Cars need constant attention. Nearly all the trouble is electrical. Six million cars now in use—a million and a half new ones will be put in service this year. That means thousands of trained men will be needed. Men trained in Detroit get the preference.

NOT A "ONE MAN SCHOOL"

The M. S. A. S. embodies the best ideas in the Auto Industry. No other school offers such an advantage as this school here in Detroit. School open all the year, enter classes any day.

KING MOTOR CAR COMPANY

BUILDERS OF KING CARS — DETROIT, U.S.A.

Replying to a recent letter addressed to Mr. Artemas Ward making inquiry as to the reputation of the Michigan State Auto School, will say that as far as we know all Detroit Automobile manufacturers endorse the work they are doing.

It is managed very efficiently and they have been turning out some pretty good men for the automobile industry, and cannot see any reason why you should hesitate about taking a course with this Institution.

Yours very truly,
KING MOTOR CAR COMPANY

MONEY-BACK GUARANTEE

We guarantee to qualify you for a position as chauffeur, repair man, tester, demonstrator, auto electrician, garage man, automobile dealer, Aeroplane motor mechanic or tractor mechanic and operator, paying from $100 to $400 monthly or refund your money.

Be An Auto Electrician
Earn $200 to $500 Monthly

If you are electrically inclined this is your best opportunity. Our complete Auto Course trains you thoroughly in Auto Electrics. You can hold down **any** job or run a business of your own. You make more money because you can locate trouble quickly, without waste of time. All your time is spent repairing the trouble—not looking for it. Our successful graduates are in every part of the world.

Auto Factories Heartily Endorse Our School

They not only endorse the M. S. A. S. but they also give us hearty co-operation. They employ our students while taking course and after they graduate. We have the latest model chassis for students to work on. In this way our students get best possible training in most practical manner.

"School News" and 176 Page Catalog FREE

Just off the press. Gives complete information. Quotes dozens of letters from students who have actually done what you would like to do. What better proof do you want that YOU can do it? You CAN! — but get busy. "Jump" a train and come to Detroit. Hundreds have done it and made good. Will help you get a job if necessary to pay expenses while taking our course. Get action NOW.

DETROIT
THE HEART OF THE AUTO INDUSTRY



Michigan State Auto School The Old Reliable School
670 Auto Bldg. Detroit, Mich. U. S. A. A. G. ZELLER, Pres.

CARNOTITE

(Radium Mineral.) The American Pitchblende found in Colorado, from which *Radium* is extracted.

A generous piece, enough to conduct experiments, such as affecting photographic plates thru opaque material (similar to X-Ray pictures), first made by Sir W. Crookes and Mme. Curie, is furnished in neat, wooden box. **URANIUM ORE** (*Radio-Active*)

Containing about 35% of pure Uranium; also Radium and Vanadium. One of the most rare and interesting minerals. Twenty milligrams are furnished in glass vial protected by lead cover.

One box of *Carnotite* and one vial of *Uranium Ore* as described above 50c sent prepaid.

FORMULAS

Luminous Paint—Silver Plating Powder—Liquid Court Plaster—Soap Bubble Liquid—Straw Hat Bleach—Collapsible Tube Tooth Paste—Resilvering Mirror Liquid—Polish for Tan Shoes—Dressing for Tan Shoes—Paint to make Oil Cloth.

These Ten Recipes in sealed envelope for 50c. Sent prepaid.

SIDNEY SPECIALTY CO., 233 Fulton Street New York City

Enormous Income from Insignificant Investment



Open a tire Repairing Shop—business pours in. Vanderpool Vulcanizer (5 Cavity Model) has capacity of $100 worth of work a day. We are the pioneer manufacturers of the Dry Cure Vulcanizer — the only vulcanizer that guarantees absolutely PERFECT work. We send you FREE TIRE REPAIRING MANUAL and give you free instruction. Write today for full particulars.

In answering address Dept. X-15

WM. VANDERPOOL CO. **Springfield, O.**

MODEL AIRPLANE SUPPLIES

Build and fly Model Airplanes ~

Send 5¢ for catalog of complete and knocked-down scale models of new machines, parts, fittings, and supplies.

Wading River Mfg. Co. 672 Broadway, Brooklyn, N.Y.

My Inventions

By Nikola Tesla

(*Continued from page* 554)

ternal cause of this strange manifestation and, to my great relief, I succeeded after many months of fruitless effort. I had seen the painting of a celebrated artist, representing allegorically one of the seasons in the form of a cloud with a group of angels which seemed to actually float in the air, and this had struck me forcefully. It was exactly the same that appeared in my dream, with the exception of my mother's likeness. The music came from the choir in the church nearby at the early mass of Easter morning, explaining everything satisfactorily in conformity with scientific facts.

This occurred long ago, and I have never had the faintest reason since to change my views on psychical and spiritual phenomena, for which there is absolutely no foundation. The belief in these is the natural outgrowth of intellectual development. Religious dogmas are no longer accepted in their orthodox meaning, but every individual clings to faith in a supreme power of some kind. We all must have an ideal to govern our conduct and insure contentment, but it is immaterial whether it be one of creed, art, science or anything else, so long as it fulfills the function of a dematerializing force. It is essential to the peaceful existence of humanity as a whole that one common conception should prevail.

Tesla's Astounding Discovery.

While I have failed to obtain any evidence in support of the contentions of psychologists and spiritualists, I have proved to my complete satisfaction the automatism of life, not only through continuous observations of individual actions, but even more conclusively through certain generalizations. These amount to a discovery which I consider of the greatest moment to human society, and on which I shall briefly dwell. I got the first inkling of this astounding truth when I was still a very young man, but for many years I interpreted what I noted simply as coincidences. Namely, whenever either myself or a person to whom I was attached, or a cause to which I was devoted, was hurt by others in a particular way, which might be best popularly characterized as the most unfair imaginable, I experienced a singular and undefinable pain which, for want of a better term, I have qualified as "cosmic," and shortly thereafter, and invariably, those who had inflicted it came to grief. After many such cases I confided this to a number of friends, who had the opportunity to convince themselves of the truth of the theory which I have gradually formulated and which may be stated in the following few words:

Our bodies are of similar construction and exposed to the same external influences. This results in likeness of response and concordance of the general activities on which all our social and other rules and laws are based. We are automata entirely controlled by the forces of the medium, being tossed about like corks on the surface of the water, but mistaking the resultant of the impulses from the outside for free will. The movements and other actions we perform are always life preservative and tho seemingly quite independent from one another, we are connected by invisible links. So long as the organism is in perfect order it responds accurately to the agents that prompt it, but the moment that there is some derangement in any individual, his self-preservative power is impaired. Everybody understands, of course, that if one becomes deaf, has his eyesight weakened, or his limbs injured, the chances for his continued existence are lessened. But

(*Continued on page* 600)

$1.00 INEXPENSIVE ELECTRIC POWER $1.00

The wonder of the twentieth century inexpensive electric power, this is possible with our new electric power system, a new idea in electricity. With the aid of our instruction and chemicals you can make and install a power battery as shown in the illustration, absolutely safe and simple. **Stop wasting money** on buying batteries, install the new electric power battery. It is not an acid or dry battery, it is a new combination of wet and dry elements which produce electricity. These batteries are **powerful and cheap** to operate, they produce a direct current of more than 20 volts, cheaper than any other form of battery. They are wonderful for operating all kinds of experimental work, for lighting purposes and for many other uses where electric current is needed. Any user of batteries knows the value of an inexpensive high voltage electric current. These batteries should be in every home, office, shop and factory, no matter how small a current is needed; to reduce or raise the current of the battery, simply move the volt regulator on the switch board. The beauty of these power batteries is, that they do not evaporate or lose current when not in use, therefore, with every day use recharging the battery is necessary about every month or so, it can be recharged at home in a few minutes, **no electricity or machinery is required** for this operation, recharging material can usually be obtained around your home or can be bought for a few cents. These batteries when charged weigh about 84 pounds and if properly installed will last **for years.** Each battery making outfit consists of a completely wired switch board, battery connectors, wire, instructions and plan for making, installing and recharging the battery and complete chemicals. **Special introductory price, $1.00, prepaid.** Outside the U. S., $1.25.



NEW MODEL TELEPHONES $2.00

The most useful and inexpensive wall telephones yet developed. Good use can be found for a set of these telephones in many homes, and in office, store or shop, indoors and outdoors; they save many steps and much time. You can easily install these new model telephones and have your own private line with no operators to bother or listen to your conversation. They are thoroughly practical and serviceable all around telephones. Their construction is simple and neat, nothing to break or to get out of order, a child can operate them with ease, they will give satisfactory service at any distance up to 5 miles, and even at that distance the voice will be perfectly plain and understandable as with the **regular commercial telephone.** These new model telephones are electrically operated, two batteries will operate a set of phones for a long time, the cabinets are made of polished oak and finished with a durable varnish and fitted with excellent receivers and transmitters, fine workmanship and construction throughout, **guaranteed to operate** under all conditions. We are offering the New Model Telephones at an **exceptionally low price.** Each telephone set consists of two New Model Telephones, calling system, wire, instructions and diagram for installing. **Special price to introduce $2.00, prepaid.** Outside the U. S. $2.25. **FREE**—We want every reader to own a New Model Telephone set, so we are going to give away a 2-cell battery **FREE** to every purchaser of a New Model Telephone Set.

ELECTRIC LIGHT IN YOUR HOME $1.00

The latest electric light, no batteries to buy or electric bills to pay. Anyone can install and maintain this midget electric light. Safe, simple and inexpensive. No more smoke and smell, no wicks or oil, no chimneys to clean or break, just as safe in the barn, garage and clothes closet as in any open room, always ready for use, day or night. A touch on the switch and you instantly have a **bright electric light.** No matter where you live this light can be installed. It is not affected by heat or cold. Many homes have installed this electric light in their halls, closets, pantries, barns, sheds, cellars, garages, etc., with good results. It is an extremely useful light which no household should be without. The reason for this bright electric light is that the lighting bulb is fitted with a drawn Tungsten filament wire which is much more efficient and durable, besides giving a **300% increase in light** as compared with the ordinary carbon lamp. The power system furnished with this lighting outfit is somewhat similar to the electric power battery described above. Each electric light outfit includes the following: Complete directions and plans, copper wire, insulated wire holders, knife switch, drop light fixture with socket, friction tape, battery protector, maroon shade, national mazda globe. Our dry battery compound, which assists in renewing and supplying the current and our current renewing system with which you can **renew the current at home without expense.** With every day use one recharge usually lasts two to three weeks. This electric lighting outfit is undoubtedly the most practical and durable electric light of low cost and long service ever devised. **Special price to introduce these electric lighting outfits $1.00, prepaid.** Outside the U. S. $1.25.

Our Guarantee—It is our intention that every article described above will reach you exactly as described, that it will satisfy you perfectly, that it represents full value for the money you paid or we will refund your money.

Just to introduce our new line of goods we are offering them at these greatly reduced prices. We only have a limited number of the above described goods at these prices. **Order now,** direct from this ad. We guarantee safe delivery anywhere for additional 10 cents on each item.

A. B. C. PRODUCTS CO. 1 JOHNSON & 13th STS. CHICAGO

YOU HAVE A BEAUTIFUL FACE

BUT YOUR NOSE?



BEFORE **AFTER**

IN THIS DAY AND AGE attention to your appearance is an absolute necessity if you expect to make the most out of life. Not only should you wish to appear as attractive as possible, for your own self-satisfaction, which is alone well worth your efforts, but you will find the world in general judging you greatly, if not wholly, by your "*looks*," therefore it pays to "look your best" at all times.

Permit no one to see you looking otherwise; it will injure your welfare! Upon the impression you constantly make rests the failure or success of your life. Which is to be your ultimate destiny? My new *Nose-Shaper*, "TRADOS" (Model 24) corrects now ill-shaped noses without operation, quickly, safely and permanently. Is pleasant and does not interfere with one's daily occupation, being worn at night.

Write today for free booklet, which tells you how to correct ill-shaped noses without cost if not satisfactory

M. TRILETY, Face Specialist **K-1283 Ackerman Bldg., Binghamton, N. Y.**

ALL THE PARTS AND PLANS

HERE BOYS

Model A, $1.00. Model B, $1.50. Completed Model, A, $1.50, B, $2.00. Made like a SKEETER, no other will fly. No other can BEAT her, all others so die; Made in a JIFFY, fly it in the Park, Maiden so NIFTY, fun as Noah's Ark!

Prepaid—Don't send stamps.

NIFTY NOVELTY & TOY CO. Newark, N. J.

LEARN WATCHMAKING

By our PROFIT SHARING plan watchmakers earn from $40 to $80 per week and the demand for competent men is greater than the supply. Write for free book.

CHICAGO SCHOOL OF WATCHMAKING
Dept. 30, 190 N. State Street, Chicago.

My Inventions

By Nikola Tesla

(*Continued from page* 556)

this is also true, and perhaps more so, of certain defects in the brain which deprive the automaton, more or less, of that vital quality and cause it to rush into destruction. A very sensitive and observant being, with his highly developed mechanism all intact, and acting with precision in obedience to the changing conditions of the environment, is endowed with a transcending mechanical sense, enabling him to evade perils too subtle to be directly perceived. When he comes in contact with others whose controlling organs are radically faulty, that sense asserts itself and he feels the "cosmic" pain. The truth of this has been borne out in hundreds of instances and I am inviting other students of nature to devote attention to this subject, believing that thru combined and systematic effort results of incalculable value to the world will be attained.

Dr. Tesla's First Automaton.

The idea of constructing an automaton, to bear out my theory, presented itself to me early but I did not begin active work until 1893, when I started my wireless investigations. During the succeeding two or three years a number of automatic mechanisms, to be actuated from a distance, were constructed by me and exhibited to visitors in my laboratory. In 1896, however, I designed a complete machine capable of a multitude of operations, but the consummation of my labors was delayed until late in 1897. This machine was illustrated and described in my article in the Century Magazine of June, 1900, and other periodicals of that time and, when first shown in the beginning of 1898, it created a sensation such as no other invention of mine has ever produced. In November, 1898, a basic patent on the novel art was granted to me, but only after the Examiner-in-Chief had come to New York and witnesst the performance, for what I claimed seemed unbelievable. I remember that when later I called on an official in Washington, with a view of offering the invention to the Government, he burst out in laughter upon my telling him what I had accomplished. Nobody thought then that there was the faintest prospect of perfecting such a device. It is unfortunate that in this patent, following the advice of my attorneys, I indicated the control as being effected thru the medium of a single circuit and a well-known form of detector, for the reason that I had not yet secured protection on my methods and apparatus for individualization. As a matter of fact, my boats were controlled thru the joint action of several circuits and interference of every kind was excluded. Most generally I employed receiving circuits in the form of loops, including condensers, because the discharges of my high-tension transmitter ionized the air in the hall so that even a very small aerial would draw electricity from the surrounding atmosphere for hours. Just to give an idea, I found, for instance, that a bulb 12" in diameter, highly exhausted, and with one single terminal to which a short wire was attached, would deliver well on to one thousand successive flashes before all charge of the air in the laboratory was neutralized. The loop form of receiver was not sensitive to such a disturbance and it is curious to note that it is becoming popular at this late date. In reality it collects much less energy than the aerials or a long grounded wire, but it so happens that it does away with a number of defects inherent to the present wireless devices. In demonstrating my invention before audiences, the visitors were requested to ask any questions, however involved, and the automaton

NEWS-WRITING PAYS

The **WHITNEY COURSE IN JOURNALISM** quickly and thoroughly develops your latent ability and prepares you for this fascinating work. Highly recommended by authorities. Cost moderate; terms easy.

Send for Prospectus giving full particulars and outlining every subject taught.

American Institute of Journalism
"A Newspaper School Run by Newspaper Men"
Dept. E, 22 Hawley St., Boston, Mass.

Become a
MOTION PICTURE OPERATOR

Prepare yourself for an all-year-round, steady, well-paying position; salary $30 weekly and upward; cost of instruction, $15; $5.00 will start you. Day and Evening Classes. No charge for positions secured.

Moving Picture Operators School
644 8th Ave., Near 42d St., New York

AVIATION Information FREE

Send us your name and address for full information regarding the Aviation and Airplane business. Find out about the many great opportunities now open and how we prepare you at home, during spare time, to qualify. Our new book "Opportunities in the Airplane Industry" also sent free if you answer at once.
AMERICAN SCHOOL OF AVIATION
Dept. 8037 431 S. Dearborn St. CHICAGO

Bewitching Pictures!

Exact reproductions from original Photographs, already for mounting and framing. If you are a lover of the beautiful in art, here is just what you have long wanted. For a short time we make a special introductory offer, as follows: **Send 25c and we will send you eight selected beauties** and our beautifully illustrated catalog. After seeing the samples you will want more.
PARIS NOVELTY COMPANY
Dept. P. 1, 26 E. Adams St. Chicago

How to Get Rid of Moles

A simple, safe home treatment—15 years' success in my practice. Moles (also BIG growths) **Dry Up.**

Ask for Free Booklet of Full Particulars

WM. DAVIS, M. D.
4140 State Street Perth Amboy, N.J.

BE HAPPY ! !
YOU NEED NOT
STAMMER

Many have been cured by my system. Complete cure in from four to five weeks' treatment. Terms according to arrangements.
Write or call for details and references.
CHARLES PFERDMENGES,
25 E. Washington St. Chicago
Tel. Rand. 3431

If you are earning less than **$50.00 PER WEEK** and like to draw—you should study
COMMERCIAL ART
Leading Art Managers—the men who know—recommend us and employ our students. We will guarantee to make you successful—Learn at home in your spare time—or in our resident school—Day or evening.
Write for FREE illustrated catalogue.
COMMERCIAL ART SCHOOL
703, 116 So. Michigan Ave., Chicago, Ill.

"Hang Your Own Lighting Fixtures"

One Light Bracket $1.05—4 Light Shower $6.15
Semi-Bowls $5.85—Plate & Ball 85c, complete with glassware, Wired, Fine finishes. Send for Photos complete line.

ERIE FIXTURE SUPPLY CO.
Sta. C., Erie, Pa.

LUMINOUS WATCH, tells time in dark, guaranteed 2 years, also other valuable presents, cameras, air rifles, talking machines, typewriters, telescopes, given absolutely free for selling our art and religious pictures at 10c. Send for 25, when sold, send money and receive premium.
SPENCER PUB. CO.
Dept. 303 Chicago

Be FREE From STAMMERING
Home Exercise Course. Results GUARANTEED or NO PAY. Write for full particulars.
Sutherland Course, Educational Bldg., 70-5th Ave., N. Y.

would answer them by signs. This was considered magic at that time but was extremely simple, for it was myself who gave the replies by means of the device.

At the same period another larger tetautomatic boat was constructed, a photograph of which is shown in this number of the ELECTRICAL EXPERIMENTER. It was controlled by loops, having several turns placed in the hull, which was made entirely water-tight and capable of submergence. The apparatus was similar to that used in the first with the exception of certain special features I introduced as, for example, incandescent lamps which afforded a visible evidence of the proper functioning of the machine.

Telautomatics of the Future.

These automata, controlled within the range of vision of the operator, were, however, the first and rather crude steps in the evolution of the Art of Telautomatics as I had conceived it. The next logical improvement was its application to automatic mechanisms beyond the limits of vision and at great distance from the center of control, and I have ever since advocated their employment as instruments of warfare in preference to guns. The importance of this now seems to be recognized, if I am to judge from casual announcements thru the press of achievements which are said to be extraordinary but contain no merit of novelty, whatever. In an imperfect manner it is practicable, with the existing wireless plants, to launch an aeroplane, have it follow a certain approximate course, and perform some operation at a distance of many hundreds of miles. A machine of this kind can also be mechanically controlled in several ways and I have no doubt that it may prove of some usefulness in war. But there are, to my best knowledge, no instrumentalities in existence today with which such an object could be accomplished in a precise manner. I have devoted years of study to this matter and have evolved means, making such and greater wonders easily realizable. As stated on a previous occasion, when I was a student at college I conceived a flying machine quite unlike the present ones. The underlying principle was sound but could not be carried into practice for want of a prime-mover of sufficiently great activity. In recent years I have successfully solved this problem and am now planning aerial machines devoid of sustaining planes, ailerons, propellers and other external attachments, which will be capable of immense speeds and are very likely to furnish powerful arguments for peace in the near future. Such a machine, sustained and propelled entirely by reaction, is shown on one of the pages and is supposed to be controlled either mechanically or by wireless energy. By installing proper plants it will be practicable to project a missile of this kind into the air and drop it almost on the very spot designated, which may be thousands of miles away. But we are not going to stop at this. Telautomata will be ultimately produced, capable of acting as if possesst of their own intelligence, and their advent will create a revolution. As early as 1898 I proposed to representatives of a large manufacturing concern the construction and public exhibition of an automobile carriage which, left to itself, would perform a great variety of operations involving something akin to judgment. But my proposal was deemed chimerical at that time and nothing came from it.

At present many of the ablest minds are trying to devise expedients for preventing a repetition of the awful conflict which is only theoretically ended and the duration and main issues of which I have correctly predicted in an article printed in the *Sun* of December 20, 1914. The proposed League is not a remedy but, on the con-

(*Continued on page* 603)

BOYS

Learn Drafting

Employers everywhere are looking for skilled draftsmen. They are offering good salaries to start with splendid chances for advancement.

Drafting offers exceptional opportunities to a young man because drafting itself not only commands good pay, but it is the first step toward success in Mechanical or Structural Engineering or Architecture. And drafting is just the kind of work a boy likes to do. There is an easy delightful way in which you can learn right at home in spare time. For 28 years the International Correspondence Schools have been giving boys just the training they need for success in Drafting and more than 200 other subjects. Thousands of boys have stepped into good positions through I. C. S. help, but never were opportunities so great as now.

Let the I. C. S. help *you*. Choose the work you like best in the coupon, then mark and mail it. This doesn't obligate you in the least and will bring you information that may start you on a successful career. This is your chance. Don't let it slip by. Mark and mail this coupon now.

TEAR OUT HERE
INTERNATIONAL CORRESPONDENCE SCHOOLS
BOX 6204, SCRANTON, PA.

Explain, without obligating me, how I can qualify for the position, or in the subject, *before* which I mark X.

☐ MECHANICAL DRAFTING	☐ SALESMANSHIP
☐ STRUCTURAL DRAFTING	☐ ADVERTISING
☐ SHIP DRAFTING	☐ Show Card Writer
☐ ELECTRICAL DRAFTING	☐ Sign Painter
☐ ARCHITECTURAL DRAFTING	☐ ILLUSTRATING
☐ SHEET METAL DRAFTING	☐ Cartooning
☐ BOILER MAKER DRAFTING	☐ BOOKKEEPER
☐ BRIDGE DRAFTING	☐ Stenographer and Typist
☐ MACHINE DESIGN	☐ Cert. Public Accountant
☐ ELECTRICAL ENGINEER	☐ TRAFFIC MANAGER
☐ Electric Lighting and Railways	☐ Railway Accountant
☐ Electric Wiring	☐ GOOD ENGLISH
☐ Telegraph Engineer	☐ Teacher
☐ Telephone Work	☐ Common School Subjects
☐ MECHANICAL ENGINEER	☐ Mathematics
☐ Machine Shop Practice	☐ CIVIL SERVICE
☐ Gas Engine Operating	☐ Railway Mail Clerk
☐ CIVIL ENGINEER	☐ AUTOMOBILE OPERAT'G
☐ Surveying and Mapping	☐ Auto Repairing
☐ STATIONARY ENGINEER	☐ PLUMBING AND HEATING
☐ Marine Engineer	☐ Textile Overseer or Supt.
☐ ARCHITECT	☐ CHEMIST
☐ Contractor and Builder	☐ Navigation ☐ Spanish
☐ Concrete Builder	☐ AGRICULTURE ☐ French
☐ Structural Engineer	☐ Poultry Raising ☐ Italian

Name_____
Present Occupation_____
Street and No._____
City_____ State_____

BUILD A $100 PHONOGRAPH
Assemble your own Phonograph
Do it yourself easily. Have the finest machine. Astounding saving. We give you the phonograph secrets. Complete instructions 10 cents.
ELECTRO MECHANICAL PARTS CO.
160 N. Wells St. CHICAGO

MATHEMATICS MADE EASY

The Arcascope—the Combination Triangle with a Brain—will multiply, divide, figure percentage and proportion, solve all problems in trigonometry and geometry, draw symmetrical figures, plot arcs, etc. Superior to any slide rule. Simple to operate. Also includes a TRANSPARENT TRIANGLE, PROTRACTOR and THREE RULES. Used at Columbia University, West Point, U. S. Aeronautic Schools, etc. Only 85 cents Postpaid. Order today before you forget.
Dept. J. L. J. LEISHMAN CO., Ogden, Utah

SAVE 25% to 60%
on slightly used
GRAFLEX-KODAKS
Cameras and Lenses of every description. Equal to new. Save money. Write now for **Free Bargain Book and Catalog** listing hundreds of money-saving bargains in slightly used and new cameras and supplies. **All goods sold on 10 days' Free Trial.** Money back if not satisfied. You take no chances dealing with us. We have been in the photographic business over 16 years. Write now.
CENTRAL CAMERA CO., Dept. 17 A 124 S. Wabash Ave., Chicago

GO INTO **MOVING PICTURE BUSINESS**
Small Capital Starts You
Our Catalog FREE. Show you how to earn $25.00 to $50.00 per day
on our easy payment plan. Begin now and get your share. We sell everything. Write today.
Atlas Moving Picture Co.
Dept. 50 538 S. Dearborn St., Chicago

Learn the Sign-Show Card Business
Big field—unlimited possibilities—increasing demand for men with creative ideas. Our course develops ability and originality. Work intensely interesting.
EARN $25. TO $75. WEEKLY
You can do it if ambitious. Successful graduates everywhere. Our course covers every phase of work completely and thoroughly. Our graduates command big salaries. Write for catalog, samples, guarantee and Free Outfit Offer.
DETROIT SCHOOL OF LETTERING, 490 D. S. L. Bldg. Detroit, Mich.

Fun, Magic and Mystery!
56 Feats in Magic, 250 New Jokes, 21 Puzzles, 1 Fortune Telling Tablet, 52 Money-Making Secrets, 15 Card Tricks, 71 Toasts, 58 Verses in Comic Poetry, 10 Funny Readings, 41 Epitaphs, and 11 Parlor Pastimes. You get all the above-mentioned and our big illustrated Catalog of 125 Magic Tricks for only 10 cents. Write today.
MYSTIC MFG. CO.,
909 Springwells Ave., Detroit, Mich.

SECURE A MOTOR-CYCLE AT LOW COST

by putting a RELIABLE STEFFEY MOTOR on your wheel. Easy to attach. Costs less to run than an expensive motorcycle. Write at once and secure low factory prices.
STEFFEY MFG. CO.
Dept. E, 5025 Brown St., Philadelphia, Pa

Learn Autos and Tractors

Wonderful opportunities constantly offered trained men; we train you thoroughly to start your own business or make good money as motor expert, driver, shop foreman, etc.
5000 Graduates making good. Catalog Free.
Cleveland Automobile School, 1807 E. 24th St., Cleveland, O.

$3 AND A month **$4 WILL BUY**
A Beautifully Reconstructed
TYPEWRITER
With Every Modern Writing Convenience
WRITE TODAY FOR ILLUSTRATED CIRCULAR Explaining Try-Before-You-Buy Plan
HARRY A. SMITH, 738-218 North Wells St., Chicago, Ill.

WOULD YOU KNOW WHAT TO DO?
TO HAVE YOUR WISHES COME TRUE?
TO BE HAPPY AND SUCCESSFUL?
TO FEEL THE THRILL OF NEW POWERS?
TO HAVE A WINNING PERSONALITY?
Our system of Personal Development has shown thousands. It can show YOU. First lesson in SUCCESS, and your Personality Sketch for 10c and birthdate.
THOMSON-HEYWOOD CO.
Dept. 350, Chronicle Bldg., San Francisco, Cal.

You can be quickly cured, if you
STAMMER
Send 10 cents coin or stamps for 70-page book on Stammering and Stuttering, "Its Cause and Cure." It tells how I cured myself after stammering for 20 years.
Benjamin N. Bogue, 759 Bogue Building, Indianapolis

Dollars in Hares
We pay $7.00 to $9.50 a pair and express charges. **Big Profits.** We furnish guaranteed high grade stock and buy all you raise. Use back yard, barn, cellar, attic. Contract and Illustrated Catalog Free.
STANDARD FOOD & FUR ASS'N
303Z Broadway New York

GENUINE MOVING PICTURE MACHINE and film, also other valuable presents, watches, air rifles, cameras, talking machines, telescopes, typewriters, given absolutely free for selling our art and religious pictures at 10c. Send for 25, when sold send money and receive premium.
Spencer Pub. Co., Dept. 302, Chicago

My Inventions

By Nikola Tesla

(*Continued from page* 601)

trary, in the opinion of a number of competent men, may bring about results just the opposite. It is particularly regrettable that a punitive policy was adopted in framing the terms of peace, because a few years hence it will be possible for nations to fight without armies, ships or guns, by weapons far more terrible, to the destructive action and range of which there is virtually no limit. Any city, at a distance, whatsoever, from the enemy, can be destroyed by him and no power on earth can stop him from doing so. If we want to avert an impending calamity and a state of things which may transform this globe into an inferno, we should push the development of flying machines and wireless transmission of energy without an instant's delay and with all the power and resources of the nation.

What the X-Rays Show

(*Continued from page* 510)

hardly ever be suspected as being caused by the small and apparently infinitesimal "toothache." The modern dentist not only needs an X-ray, but he practically *must* have one of these scientific apparatus in order to be sure that every tooth is sound.

In figure 10 is shown one of the latest advances in X-rays—the "Movie X-ray." This branch of X-ray science has only been developed to a very slight extent, and gives promise of really wonderful possibilities in the near future. A year or so ago there was exhibited before a body of surgeons and physicians in New York City an *X-ray motion picture* in which the action of various organs, functioning in a live person, were shown, a bismuth meal having first been ingested; the intestines were shown functioning as well as the heart. It is not commonly known that with the modern X-ray, provided with an up-to-date tube of the Coolidge tube, and excited by a 5 to 10 kilowatt, 100,000-volt transformer, and the other necessary appurtenances, practically every part of the body and its organs may be seen on the fluoroscope, or otherwise on the photographic negative or skiagraph. This includes the heart, lungs, stomach, ulcers of the stomach, the intestines, the appendix, gall stones, the gall bladder, and many other ailments and organs within the body which sometimes have to be diagnosed and operated on in a very short length of time, or otherwise the death of the person would often result. *X-ray-therapy* is a new field being investigated today, and gives much promise in the treatment of cancer and various skin diseases.

X-raying tobacco in order to kill organisms, especially the *tobacco weevil,* has been carried on for several years in a number of large tobacco establishments. In this case, the tobacco in large bales is wheeled into an X-ray examination chamber on small trucks, see figure 12. In this manner the tobacco can be very rapidly X-rayed. The powerful rays from the bulb have the effect of killing the weevil even in its primary germinating state.

There are many other industrial uses of the X-ray which space does not allow us to mention here, but among which we may mention the X-raying of steel and copper ingots to analyze the structure and to detect flaws, such as cracks and air-pockets, and of coal for the purpose of extending our knowledge of geology.

HIGH SCHOOL COURSE IN TWO YEARS

YOU ARE BADLY HANDICAPPED if you lack High School training. You cannot attain business or social prominence. You are barred from a successful business career, from the leading professions, from well-paid civil service jobs, from teaching and college entrance. In fact, employers of practically all worth-while positions demand High School training. You can't hope to succeed in the face of this handicap. But you can remove it. Let the American School help you.

FIT YOURSELF FOR A BIG FUTURE This Course, which has been prepared by some of America's leading professors, will broaden your mind, and make you keen, alert and capable. It is complete, simplified and up-to-date. It covers all subjects given in a resident school and *meets all requirements* of a High School training. From the first lesson to the last you are carefully examined and coached.

USE SPARE TIME ONLY
Most people *idle* away *fifty* hours a week. Probably you do. Use only one-fifth of your wasted hours for study and you can remove your present handicap within *two years.* You will enjoy the lessons and the knowledge you will gain will well repay the time spent in study.

TAKE 10 LESSONS FREE So that you may see for yourself how thorough and complete our training is. We invite you to take *ten lessons* in the High School Course—or any Course of specialized training in the Coupon below—before deciding whether you wish to continue. If you are not then satisfied you are not out one cent. *We absolutely guarantee satisfaction.* On that basis you owe it to yourself to make this test.
Check and mail the coupon NOW for full particulars and Free Bulletin.

AMERICAN SCHOOL OF CORRESPONDENCE
Dept. H-267 Chicago, Illinois

TRAINING—THE KEY TO SUCCESS

Please explain how I can qualify for the position marked X

.....High School Graduate	.....Lawyer
.....Electrical Engineer	.....Business Manager
.....Elec. Light & Power Supt.	.....Certified Pub. Accountant
.....Hydroelectric Engineer	.....Accountant and Auditor
.....Telephone Engineer	.....Bookkeeper
.....Telegraph Engineer	.....Stenographer
.....Wireless Operator	.....Fire Insurance Expert
.....Architect	.....Sanitary Engineer
.....Building Contractor	.....Master Plumber
.....Civil Engineer	.....Heating and Vent. Engineer
.....Structural Engineer	.....Automobile Engineer
.....Mechanical Engineer	.....Automobile Repairman
.....Shop Superintendent	.....Airplane Mechanic
.....Steam Engineer	.....General Education Course
.....Draftsman and Designer	.....Common School Branches

Name.....
Address.....

The Effect of Statics on Wireless Transmission

By NIKOLA TESLA

Written for the ELECTRICAL EXPERIMENTER

A FEW statements regarding these phenomena, in response to a request of the ELECTRICAL EXPERIMENTER, may be useful at the present time in view of the increasing interest and importance of the subject.

The commercial application of the art has led to the construction of larger transmitters and multiplication of their number, greater distances had to be covered and it became imperative to employ receiving devices of ever increasing sensitiveness. All these and other changes have co-operated in emphasizing the trouble and seriously impairing the reliability and value of the plants. To such a degree has this been the case that conservative business men and financiers have come to look upon this method of conveying intelligence as one offering but very limited possibilities, and the Government has deemed it advisable to assume control. This unfortunate state of affairs, fatal to enlistment of capital and healthful competitive development, could have been avoided had electricians not remained to this day under the spell of a delusive theory and had the practical exploiters of this advance not permitted enterprise to outrun technical competence.

With the publication of Dr. Heinrich Hertz's classical researches it was an obvious inference that the dark rays investigated by him could be used for signalling purposes, as those of light in heliography, and the first steps in this direction were made with his apparatus which, in 1896, was found capable of actuating receivers at a distance of a few miles. Three years prior to this, however, in lectures before the Franklin Institute and National Electric Light Association, I had described a wireless system radically opposite to the Hertzian in principle inasmuch as it depended on currents conducted thru the earth instead of on radiations propagated thru the atmosphere, presumably in straight lines.

The apparatus then outlined by me consisted of a transmitter comprising a primary circuit excited from an alternator or equivalent source of electrical energy and a high potential secondary resonant circuit, connected with its terminals to ground and to an elevated capacity, and a similar tuned receiving circuit including the operative device. On that occasion I exprest myself confidently on the feasibility of flashing in this manner not only signals to any terrestrial distance but transmitting power in unlimited amounts for all sorts of industrial purposes. The discoveries made and experimental results attained I made with a wireless power-plant erected in 1899, some of which were disclosed in the Century Magazine of June, 1900, and several U. S. patents subsequently granted to me have, I believe, borne-out strikingly my foresight. In the meantime the Hertzian arrangements were gradually modified, one feature after another being abandoned, so that now not a vestige of them can be found and my system of four tuned circuits has been universally adopted, not only in its fundamentals but in every detail as the "quenched sparks", "ticker", "tone wheel", high frequency and rotating field alternators, forms of discharges and mercury breaks, frequency changers, coils, condensers, regulating methods and devices, etc. This fact would give me supreme satisfaction were it not that the engineers, misinterpreting the nature of the effects, are making installments so defective in construction and mode of operation as to preclude the possibility of the great realization which might be brought within easy reach by proper application of the underlying principles and one of which—the most desirable at present—is the complete elimination of all static and other interference.

Tesla's Static Elimlnator, Patented and Used by Him over Twenty Years Ago. It Will Be Fully Described In an Early Issue of the Electrical Experimenter

During the past few years several emphatic announcements have been made that a perfect solution of this problem had been discovered, but it was manifest from a casual perusal of these publications that the experts were ignoring certain truths of vital bearing on the question, and so long as this was the case no such claim could be substantiated. I achieved early success by keeping these steadily in mind and applying my efforts from the outset in the right and correct scientific direction.

I may contribute to the clearness of the subject in answering a question which I have been asked by the Editors of the ELECTRICAL EXPERIMENTER with reference to the report contained in the last issue, that signals had been received around the globe. an achievement the practicability of which I have fully demonstrated by experiment eighteen years ago.

The question is, how can Hertz waves be conveyed to such a distance in view of the curvature of the earth? A few words will be sufficient to show the absurdity of the prevailing opinion propounded in text books.

We are living on a conducting globe surrounded by a thin layer of insulating air, above which is a rarefied and conducting atmosphere. If the earth is represented by a sphere of 12½" radius, then the layer which may be considered insulating for high frequency currents of great tension is less than 1/64 of an inch thick. It is held that the Hertz waves, emanating from a transmitter, get to the distant receiver by successive reflections. The utter impossibility of this will be evident when it is shown by a simple calculation that the amount of

(*Continued on page* 658)

"THE SET UNCLE SAM USES"



"Uncle Sam" needs thousands of operators and is calling for more all the time. Here is your chance to become an expert telegrapher at a small cost. The practice outfit shown here is exactly the same as used by the United States Signal Corps and comprises the following:

A highly polished mahogany finished wood base, a real high frequency buzzer giving a high note, with nickel-plated case, regulation nickel-plated steel lever key. **Also brass etched plate showing the three International codes mounted on the base for quick practice.** A new feature not found on any other set. You simply cannot mislay this code.

This outfit quickly gives you speed, and enables you to learn telegraphy, Morse or wireless code in a short time. Special attention is called to the buzzer which gives a clear high note, not a rattling noise as many inferior outfits now on the market. **IMMEDIATE DELIVERY.** We ship the same day that order is received. Your money refunded if you are not satisfied.

Price as illustrated. Shipping weight 2 lbs. Size over all 5"x2"x7¼". **$2.80** Include sufficient postage for mailing. Send for free illustrated folder.

THE TEWNO CO. 150 CHAMBERS ST., NEW YORK

The Breakers

Atlantic City's Newest Fire-Proof Hotel

Ocean Front. Unusually attractive during the Autumn and Winter seasons.

American and European Plans



Luxurious lobbies, spacious verandas and sun parlors overlooking the ocean. Charming afternoon musicales and evening concerts. A palatial residence for those seeking rest and recreation. Sea water baths. Fireproof garage. Illustrated booklet sent on request.

MAGNETIC RECTIFIER
Patented April 18, 1916



YOUR lights will shine and sparkle with delight, your horn will squawk raucously and your engine will turnover enthusiastically if you play godfather to your starting and lighting battery by giving it an

F-F BATTERY BOOSTER

A few minutes of your time once a month or so will rejuvenate your battery and prolong indefinitely its working life.

Write today for bulletin No. 12 and obtain a prescription for this battery panacea.

The France Manufacturing Company
10325 Berea Road, Cleveland, O.

Super-Sensitive Microphone Only $7.50

This instrument is offered at an extremely low price. It is excellent for building your own radio amplifier. Can also be used in many experiments where a sensitive microphone is required.

DETECTAGRAPH $15

This detecting instrument of **marvelous sensitivity** can he used for detecting secret conversations. Outfit consists of Sensitive Transmitter, 25 ft. Black Cord, Receiver, Headhand, Case and Battery.

Send for One Today and Convince Yoursel

GASTON BOISSONNAULT
26 Cortlandt Street New York
Makers of Super-Sensitive Microphone Apparatus



DETECTAGRAPH $15

'A WIRELESS OUTFIT FOR 20c

We at last have a low-priced wireless telegraph system. With this outfit you can receive and send messages to your friends and sweethearts or neighbors across the hall, etc. This outfit consists of two mechanical snapper sounders, one for each station; also two codes of Morse Alphabet, which, with practice, will enable you to operate any telegraph system. Complete, postpaid, for 20c in coin.

THE A. B. CO. 1305 Peoria St. CHICAGO

DEAFNESS IS MISERY

I know because I was Deaf and had Head Noises for over 30 years. My invisible Anti-septic Ear Drums restored my hearing and stopped Head Noises, and will do it for you. They are Tiny Megaphones. Cannot be seen when worn. Easy to put in, easy to take out. Are "Unseen Comforts." Inexpensive. Write for Booklet and my sworn statement of how I recovered my hearing. A. O. LEONARD
Suite 369 70 5th Ave., N. Y. City

THE EFFECT OF STATICS ON WIRELESS TRANSMISSION.

(*Continued from page 627*)

energy received, even if it could be collected in its totality, is infinitesimal and would not actuate the most sensitive instrument known were it magnified many million times. The fact is these waves have no perceptible influence on a receiver if situated at a much smaller distance. It should be remembered, moreover, that since the first attempts the wave lengths have been increased until those advocated by me were adopted, in which this form of radiation has been reduced to one-billionth.

When a circuit, connected to ground and to an elevated capacity oscillates, two effects separate and distinct are produced; Hertz waves are radiated in a direction at right angles to the axis of symmetry of the conductor, *and simultaneously a current is passed through the earth.* The former propagates with the speed of light, the latter with a velocity proportionate to the cosecant of an angle which from the origin to the opposite point of the globe varies from zero to 180°. Expressed in words, at the start the speed is infinite and diminishes, first rapidly and then slowly until a quadrant is traversed when the current proceeds with the speed of light. From that region on the velocity gradually increases, becoming infinite at the opposite point of the globe. In a patent granted to me in April, 1905, I have summed up this law of propagation in the statement that the projections of all half waves on the axis of symmetry of movement are equal, which means that the successive half waves, tho of different length, cover exactly the same area. In the near future many wonderful results will be obtained by taking advantage of this fact.

There is a vast difference between these two forms of wave movement in their bearing on the transmission. The Hertz waves represent energy which is radiated and unrecoverable. The current energy, on the other hand, is preserved and can be recovered theoretically, at least, in its entirety. If the experts will free themselves from the illusions under which they are laboring, they will find that to overcome static disturbances all that is needed is a properly constructed transmitter and receiver without any additional devices or preventives. I have, however, devised several forms of apparatus eliminating statics even in the present defective wireless installations in which they are magnified many times. Such a form of instrument which I have used successfully is shown in the annexed photograph. These phenomena have been studied by me for a number of years and I have found that there are nine or ten different causes tending to intensify them, and in due course I shall give a full description of the various improvements I have made, in the ELECTRICAL EXPERIMENTER. For the present I would only point out that in order to perfectly eliminate the static interference, it is indispensable to redesign the whole wireless apparatus as now employed. The sooner this is understood the better it will be for the further evolution of the Art.

A means of making use of the electric magnet under water has been devised in Japan, and it promises to be of great assistance in locating sunken vessels, to recover which salvage operations on a big scale are expected after the war.

With the aid of special oxygen masks airplane experts believe that air fighters will be able to carry on battles five miles above the earth.

Famous Scientific Illusions

By NIKOLA TESLA

Written specially for the Electrical Experimenter

In this original and revolutionizing discussion, Nikola Tesla gives us something really new to think about. First—Does the moon rotate on its axis? Second—Is the Franklin pointed lightning rod correct in theory and operation? Third—Do wireless signals fly thru space by means of so-called Hertzian waves in the ether, or are they propagated thru the earth at prodigious velocity by means of earth-bound oscillations? World-famous conundrums these—questions which have been answered in many ways by some of the greatest scientists. Dr. Tesla explains these three predominant scientific fallacies in a masterly way, so that everyone can understand them.

THE human brain, with all its wonderful capabilities and power, is far from being a faultless apparatus. Most of its parts may be in perfect working order, but some are atrophied, undeveloped or missing altogether. Great men of all classes and professions—scientists, inventors, and hard-headed financiers—have placed themselves on record with impossible theories, inoperative devices, and unrealizable schemes. It is doubtful that there could be found a single work of any one individual free of error. There is no such thing as an infallible brain. Invariably, some cells or fibers are wanting or unresponsive, with the result of impairing judgment, sense of proportion, or some other faculty. A man of genius eminently practical, whose name is a household word, has wasted the best years of his life in a visionary undertaking. A celebrated physicist was incapable of tracing the direction of an electric current according to a childishly simple rule. The writer, who was known to recite entire volumes by heart, has never been able to retain in memory and recapitulate in their proper order the words designating the colors of the rainbow, and can only ascertain them after long and laborious thought, strange as it may seem.

Our organs of reception, too, are deficient and deceptive. As a semblance of life is produced by a rapid succession of inanimate pictures, so many of our perceptions are but trickery of the senses, devoid of reality. The greatest triumphs of man were those in which his mind had to free itself from the influence of delusive appearances. Such was the revelation of Buddha that self is an illusion caused by the persistence and continuity of mental images; the discovery of Copernicus that, contrary to all observation, this planet rotates around the sun; the recognition of Descartes that the human being is an automaton, governed by external influence and the idea that the earth is spherical, which led Columbus to the finding of this continent. And tho the minds of individuals supplement one another and science and experience are continually eliminating fallacies and misconceptions, much of our present knowledge is still incomplete and unreliable. We have sophisms in mathematics which cannot be disproved. Even in pure reasoning, free of the shortcomings of symbolic processes, we are often arrested by doubt which the strong-



Fig. 1

It Is Well Known That the Moon, M, Always Turns the Same Face Toward the Earth, E, as the Black Arrows Indicate. The Parallel Rays From the Sun Illuminate the Moon in Its Successive Orbital Positions as the Unshaded Semi-circles Indicate. Bearing This in Mind, Do You Believe That the Moon Rotates on Its Own Axis?



Fig. 2.—Tesla's Conception of the Rotation of the Moon, M, Around the Earth, E; the Moon, In This Demonstration Hypothesis, Being Considered as Embedded in a Solid Mass, M_1. If, As Commonly Believed, the Moon Rotates, This Would Be Equally True For a Portion of the Mass M_2, and the Part Common to Both Bodies Would Turn Simultaneously in "Opposite" Directions.

FOR over a century and a half the whole world, educated and otherwise, thought that the moon revolved around its axis. Nikola Tesla in the present highly instructive article disproves that theory and will convince scientists and all others alike that the moon does no such thing.

For thousands of years it was thought that the sun and stars revolved around the earth and all kinds of experimental proofs were furnished to substantiate this theory. The illustrious Galileo thought different, and everyone today knows that the earth revolves around the sun.

So it is with Tesla's discovery. Tesla also, in the second part of the present paper, shows us that the ancient and time-worn theory advanced by Benjamin Franklin as to the lightning conductor is not substantially correct as viewed by latter day science. It will come as a shock even to our professors that the lightning rod actually aids the lightning in hitting the building. The reason is that the lightning rod helps in ionizing (making conductive) the surrounding air.

Mr. Tesla has devised a lightning conductor with no points, and there is no doubt whatsoever that his theory is right. Scientists the world over will acknowledge this very shortly.

In a third section of the same paper Tesla explodes still another popular delusion, viz., that wireless waves follow the curvature of the earth when messages are transmitted, let us say from a point in the United States to a point in Europe. In his revolutionary arguments, supported by facts as well as by logic, Tesla shows why the currents do not travel around the earth but directly thru it. In other words, Tesla maintains that wireless communication is accomplished ONLY thru the medium of the earth itself. His contention seems very sound. If it were not so, let every wireless station, commercial or otherwise, do away with its ground connection. None could then operate as is well known, except perhaps over very limited distances.

Mr. Tesla's present article will arouse world-wide comment due to the revolutionary philosophy contained therein. We are sure our readers will appreciate Mr. Tesla's most timely and illuminating article on this but little understood subject.

Copyright, 1919, by E. P. Co. All rights reserved.

est intelligences have been unable to dispel. Experimental science itself, most positive of all, is not unfailing.

In the following I shall consider three exceptionally interesting errors in the interpretation and application of physical phenomena which have for years dominated the minds of experts and men of science.

I. The Illusion of the Axial Rotation of the Moon.

It is well known since the discovery of Galileo that the moon, in travelling thru space, always turns the same face towards the earth. This is explained by stating that while passing once around its mother-planet the lunar globe performs just one revolution on its axis. The spinning motion of a heavenly body must necessarily undergo modifications in the course of time, being either retarded by resistances internal or external, or accelerated owing to shrinkage and other causes. An unalterable rotational velocity thru all phases of planetary evolution is manifestly impossible. What wonder, then, that at this very instant of its long existence our satellite should revolve exactly so, and not faster or slower. But many astronomers have accepted as a physical fact that such rotation takes place. It does not, but only appears so; it is an illusion, a most surprising one, too.

I will endeavor to make this clear by reference to Fig. 1, in which E represents the earth and M the moon. The movement thru space is such that the arrow, firmly attached to the latter, always occupies the position indicated with reference to the earth. If one imagines himself as looking down on the orbital plane and follows the motion he will become convinced that the moon *does* turn on its axis as it travels around. But in this very act the observer will have deceived himself. To make the delusion complete let him take a washer similarly marked and supporting it rotatably in the center, carry it around a stationary object, constantly keeping the arrow pointing towards the latter. Tho to his bodily vision the disk will revolve on its axis, such movement does not exist. He can dispel the illusion at once by holding the washer fixedly while going around. He will now readily see that the supposed axial rotation is only apparent, the impression being produced by successive changes of position in space.


ELECTROMAGNETIC HERTZ WAVES
RADIATED HORIZONTALLY FROM VERTICAL CONDUCTOR, SLIGHTLY AFFECTED BY CONDUCTING EARTH SURFACE
ENERGY UNRECOVERABLE
VELOCITY V= SPEED OF LIGHT
V₁=V cosec 0 = ∞
RESULTANT OSCILLATORY CURRENT THROUGH EARTH, SPEED V₁=V cosec α
ENERGY RECOVERABLE
V₁=V cosec 90°=V
V₁=V cosec 180°= − ∞

Fig. 9. THEORY.

But more convincing proofs can be given that the moon does not, and cannot revolve on its axis. With this object in view attention is called to Fig. 2, in which both the satellite, M, and earth, E, are shown embedded in a solid mass, M_1 (indicated by stippling) and supposed to rotate so as to impart to the moon its normal translatory velocity. Evidently, if the lunar globe could rotate as commonly believed, this would be equally true of any other portion of mass M_1, as the sphere M_2, shown in dotted lines, and then the part common to both bodies would have to turn *simultaneously in opposite directions*. This can be experimentally illustrated in the manner suggested by using instead of one, two overlapping rotatable washers, as may be conveniently represented by circles M and M_2, and carrying them around a center as E, so that the plain and dotted arrows are always pointing towards the same center. No further argument is needed to demonstrate that the two gyrations cannot co-exist or even be pictured in the imagination and reconciled in a purely abstract sense.

The truth is, the so-called "axial rotation" of the moon is a phenomenon deceptive alike to the eye and mind and devoid of physical meaning. It has nothing in common with real mass revolution characterized by effects positive and unmistakable. Volumes have been written on the subject and many erroneous arguments advanced in support of the notion. Thus, it is reasoned, that if the planet did *not* turn on its axis it would expose the whole surface to terrestrial view; as only one-half is visible, it *must* revolve. The first statement is true but the logic of the second is defective, for it admits of only one alternative. The conclusion is not justified as the same appearance can also be produced in another way. The moon does rotate, not on its own, **but about an axis passing thru the center of the earth, the true and only one.**

The unfailing test of the spinning of a mass is, however, the existence of


"ANALOGY"
HAND PUMP
G= PRESSURE INDICATOR GAGES
FLEXIBLE SPHERICAL ENVELOPE: FILLED WITH LIQUID OR GAS.
ANALOGY OF TESLA'S EARTH WAVE VIBRATION THEORY:
EACH PULSE OF THE PUMP IS FELT WITH EQUAL FORCE AT ALL POINTS OF THE SPHERE.
"REALIZATION"
THE WIRELESS LIGHT: PLACE A WIRE IN THE GROUND: THAT IS ALL
TESLA'S WIRELESS POWER FOR PROPELLING SHIPS AND AEROPLANES
TESLA'S WIRELESS TRANSMISSION THEORY
THE OSCILLATING ENERGY SURGES THRU THE EARTH TO EVERY POINT ON THE GLOBE. THUS ELECTRIC LIGHT, HEAT AND POWER CAN BE DRAWN AT ANY POINT OF THE EARTH FROM A UNIVERSAL CENTRAL STATION.

Tesla's World-Wide Wireless Transmission of Electrical Signals, As Well As Light and Power, Is Here Illustrated In Theory, Analogy and Realization. Tesla's Experiments With 100 Foot Discharges At Potentials of Millions of Volts Have Demonstrated That the Hertz Waves Are Infinitesimal In Effect and Unrecoverable; the Recoverable Ground Waves of Tesla Fly "Thru the Earth". Radio Engineers Are Gradually Beginning to See the Light and That the Laws of Propagation Laid Down by Tesla Over a Quarter of a Century Ago Form the Real and True Basis of All Wireless Transmission To-Day.

energy of motion. The moon is not possest of such *vis viva*. If it were the case then a revolving body as M_1 would contain mechanical energy other than that of which we have experimental evidence. Irrespective of this so exact a coincidence between the axial and orbital periods is, in itself, immensely improbable for this is not the permanent condition towards which the system is tending. Any axial rotation of a mass left to itself, retarded by forces external or internal, must cease. Even admitting its perfect control by tides the coincidence would still be miraculous. But when we remember that most of the satellites exhibit this peculiarity, the probability becomes infinitestimal.

Three theories have been advanced for the origin of the moon. According to the oldest suggested by the great German philosopher Kant, and developed by Laplace in his monumental treatise "Mécanique Céleste", the planets have been thrown off from larger central masses by centrifugal force. Nearly forty years ago Prof. George H. Darwin in a masterful essay on tidal friction furnished mathematical proofs, deemed unrefutable, that the moon had separated from the earth. Recently this established theory has been attacked by Prof. T. J. J. See in a remarkable work on the "Evolution of the Stellar Systems", in which he propounds the view that centrifugal force was altogether inadequate to bring about the separation and that all planets, including the moon, have come from the depths of space and have been captured. Still a third hypothesis of unknown origin exists which has been examined and commented upon by Prof. W. H. Pickering in "Popular Astronomy of 1907", and according to which the moon was torn from the earth when the later was partially solidified, this accounting for the continents which might not have been formed otherwise.

Undoubtedly planets and satellites have originated in both ways and, in my opinion, it is not difficult to ascertain the character of their birth. The following conclusions can be safely drawn:

1. A heavenly body thrown off from a larger one cannot rotate on its axis. The mass, rendered fluid by the combined action of heat and pressure, upon the reduction of the latter immediately stiffens, being at the same time deformed by gravitational pull. The shape becomes permanent upon cooling and solidification and the smaller mass continues to move about the larger one as tho it were rigidly connected to it except for pendular swings or librations due to varying orbital velocity. Such motion precludes the possibility of axial rotation in the strictly physical sense. The moon has never spun around as is well demonstrated by the fact that the most precise measurements have failed to show any measurable flattening in form.

2. If a planetary body in its orbital movement turns the same side towards the central mass this is a positive proof that it has been separated from the latter and is a true satellite.

3. A planet revolving on its axis in its passage around another cannot have been thrown off from the same but must have been captured.

Fig. 5


Highly rarefied medium (insulating).
Moderately rarefied conducting atmosphere above insulating stratum.
Dense thin insulating layer of air.

Fig. 6


60°
4143 miles along earth's surface
Earth and dense insulating air layer to scale
Thickness of layer 1/64 of an inch when radius of earth model = 12½ inches
EE

A Section of the Earth and Its Atmospheric Envelope Drawn to Scale. It Is Obvious That the Hertzian Rays Cannot Traverse So Thin a Crack Between Two Conducting Surfaces For Any Considerable Distance, Without Being Absorbed, Says Dr. Tesla, in Discussing the Ether Space Wave Theory.

II. The Fallacy of Franklin's Pointed Lightning-Rod.

The display of atmospheric electricity has since ages been one of the most marvelous spectacles afforded to the sight of man. Its grandeur and power filled him with fear and superstition. For centuries he attributed lightning to agents god-like and supernatural and its purpose in the scheme of this universe remained unknown to him. Now we have learned that the waters of the ocean are raised by the sun and maintained in the atmosphere delicately suspended, that they are wafted to distant regions of the globe where electric forces assert themselves in upsetting the sensitive balance and causing precipitation, thus sustaining all organic life. There is every reason to hope that man will soon be able to control this life-giving flow of water and thereby solve many pressing problems of his existence.

Atmospheric electricity became of special scientific interest in Franklin's time. Faraday had not yet announced his epochal discoveries in magnetic induction but static frictional machines were already generally used in physical laboratories. Franklin's powerful mind at once leaped to the conclusion that frictional and atmospheric electricity were identical. To our present view this inference appears obvious, but in his time the mere thought of it was little short of blasphemy. He investigated the phenomena and argued that if they were of the same nature then the clouds could be drained of their charge exactly as the ball of a static machine, and in 1749 he indicated in a publisht memoir how this could be done by the use of pointed metal rods.

(*Continued on page 728*)


MODE OF PROPAGATION OF THE CURRENT FROM THE TRANSMITTER THRU THE EARTH
SUN
MOON
EARTH
MOON'S SHADOW JUST TOUCHING; SPREADS OVER THE EARTH'S SURFACE WITH INFINITE SPEED
PLANE OF ECLIPTIC; SHADOW PASSES OVER THE EARTH WITH IT'S TRUE VELOCITY THRU SPACE
MOON'S SHADOW LEAVING THE EARTH AGAIN, REACHING INFINITE SPEED

Fig. 8.—This Diagram Illustrates How, During a Solar Eclipse, the Moon's Shadow Passes Over the Earth With Changing Velocity, and Should Be Studied In Connection With Fig. 9. The Shadow Moves Downward With Infinite Velocity at First, Then With Its True Velocity Thru Space, and Finally With Infinite Velocity Again.

BE A BOY CHEMIST

Test water, foods and other things you use and wear. Make soap, ink, dye; fire-proof cloth and wood, and work hundreds of useful, fascinating experiments just like a real chemist. Perform weird, puzzling tricks of chemical magic. You can, with "CHEMCRAFT". Outfits contain all chemicals and laboratory supplies to work each experiment many times; also a Manual of Instruction. "CHEMCRAFT" is absolutely harmless; made by a practical chemist and is scientifically correct.

Chemcraft No. 1—$1.50
West of Mississippi River and in Canada—$2.00
Chemcraft No. 2—$3.00
West of Mississippi River and in Canada—$3.50
Chemcraft No. 3—$5.00
West of Mississippi River and in Canada—$6.00

Be sure you get "CHEMCRAFT," the original and most complete and scientific chemical outfit. Ask for it by name at your Toy Store, or send price and we will deliver direct prepaid.

THE PORTER CHEMICAL CO.
Industrial Bldg., W. Washington St.
Hagerstown Maryland

BOYS
Build and Fly Your Own Training Plane

Train yourself in Aviation. Be an Amateur Aviator with an Aeroplane of your own. Learn how Aeroplanes are built; learn the principles of construction, operation and control. We sell IDEAL Accurate Scale Drawings, and Building and Flying Instructions which show you how to build a perfect Model Aeroplane, 3 ft. size, that will rise from the ground by its own power and fly like a big one. Send now for the Drawings and Instructions for the one you want to build.

Drawings and Instructions for
Curtiss Military Tractor
Bleriot Monoplane
Nieuport Monoplane
Taube Monoplane
Curtiss Flying Boat
Wright Biplane
Cecil Peoli Racer
25c EACH
Set of Seven $1.50 postpaid

Ideal Model Aeroplane Catalog 5c—None Free
Tells about Model Aeroplanes, Racing Aeroplanes, Flying Toys, and parts and supplies to build them with. 48 pages. Sent only upon receipt of 5 cents.
IDEAL AEROPLANE & SUPPLY COMPANY
76-82 West Broadway New York City

The Electric Safety razor makes shaving a pleasure. Blade vibrating 7,200 times a minute cuts the beard smoothly and without slightest pull or irritation—feels like a gentle message. Can be used with or without electric current.

All users of the Lek-Tro-Shav speak well of it

A barber says—"Have shaved for years and have never used any shaving device near its equal."
A home user says—"The most pleasing shave I've ever had in my life. Shaves my face closer than I used to shave, but there is no after irritation or ill effects as I usually get from another razor."
No. 1 Made for use from Light Socket.
No. 2 Made for use from Dry Battery.
Write for illustrated circular describing Lek-Tro-Shav Safety Razor fully.

VIBRATING ELECTRIC RAZOR CO.
Dept. 122. Omaha, Nebr.

Printing Cheap
Cards, circulars, labels, book, paper. Press $6. Larger $20 Job press $85 up. Save money. Print for others, big profit. All easy, rules sent. Write factory for press catalog, TYPE, cards, paper. THE PRESS CO. D-47 Meriden, Conn.

Famous Scientific Illusions

(*Continued from page* 694)

The earliest trials were made by Dalibrand in France, but Franklin himself was the first to obtain a spark by using a kite, in June, 1752. When these atmospheric discharges manifest themselves today in our wireless station we feel annoyed and wish that they would stop, but to the man who discovered them they brought tears of joy.



Fig. 7

The Theory Has Been Seriously Advanced and Taught that the Radio Ether Wave Oscillations Pass Around the Earth by Successive Reflections, as Here Shown. The Efficiency of Such a Reflector Cannot be more than 25 Per Cent; the Amount of Energy Recoverable in a 12,000-mile Transmission being but One Hundred and Fifteen Billionth Part of One Watt, with 1,000 Kilowatts at the Transmitter.

The lightning conductor in its classical form was invented by Benjamin Franklin in 1755 and immediately upon its adoption proved a success to a degree. As usual, however, its virtues were often exaggerated. So, for instance, it was seriously claimed that in the city of Piatermaritzburg (capital of Natal, South Africa) no lightning strokes occurred after the pointed rods were installed, altho the storms were as frequent as before. Experience has shown that just the opposite is true. A modern city like New York, presenting innumerable sharp points and projections in good contact with the earth, is struck much more often than equivalent area of land. Statistical records, carefully compiled and publisht from time to time, demonstrate that the danger from lightning to property and life has been reduced to a small percentage by Franklin's invention, but the damage by fire amounts, nevertheless, to several million dollars annually. It is astonishing that this device, which has been in universal use for more than one century and a half, should be found to involve a gross fallacy in design and construction which impairs its usefulness and may even render its employment hazardous under certain conditions.

For explanation of this curious fact I may first refer to Fig. 3, in which s is a metallic sphere of radius r, such as the capacity terminal of a static machine, provided with a sharply pointed pin of length h, as indicated. It is well known that the latter has the property of quickly dissipating the accumulated charge into the air. To examine this action in the light of present knowledge we may liken electric potential to temperature. Imagine that sphere s is heated to T degrees and that the pin or metal bar is a perfect conductor of heat so that its extreme end is at the same temperature T. Then if another sphere of larger radius, v_1, is drawn about the first and the temperature along this boundary is T_1, it is evident that there will be between the end of the bar and its surrounding a difference of temperature $T - T_1$, which will determine the outflow of heat. Obviously, if the adjacent medium was not affected by the hot sphere this temperature difference would be greater and more heat would be given off. Exactly so in the electric system. Let q be the quantity of the charge, then the sphere—and owing to its great conductivity also the pin—will be at the potential $\frac{q}{r}$. The medium around the point of the pin will be at the potential $\frac{q}{r_1} = \frac{q}{r+h}$ and, consequently, the difference $\frac{q}{r} - \frac{q}{r+h} = \frac{qh}{r(r+h)}$. Suppose now that a sphere S of much larger radius $R = nr$ is employed containing a charge Q this difference of potential will be, analogously $\frac{Qh}{R(R+h)}$. According to elementary principles of electro-statics the potentials of the two spheres s and S will be equal if $Q = nq$ in which case $\frac{Qh}{R(R+h)} =$

(*Continued on page* 730)

Mesco Telegraph Practice Set

For Learning Telegraph Codes



The Practice Set comprises a regular telegraph key, without circuit breaker, a special high pitch buzzer, one cell Red Seal Dry Battery, and four feet of green silk covered flexible cord.

The key and buzzer are mounted on a highly finished wood base, and three nickel plated binding posts are so connected that the set may be used for five different purposes.

List No.		Price
342	Telegraph Practice Set, with Battery and Cord	$3.24

Weighs 4 lbs. packed.
Price does not include postage.

MESCO Combination Practice Set for learning the Morse and Continental Visual and Audible Codes



This outfit is the only reliable instrument which will enable students to become proficient operators in the U. S. Naval Service, because it is equipped with a buzzer and miniature lamp enabling the user to master both the visual and audible signals quickly.

List No. 52—Practice Set with Red Seal Battery and Cord $4.05
Weighs 4 lbs. packed. Price does not include postage.

Send for the New Edition of Our Catalog W28

It is pocket size, contains 248 pages, with over 1,000 illustrations, and describes in plain, clear language all about Bells, Push Buttons, Batteries, Telephone and Telegraph Material, Electric Toys, Burglar and Fire Alarm Contrivances, Electric Call Bells, Electric Alarm Clocks, Medical Batteries, Motor Boat Horns, Electrically Heated Apparatus, Battery Connectors, Switches, Battery Gauges, Wireless Telegraph Instruments, Ignition Supplies, etc.

Send for the Catalog Now

Manhattan Electrical Supply Co., Inc.

NEW YORK: 17 Park Place — CHICAGO: 114 S. Wells St. — ST. LOUIS: 1106 Pine St.
San Francisco Office: 604 Mission St.

MECHANICALLY RIGHT—A REAL LATHE
A Regular lathe, not a toy



Swing 4 inches, 11 inches between centers. 17 inches total length. Net weight 9 lbs. Shipping weight 13 lbs.
The bed of this lathe is machined. Workmanship is first class throughout. Lathe comes equipped with wood turning chuck. Lathe can be fitted with 3 inch face plate and drill chuck as special equipment. Order one today. Price $5.00 cash with order.
SYPHER MFG. CO., Dept. C., TOLEDO, OHIO

Feldman's "Geyser" Electric Water Heater

Instantaneous Hot Water

FELDMAN MFG. CO.

1500 Times Bldg. New York City

HAVE *You* SENT

for our booklet No. 4, giving diagrams and experiments with the Steco Button?

STECO, 2134 N. Clark St., Chicago, Ill.

FAMOUS SCIENTIFIC ILLUSIONS.

(*Continued from page 728*)

$\frac{nqh}{nr(nr+h)} = \frac{qh}{r(nr+h)}$. Thus the difference of potential between the point of the pin and the medium around the same



Fig. 4. Tesla Explains the Fallacy of the Franklin Pointed Lightning Rod, Here Illustrated, and Shows that Usually Such a Rod Could Not Draw Off the Electricity in a Single Cloud in Many Years. The Density of the Dots Indicates the Intensity of the Charges.

will be smaller in the ratio $\frac{r+h}{nr+h}$ when the large sphere is used. In many scientific tests and experiments this important observation has been disregarded with the result of causing serious errors. Its significance is that the behavior of the pointed rod entirely depends on the linear dimensions of the electrified body. Its quality to give off the charge may be entirely lost if the latter is very large. For this reason, all points or projections on the surface of a conductor of such vast dimensions as the earth would be quite ineffective were it not for other influences. These will be elucidated with reference to Fig. 4, in which our artist of the Impressionist school has emphasized Franklin's notion that his rod was drawing electricity from the clouds. If the earth were not surrounded by an atmosphere which is generally oppositely charged it would behave, despite all its irregularities of surface, like a polished sphere. But owing to the electrified masses of air and cloud the distribution is greatly modified. Thus in Fig. 4, the positive charge of the cloud induces in the earth an equivalent *opposite* charge, the density at the surface of the latter diminishing with the cube of the distance from the static center of the cloud. A brush discharge is then formed at the point of the rod and the action Franklin anticipated takes place. In addition, the surrounding air is ionized and rendered conducting and, eventually, a bolt may hit the building or some other object in the vicinity. The virtue of the pointed end to dissipate the charge, which was uppermost in Franklin's mind is, however, infinitesimal. *Careful measurements show that it would take many years before the electricity stored in a single cloud of moderate size would be drawn off or neutralized thru such a lightning conductor.* The grounded rod has the quality of rendering harmless most of the strokes it receives, tho occasionally the charge is diverted with damaging results. But, what is very important to note, it invites danger and hazard on account of the fallacy involved in its design. The sharp point which was thought advantageous and indispensable to its operation, is really a defect detracting considerably from the practical value of the device. I have produced a much improved form of lightning protector characterized by the employment of a terminal of considerable area and large radius of curvature which makes impossible undue density of the charge and ionization of the air.* *These protectors act as quasi-repellents and so far have never been struck tho exposed a long time.* Their safety is experimentally demonstrated to greatly exceed that invented by Franklin. By their use property worth millions of dollars which is now annually lost, can be saved.

III. The Singular Misconception of the Wireless.

To the popular mind this sensational advance conveys the impression of a single invention but in reality it is an art, the successful practise of which involves the employment of a great many discoveries and improvements. I viewed it as such when I undertook to solve wireless problems and it is due to this fact that my insight into its underlying principles was clear from their very inception.

In the course of development of my induction motors it became desirable to operate them at high speeds and for this purpose I constructed alternators of relatively

*Refer to the October, 1918, issue of this journal wherein Dr. Tesla's new form of non-pointed lightning rod was fully described and illustrated.

(*Continued on page 732*)



Fig. 3

Diagram Used to Explain the Fallacy of the Franklin Pointed Lightning Rod, and an Analogy Whereby the Author Shows in a Clear Manner How the Charged Sphere May for Illustration be Considered as Heated to a High Degree, and the Heat Allowed to Escape at a Known Rate

You can be quickly cured, if you

STAMMER

Send 10 cents coin or stamps for 70-page book on Stammering and Stuttering, "Its Cause and Cure." It tells how I cured myself after stammering for 20 years.

Benjamin N. Bogue, 751 Bogue Building, Indianapolis

With the consent of NIKOLA TESLA

We have prepared a genuine, handsome photograph, autographed in facsimile by the great inventor. This photograph, taken in December, 1918, was posed especially for the cover design of the February, 1919, issue of the "Electrical Experimenter". It shows Tesla as he is today, holding his famous wireless-lighted globe. No advertising whatsoever on this photo, except for the autograph. Size about 9 x 12". Ready for framing. A striking picture of the world's greatest inventor for your den, library, laboratory, workshop or radio station. Sent prepaid in strong cardboard tube. Price $1.00.

EXPERIMENTER PUBLISHING CO
231 Fulton St. Book Department N. Y. City

FAMOUS SCIENTIFIC ILLUSIONS

(*Continued from page* 730)

high frequencies. The striking behavior of the currents soon captivated my attention and in 1889 I started a systematic investigation of their properties and the possibilities of practical application. The first gratifying result of my efforts in this direction was the transmission of electrical energy thru *one wire* without return, of which I gave demonstrations in my lectures and addresses before several scientific bodies here and abroad in 1891 and 1892. During that period, while working with my oscillation transformers and dynamos of frequencies up to 200,000 cycles per second, the idea gradually took hold of me that the earth might be used in place of the wire, thus dispensing with artificial conductors altogether. The immensity of the globe seemed an unsurmountable obstacle but after a prolonged study of the subject I became satisfied that the undertaking was rational, and in my lectures before the Franklin Institute and National Electric Light Association early in 1893 I gave the outline of the system I had conceived. In the latter part of that year, at the Chicago World's Fair, I had the good fortune of meeting Prof. Helmholtz to whom I explained my plan, illustrating it with experiments. On that occasion I asked the celebrated physicist for an expression of opinion on the feasibility of the scheme. He stated unhesitatingly that it was practicable, provided I could perfect apparatus capable of putting it into effect but this, he anticipated, would be extremely difficult to accomplish.

I resumed the work very much encouraged and from that date to 1896 advanced slowly but steadily, making a number of improvements the chief of which was my system of *concatenated tuned circuits* and method of regulation, now universally adopted. In the summer of 1897 Lord Kelvin happened to pass thru New York and honored me by a visit to my laboratory where I entertained him with demonstrations in support of my wireless theory. He was fairly carried away with what he saw but, nevertheless, condemned my project in emphatic terms, qualifying it as something impossible, "an illusion and a snare." I had expected his approval and was pained and surprised. But the next day he returned and gave me a better opportunity for explanation of the advances I had made and of the true principles underlying the system I had evolved. Suddenly he remarked with evident astonishment: "Then you are not making use of Hertz waves?" "Certainly not," I replied, *"these are radiations.* No energy could be economically transmitted to a distance by any such agency. In my system the process is one of *true conduction* which, theoretically, can be effected at the greatest distance without appreciable loss." I can never forget the magic change that came over the illustrious philosopher the moment he freed himself from that erroneous impression. The skeptic who would not believe was suddenly transformed into the warmest of supporters. He parted from me not only thoroly convinced of the scientific soundness of the idea but strongly exprest his confidence in its success. In my exposition to him I resorted to the following mechanical analogues of my own and the Hertz wave system.

Imagine the earth to be a bag of rubber filled with water, a small quantity of which is periodically forced in and out of the same by means of a reciprocating pump, as illustrated. If the strokes of the latter are effected in intervals of more than one hour and forty-eight minutes, sufficient for the transmission of the impulse thru the whole mass, the entire bag will expand and contract and corresponding movements will be imparted to pressure gauges or movable pistons with the same intensity, irrespective of distance. By working the pump faster, shorter waves will be produced which, on reaching the opposite end of the bag, may be reflected and give rise to stationary nodes and loops. but in any case, the fluid being incompressible, its inclosure perfectly elastic, and the frequency of oscillations not very high, the energy will be economically transmitted and very little power consumed so long as no work is done in the receivers. This is a crude but correct representation of my wireless system in which, however, I resort to various refinements. Thus, for instance, the pump is made part of a resonant system of great inertia, enormously magnifying the force of the imprest impulses. The receiving devices are similarly conditioned and in this manner the amount of energy collected in them vastly increased.

The Hertz wave system is in many respects the very opposite of this. To explain it by analogy, the piston of the pump is assumed to vibrate to and fro at a terrific rate and the orifice thru which the fluid passes in and out of the cylinder is reduced to a small hole. There is scarcely any movement of the fluid and almost the whole work performed results in the production of radiant heat, of which an infinitesimal part is recovered in a remote locality. However incredible, it is true that



Wireless Stations Will Shortly Re-open

Date, only, uncertain

Heed Our Advice ***ORDER NOW***

As a matter of law Congress loses all control over wireless receiving stations and transmitting stations with a range within the borders of the state where located as soon as peace is declared. The Radio Inspector of this district has already asked our co-operation in printing in the next edition of our catalog the necessity of securing licenses for transmitting sets with a range beyond the borders of the state. No wireless manufacturer wants the stations to open tomorrow. They could not take care of the business. Order now and be prepared. We have a big stock of wireless instruments.

No. 11 is our latest catalog. No new price list.

Please do not write for catalog if you have No. 11. Paper costs three times as much as formerly. Let the amateur without a catalog secure one. Write for prices in advance. Just now we have no price list, because the changes have been so frequent. Will advise through this magazine when revised price list is ready, which will be as quickly as possible.

Send 8c in coin or stamps today for our big 300 page No. 11 Electrical and Wireless Catalog. Any wireless amateur will tell you it is the one catalog to have. You need no others. Our catalog contains most everything in wireless worth while, and is a guarantee that the goods are dependable.

THE WILLIAM B. DUCK CO., 230-232 Superior St., Toledo, Ohio

"THERE'S MONEY IN IT"

AT HOME LEARN TELEGRAPHY AT HOME

MORSE AND WIRELESS

TEACH YOURSELF



In half the usual time, at trifling cost, with the wonderful Automatic Transmitter, **THE OMNIGRAPH.** Sends unlimited Morse or Continental messages, at any speed, just as an expert operator would.

Adopted by U. S. Gov't. 4 styles. Catalogue free.

OMNIGRAPH MFG. CO.

39L Cortlandt St. New York

MAGNETIC RECTIFIER

Patented April 18, 1916



The F-F Battery Booster

For Home Charging of Storage Batteries

AUTOMOBILE OWNERS: Eliminate your starting and lighting troubles by the use of an F-F BATTERY BOOSTER in your own garage, without breaking any electrical connections or removing battery from car. Keeps your battery 100% efficient and prolongs its life indefinitely at a cost of about six cents a month. Write for bulletin No. 12 today.

The French Manufacturing Company

Cleveland, Ohio U. S. A.

the minds of some of the ablest experts have been from the beginning, and still are, obsest by this monstrous idea, and so it comes that the true wireless art, to which I laid the foundation in 1893, has been retarded in its development for twenty years. This is the reason why the "statics" have proved unconquerable, why the wireless shares are of little value and why the Government has been compelled to interfere.

We are living on a planet of well-nigh inconceivable dimensions, surrounded by a layer of insulating air above which is a rarefied and conducting atmosphere (Fig. 5). This is providential, for if all the air were conducting the transmission of electrical energy thru the natural media would be impossible. My early experiments have shown that currents of high frequency and great tension readily pass thru an atmosphere but moderately rarefied, so that the insulating stratum is reduced to a small thickness as will be evident by inspection of Fig. 6, in which a part of the earth and its gaseous envelope is shown to scale. If the radius of the sphere is 12½", then the non-conducting layer is only 1/64" thick and it will be obvious that the Hertzian rays cannot traverse so thin a crack between two conducting surfaces for any considerable distance, without being absorbed. The theory has been seriously advanced that these radiations pass around the globe by *successive reflections,* but to show the absurdity of this suggestion reference is made to Fig. 7 in which this process is diagrammatically indicated. Assuming that there is no refraction, the rays, as shown on the right, would travel along the sides of a polygon drawn around the solid, and inscribed into the conducting gaseous boundary in which case the length of the side would be about 400 miles. As one-half the circumference of the earth is approximately 12,000 miles long there will be, roughly, thirty deviations. The efficiency of such a reflector cannot be more than 25 per cent, so that if none of the energy of the transmitter were lost in other ways, the part recovered would be measured by the fraction $(¼)^{30}$. Let the transmitter radiate Hertz waves at the rate of 1,000 kilowatts. Then about *one hundred and fifteen billionth part of one watt* is all that would be collected in a *perfect* receiver. In truth, the reflections would be much more numerous as shown on the left of the figure, and owing to this and other reasons, on which it is unnecessary to dwell, the amount recovered would be a vanishing quantity.

Consider now the process taking place in the transmission by the instrumentalities and methods of my invention. For this purpose attention is called to Fig. 8, which gives an idea of the mode of propagation of the current waves and is largely self-explanatory. The drawing represents a solar eclipse with the shadow of the moon just touching the surface of the earth at a point where the transmitter is located. As the shadow moves downward it will spread over the earth's surface, first with infinite and then gradually diminishing velocity until at a distance of about 6,000 miles it will attain its true speed in space. From there on it will proceed with increasing velocity, reaching infinite value at the opposite point of the globe. It hardly need be stated that this is merely an illustration and not an accurate representation in the astronomical sense.

The exact law will be readily understood by reference to Fig. 9, in which a transmitting circuit is shown connected to earth and to an antenna. The transmitter being in action, two effects are produced: Hertz waves pass thru the air, and a current traverses the earth. The former propagate with the speed of light and their energy is *unrecoverable* in the circuit. The latter proceeds with the speed varying as the cosecant of the angle which a radius drawn from any point under consideration forms

Increase Your Will Power In One Hour

Author of This Article Tells How He Quickly Acquired a Dominating Will Power That Earns Him Between $50,000 *and* $70,000 *a Year*

FOUR YEARS ago a man offered me a wonderful bargain. He was hard up for money and wanted to sell me some shares in a young, growing company for $1,000. Based on the earnings of the Company the stock offered me was easily worth $5,000—in fact, the man who finally bought the shares sold them again in five months **at a profit of $4,300.**

The reason I didn't buy the shares was that I could no more raise a thousand dollars than I could hop, skip, and jump across the Atlantic Ocean. A thousand dollars! And my income only twenty-five a week.

The second chapter in my life began a few months later, when another opportunity came to me. It required an investment of $20,000 during the first year. I raised the money easily, paid back every penny I borrowed, and had $30,000 left at the end of the first year! To date, in less than four years, my business has paid me a clear profit of over $200,000 and is now earning between $50,000 and $70,000 a year. **Yet for twelve years before, the company had been losing money every year!**

The natural question for my reader to ask is, "How could you borrow $20,000 to invest in a business which had previously been a failure, after being unable to borrow $1,000 for an investment that seemed secure?" It is a fair question. Andd the answer can be given in two little words— **WILL POWER.**

When the first proposition came to me I passed it by simply because I didn't have the money and couldn't borrow it. I went from one friend to the next and all turned me down. Several refused to talk business with me at all. They all liked me personally, and they asked me about the kiddies, but when it came to money matters I hadn't a chance. I was scared stiff every time I talked to one of them. I pleaded with them, almost begged them. But everybody had their "money all tied up in other investments." It was an old excuse, but I accepted it meekly. I called it hard luck. But I know today that it was nothing in the world except my lack of Will Power, or rather my weak Will Power, which kept me from getting what I wanted.

When I heard that the man sold those shares at a profit of $4,300, it seemed that my sorrow could not be greater. That profit was just about what my salary amounted to for four years! But instead of grieving over my "hard luck," I decided to find out why I was so easily beaten in everything I tried to accomplish. It must be that there was something vital that made the difference between success and failure. It wasn't lack of education, for many illiterate men become wealthy. What was this vital spark? What was this one thing which successful men had and which I did not have?

Partial List of Contents

The Law of Great Thinking
The Four Factors on which it depends.
How to develop analytical power.
How to think "all around" any subject.
How to throw the mind into deliberate, controlled, productive thinking.
Detailed directions for Perfect Mind Concentration.
How to acquire the power of Consecutive Thinking, Reasoning, Analysis.
How to acquire the skill of Creative Writing
How to guard against errors in Thought.
How to drive from the mind all unwelcome thoughts.
How to follow any line of thought with keen, concentrated Powers.
How to develop Reasoning Power.
How to handle the mind in Creative Thinking.
The secret of Building Mind Power
How the Will is made to act.
How to test your Will.
How a Strong Will is Master of Body.
What creates Human Power.
The Six Principles of Will Training.
Definite Methods for developing Will.
The NINETY-NINE METHODS for using Will Power in the Conduct of Life.
Seven Principles of drill in Mental, Physical, Personal power
FIFTY-ONE MAXIMS for Applied Power of Perception, Memory, Imagination, Self-Analysis, Control.
How to develop a strong, keen gaze.
How to concentrate the eye upon what is before you—object, person, printed page, work.

These are only a few of the many subjects treated.

I began to read books about psychology and mental power. But everything I read was too general. There was nothing definite — nothing that told me **what to do.**

After several months of discouraging effort. I finally encountered a book called "Power of Will," by Prof. Frank Channing Haddock. The very title came to me as a shock. When I opened the book I was amazed. I realized that will power was the vital spark—the one thing that I lacked And here in this book were the very rules, lessons and exercises through which anyone could increase their will power. Eagerly I read page after page; including such articles as, The Law of Great Thinking; How to Develop Analytical Power; How to Concentrate Perfectly; How to Guard Against Errors in Thought; How to Develop Fearlessness; How to Acquire a Dominating Personality.

An hour after I opened the book I felt like a new person. My sluggish will power was beginning to awaken. There was a new light in my eye, a new spring in my step, a new determination in my soul. I began to see, in my past, the many mistakes I had made, and I knew I would never make them again.

I practiced some of the simple exercises. They were more fascinating than any game of cards or any sport.

Then came an opportunity to acquire the business which had lost money for twelve years, and which I turned into a $50,000 a year money maker. Instead of cringing before the moneyed people, I won them over by my sheer force of will. I would not be denied. And my every act and word since then has been the result of my training in will power.

I am convinced that every man has within himself every essential quality of success except a strong will. Any man who doubts that statement need only analyze the successful men he knows, and he will find himself their equal, or their superior, in every way except in will power. Without a strong will, education counts for little, money counts for nothing, opportunities are useless.

I earnestly recommend Prof. Haddock's great work, "Power of Will," to those who feel that success is just out of reach—to those who lack that something which they cannot define, yet which holds them down to the grind of a small salary.

Never before have business men and women needed this help so badly as in these trying times. Hundreds of real and imaginary obstacles confront us every day, and only those who are masters of themselves and who hold their heads up will succeed. "Power of Will" as never before is an absolute necessity—an investment in self-culture which no one can afford to deny himself.

I am authorized to say that any reader who cares to examine "Power of Will" for five days may do so without sending any money in advance. If after one hour you do not feel that your will power has increased, and if after a week's reading you do not feel that this great book supplies that one faculty you need most to win success, return it and you will owe nothing. Otherwise send only $3, the small sum asked.

Some few doubters will scoff at the idea of will power being the fountainhead of wealth, position and everything we are striving for, but the great mass of intelligent men and women will at least investigate for themselves by sending for the book at the publisher's risk. I am sure that any book that has done for me—and for thousands of others—what "Power of Will" has done—is well worth investigating. It is interesting to note that among the 250,000 owners of "Power of Will" are such prominent men as Supreme Court Justice Parker; Wu Ting Fang, Ex-U. S. Chinese Ambassador; Gov. McKelvie, of Nebraska; Assistant Potmaster-General Britt; General Manager Christeson, of Wells-Fargo Express Co.; E. St. Elmo Lewis; Senator Arthur Capper of Kansas and thousands of others. In fact, today "Power of Will" is just as important, and as necessary to a man's or woman's equipment for success, as a dictionary. To try to succeed without Power of Will is like trying to do business without a telephone.

As your first step in will training, I suggest immediate action in this matter before you. It is not even necessary to write a letter. Use the form below, if you prefer, addressing it to the Pelton Publishing Company, 30-B Wilcox Block, Meriden, Conn., and the book will come by return mail. You hold in your hand, this very minute, the beginning of a new era in your life. Over a million dollars has been paid for "Power of Will" by people who sent for it on free examination. Can you, in justice to yourself, hesitate about sending in the coupon? Can you doubt, blindly, when you can see, without a penny deposit, this wonder-book that will increase your will power in one hour.

The cost of paper, printing and binding has almost doubled during the past three years, in spite of which "Power of Will" has not been increased in price. The publisher feels that so great a work should be kept as low-priced as possible, but in view of the enormous increase in the cost of every manufacturing item, the present edition will be the last sold at the present price The next edition will cost more. I urge you to send in the coupon now.

PELTON PUBLISHING COMPANY
30-B Wilcox Block, Meriden, Conn.

I will examine a copy of "Power of Will," at your risk I agree to remit $3 or remail book in 5 days.

Name.....

Address.....

City.....State.....

1/4 H.P., 110 volts, A.C. 60 cycle, single phase, 1750 R.P.M.

MOTORS



We have 1000 NEW WASHING MACHINE MOTORS. These are of standard manufacture and carry the regular factory guarantee. Shipped in original boxes. Complete as cut.

Bought from Bankruptcy Stock

Suitable for operating Coffee Grinders, Cream Seperators, Bottle Washers, Air Compressors Small Lathes, Etc.

Mail $3.00 cash or Money Order. We will send C.O.D. subject to full examination.
MONEY BACK GUARANTEE

$18.50 EACH
Special Quantity Prices Regular Value $34

MANUFACTURERS' DISTRIBUTER

BARGAINS In Small Motors and Generators Write for Catalogue

CHAS. H. JOHNSTON - West End - Pittsburgh, Pa.

Wireless Taught By Mail

Merchant Marine Needs THOUSANDS of Operators

Men also needed for big Land Wireless Stations—Aerial Mail Service—Railroad and Telegraph companies. Salaries up to $200 a month. Excellent opportunities to win promotion to Radio Engineer—Inspector—or Draftsman. Chance to travel the world over or locate at Land Station in America.

Complete Course by Mail in Ten Weeks

Our students actually pass the commercial examination in Ten Weeks or less. Start studying NOW in spare time at home. We send you Complete Set Practice Instruments for receiving and sending messages, with first lessons. We help you secure position in any branch of Commercial or Government Radio Service. Write TODAY for Free Particulars. A postal will do.

NATIONAL RADIO INSTITUTE
Dept. 68 Washington, D. C.



Grinding and Buffing Motors

An indispensable tool in any shop or laboratory. Your equipment is not complete without a BODINE grinding and buffing motor.

Save time and money by keeping your lathe tools, milling cutters and drills sharp.

Send for bulletin No. 522 giving full details of this handy machine.
BODINE ELECTRIC COMPANY, 2254 W. Ohio St., Chicago.

with the axis of symmetry of the waves. At the origin the speed is infinite but gradually diminishes until a quadrant is traversed, when the velocity is that of light. From there on it again increases, becoming infinite at the antipole. Theoretically the energy of this current is *recoverable* in its entirety, in properly attuned receivers.

Some experts, whom I have credited with better knowledge, have for years contended that my proposals to transmit power without wires are sheer nonsense but I note that they are growing more cautious every day. The latest objection to my system is found in the cheapness of gasoline. These men labor under the impression that the energy flows in all directions and that, therefore, only a minute amount can be recovered in any individual receiver. But this is far from being so. The power is conveyed in only one direction, from the transmitter to the receiver, and none of it is lost elsewhere. It is perfectly practicable to recover at any point of the globe energy enough for driving an airplane, or a pleasure boat or for lighting a dwelling. I am especially sanguine in regard to the lighting of isolated places and believe that a more economical and convenient method can hardly be devised. The future will show whether my foresight is as accurate now as it has proved heretofore.

SHIP RADIO OPERATORS ASK INCREASED WAGES.

Increased wages and the fixing of a standard wage scale for radio operators on vessels operating under Government direction was asked of the Shipping Board recently by a delegation representing the Marconi Radio Telegraphers' Association. The radio operators included in the request made of the Board are those on vessels operating in transatlantic and Gulf waters. Assurances were given the radio representatives by Board officials that their request would be taken under advisement for immediate consideration.

SKINDERVIKEN TRANSMITTER BUTTON



Fig. 1



Fig. 2

THE SKINDERVIKEN TRANSMITTER BUTTON presents the latest advance in microphones and marks a revolution in transmitter construction. It works on an entirely new principle, takes up practically no room, and marks the end of all telephone transmitter troubles.

The SKINDERVIKEN TRANSMITTER BUTTON can be placed in any position and it will talk loudly and distinctly and is at the same time extraordinarily sensitive. It was primarily designed to replace the old damaged or burnt out transmitter. Simply unscrew and remove the telephone transmitter front, disconnect the two inside wires, unscrew and remove the bridge and the old electrode. There remains only the diafram. These wires are then connected with the Skinderviken button, the latter screwed to the diafram, and after screwing the old transmitter housing together again, the telephone is ready for work.

ELECTRICAL EXPERIMENTER readers will be particularly interested in all the different experiments that can be performed with the Skinderviken Button. Fig. 1 shows the Skinderviken button attached to the back of an Ingersol watch case. When speaking towards the inside of the case, it will be found that the voice is reproduced clearly and loudly Fig. 2 shows another interesting stunt. By attaching the button to a tin diafram about the size of half a dollar, and by holding the diafram at the side of the throat, as shown, speech can be transmitted with surprising clarity. Fig. 3 illustrates the same arrangement placed on the chest, as shown. In this position the transmitter will talk clearly and loudly Fig. 4 shows an arrangement whereby the Skinderviken button is attached on a thin wood board at the preacher's pulpit. His voice is clearly transmitted so that people hard of hearing can readily hear the sermon. Fig. 5 shows an interesting stunt, whereby a hole is drilled in the side of a thin glass water-tumbler; the sides of the glass thus acting as a diafram, the voice is clearly transmitted. Fig. 6 shows a simple match box Detectophone. The Skinderviken button is concealed inside of the box, only the small brass nut showing on the outside. This can be camouflaged as well. This device talks well. Fig. 7 shows how to transmit phonograph music at a distance merely by drilling a small hole in the phonograph arm and attaching the Skinderviken button; a very favorite experiment with all experimenters. Fig. 8 shows how a very sensitive Detectophone can be made by placing one of the buttons in the center of a lithographed cardboard picture, so that only the small brass nut shows. The large surface of the picture acts as a big diafram, and the voice is well reproduced.



$1.00 prepaid

We have such unlimited confidence in the Skinderviken transmitter button that we make the following remarkable offer. Send us one dollar ($1.00) for which we will mail one button prepaid. If you do not wish to keep it, return it within five days and your money will be refunded. Boys! send stamp for booklet No. 4. It gives diagrams and experiments using the Skinderviken Transmitter Button, and prices of telephone equipment.

Fig. 5



Fig. 6



Fig. 3

Fig. 4



Fig. 7

Fig. 8

SKINDERVIKEN TELEPHONE EQUIPMENT CO. Address us as STECO, 2134 N. Clark St., Chicago, Ill.

Tesla's Egg of Columbus

How Tesla Performed the Feat of Columbus Without Cracking the Egg

PROBABLY one of the most far-reaching and revolutionary discoveries made by Mr. Tesla is the so-called *rotating magnetic field*. This is a new and wonderful manifestation of force —a magnetic cyclone—producing striking with any speed desired. Long ago, when Tesla was still a student, he conceived the idea of the rotating magnetic field and this remarkable principle is embodied in his famous *induction motor* and system of transmission of power now in universal use.

In this issue of the ELECTRICAL EXPERIMENTER Mr. Tesla gives a remarkable account of his early efforts and trials as an inventor and of his final success. Unlike other technical advances arrived at thru the usual hit and miss methods and hap-


COPPER EGG
PLATFORM
2 BALLS
DIRECTION OF ROTATING MAGNETIC FIELD
IRON RING CORE
TO PHASE 2
TO PHASE 1
SINGLE BALL SPINNING ON ITS OWN AXIS & FOLLOWING THE PATH OF ROTATING MAGNETIC FIELD
THE SMALLER BALLS REVOLVE AROUND THE LARGER CENTRAL EGG BOTH MOVING AROUND THE PATH OF THE REVOLVING MAGNETIC FIELD
DIRECTION OF ROTATING MAGNETIC FIELD
POLISHED WOODEN PLATFORM PLACED ON 2 PHASE MAGNET COILS
2 PHASE MAGNET WINDING
EE

Copyright, 1919, by E. P. Co.

Fig. 2. Illustrating the Polyphase Coil and Rotating Megnetic Field Which Caused Copper Eggs to Spin.
Fig. 3. Insert: Detail of Coil Apparatus Showing Coil Connections to Different Phases.

phenomena which amazed the world when they were first shown by him. It results from the joint action of two or more alternating currents definitely related to one another and creating magnetic fluxes, which, by their periodic rise and fall according to a mathematical law, cause a continuous shifting of the lines of force. There is a vast difference between an ordinary electro-magnet and that invented by Tesla. In the former the lines are stationary, in the latter they are made to whirl around at a furious rate. The first attracts a piece of iron and holds it fast; the second causes it to spin in any direction and



Fig. 1. This hitherto unpublisht photograph is extremely interesting as it shows not only "Tesla's Electric Egg" apparatus in the center of the background, but also a comprehensive view of a corner of his famous Houston Street laboratory of a decade ago. At the left may be seen a number of Tesla's oscillators or high frequency generators, while in the rear may be noted a large high frequency transformer of the spiral type, the diameter of which was a little over nine feet. The electric egg apparatus comprising a two-phase A.C. circular core and winding, rests on a table, and this particular model measured about two feet across. In making the demonstrations, Tesla applied as much as 200 H.P. from a two-phase alternator to the exciting coils, and so intense was the revolving magnetic field created in the surrounding space, that small delicately pivoted iron discs would revolve in any part of the hall, and a great many other devices could be simultaneously operated from this magnetic field when thus excited. The frequency of the two-phase A.C. energizing the coils, was varied from 25 to 300 cycles, the best results being obtained with currents of from 35 to 40 cycles. This laboratory was lighted by Tesla's vacuum tubes, several of which may be seen on the ceiling, and each of which emitted 50 C.P. The coil resting on three legs and observed in the immediate foreground is the primary of a resonant Tesla transformer which collected energy from an oscillatory circuit encircling the laboratory, no matter in what position the transformer was placed. A low tension secondary of one or two turns of heavy cable (not visible) was provided for stepping down the energy collected by "mutual induction," and supplied the current to incandescent lamps, vacuum tubes, motors and other devices. When the circuit around the hall was strongly excited, the secondary furnished energy at the rate of about three-quarters of one horse-power.

hazard experimentation, the rotating field was purely the work of scientific imagination. Tesla developed and perfected, entirely in his mind, this great idea in all its details and applications *without making one single experiment.* Not even the usual first model was used. When the various forms of apparatus he had devised were tried for the first time they worked exactly as he had imagined and he took out some forty fundamental patents covering the whole vast region he had explored. He obtained the first rotations in the summer of 1883 after five years of constant and intense thought on the subject and then undertook

the equally difficult task of finding believers in his discovery. The alternating current was but imperfectly understood and had no standing with engineers or electricians and for a long time Tesla talked to deaf ears. But, ultimately, his pains were rewarded and early in 1887 a company bearing his name was formed for the commercial introduction of the invention.

Dr. Tesla recently told the editors an amusing incident in this connection. He had approached a Wall Street capitalist—a prominent lawyer—with a view of getting financial support and this gentleman called in a friend of his, a well-known engineer at the head of one of the big corporations in New York, to pass upon the merits of the scheme. This man was a practical expert who knew of the failures in the industrial exploitation of alternating currents and was distinctly prejudiced to a point of not caring even to witness some tests. After several discouraging conferences Mr. Tesla had an inspiration. Everybody has heard of the "Egg of Columbus." The saying goes that at a certain dinner the great explorer asked some scoffers of his project to balance an egg on its end. They tried it in vain. He then took it and cracking the shell slightly by a gentle blow, made it stand upright. This may be a myth but the fact is that he was granted an audience by Isabella, the Queen of Spain, and won her support. There is a suspicion that she was more imprest by his portly bearing than the prospect of his discovery. Whatever it might have been, the Queen pawned her jewels and three ships were equipt for him and so it happened that the Germans got all that was coming to them in this war. But to return to Tesla's reminiscence. He said to these men, "Do you know the story of the Egg of Columbus?" Of course they did. "Well," he continued, "what if I could make an egg stand on the pointed end without cracking the shell?" "If you could do this we would admit that you had gone Columbus one better." "And would you be willing to go out of your way as much as Isabella?" "We have no crown jewels to pawn," said the lawyer, who was a wit, "but there are a few ducats in our buckskins and we might help you to an extent."



Fig. 5. This illustration shows one of Tesla's high frequency oscillation generators and a bank of his high frequency lamps lighted by the same. These highly evacuated, gas filled tubes were operated in different ways. In some cases they were connected to one wire only; in other instances to two wires, in the manner of ordinary incandescent lamps. Often, however, they were operated without any connection to wires at all, i.e., by "wireless energy", over quite appreciable distances, which could have been greatly extended with more power. The oscillator comprises a Tesla high potential transformer which is excited from a condenser and circuit controller, as described in his patents of 1896. The primary exciting element comprised a powerful electro-magnet actuating an armature, and this circuit was connected with 110 volt, 60 cycle A.C. or D.C. When the oscillator was put into operation, the interrupter actuated by the electro-magnet connected to the 110 volt circuit, became simultaneously the spark gap for the high potential exciting circuit, which included this vibrator, spark gap, a high tension condenser and the primary of the high frequency Tesla transformer. The lamps were connected to the secondary of the latter, the terminals of which are seen in the rear of the machine.

Mr. Tesla thus succeeded in capturing the attention and personal interest of these very busy men, extremely conservative and reluctant to go into any new enterprise, and the rest was easy. He arranged for a demonstration the following day. A rotating field magnet was fastened under the top board of a wooden table and Mr. Tesla provided a copper-plated egg and several brass balls and pivoted iron discs for convincing his prospective associates. He placed the egg on the table and, to their astonishment, it stood on end, but when they found that it was *rapidly spinning* their stupefaction was complete. The brass balls and pivoted iron discs in turn were set spinning rapidly by the rotating field, to the amazement of the spectators. No sooner had they regained their composure than Tesla was delighted with the question: "Do you want any money?" "Columbus was never in a worse predicament," said the great inventor, who had parted with his last portrait of George Washington in defraying the expenses of the preparation. Before the meeting adjourned he had a substantial check in his pocket, and it was given with the assurance that there was more to be had in the same bank. That started the ball rolling. Tens of millions of horsepower of Tesla's induction motors are now in use all over the world and their production is rising like a flood.

In 1893 Mr. Albert Schmid, then Superintendent of the Westinghouse Electric and Mfg. Co. constructed a powerful rotating field ring with an egg made of copper, and larger than that of an ostrich, for Dr. Tesla's personal collection at the Chicago World's Fair. This piece of apparatus was one of the most attractive novelties ever publicly shown and drew enormous crowds every day. Subsequently it was taken to Mr. Tesla's laboratory and served there permanently for demonstrating rotating field phenomena. In his experiments it was practicable to use as much as 200 *horsepower* for a short time, without overheating the wires and the effects of the magnetic forces were wonderfully fascinating to observe. This is the very ring indicated in the accompanying photograph (Fig. 1), giving a view of Mr. Tesla's former laboratory at 46 E. Houston Street, New York. It is shown in detail in Fig. 2, and the mode of winding is illustrated in diagram (Fig. 3). Originally the two-phase arrangement was provided but Mr. Tesla transformed it to the three- and four-phase when desired. On top of the ring was fastened a thin circular board, slightly hollowed, and provided around its circumference with a guard to prevent the objects from flying off.

Even more interesting than the spinning egg was the exhibition of *planetary motion*. In this experiment one large, and several small brass balls were usually employed. When the field was energized all the balls would be set spinning, the large one remaining in the center while the small ones revolved around it, like moons about a planet, gradually receding until they reached the outer guard and raced along the same.



Fig. 4. This photograph represents a collection of a few of Tesla's wireless lamps, such as he proposes to use in lighting isolated dwellings all over the world from central wireless plants. The two lamps at either corner at the bottom are illuminated, owing to the fact that a high frequency oscillator was in operation some distance away when this photograph was being taken. These tubes were filled with various gases for experimental research work in determining which was most efficient.

But the demonstration which most imprest the audiences was the simultaneous operation of numerous balls, pivoted discs and other devices placed in all sorts of positions and *at considerable distances from the rotating field*. When the currents were turned on and the whole animated with motion, it presented an unforgettable spectacle. Mr. Tesla had many vacuum bulbs in which small, light metal discs were pivotally arranged on jewels and these would spin anywhere in the hall when the iron ring was energized.

Rotating fields of 15,000 horsepower are now being turned out by the leading manufacturers and it is very likely that in the near future capacities of 50,000 horsepower will be employed in the steel and other industries and ship propulsion by Tesla's electric drive which, according to Secretary of the Navy Daniels' statement, has proved a great success.

But any student interested in these phenomena can repeat all the classical experiments of Tesla by inexpensive apparatus. For this purpose it is only necessary to make two slip ring connections on an ordinary small direct current motor or dynamo and to wind an iron ring with four coils as indicated in diagram Fig. 3. No particular rule need be given for the windings but it may be stated that he will get the best results if he will use an iron ring of comparatively *small section* and wind it *with as many turns of stout wire as practicable*. He can heavily copper plate an egg but he should bear in mind that Tesla's egg is not as innocent as that of Columbus. The worst that can happen with the latter is that it might be,—er—over ripe! but the Tesla egg may explode with disastrous effect because the copper plating is apt to be brought to a high temperature thru the induced currents. The sensible experimenter will, therefore, first suck out the contents of the egg—thus satisfying both his appetite and thirst for knowledge.

Besides the rotating field apparatus Mr.

(*Continued on page* 808)

Big Money for Boys!



Learn ELECTRICITY

There is a wonderful opportunity right now for boys who like electricity. Boys who are ambitious and will train themselves in spare time can step into positions just as soon as they are ready. Good salaries are offered to start with splendid chances for rapid promotion.

For 27 years the International Correspondence Schools have been training boys for success in electricity and over 200 other subjects. They will help you prepare right at home for a position in the line of electrical work you like best—or in any other work that appeals to you. Thousands of boys, through I. C. S. training, have stepped into fine jobs, but never were opportunities so great as now.

Let the I. C. S. help *you*. Choose the work you like best in the coupon below, then mark and mail it today. This doesn't obligate you in the least, and it will bring you information that will start you on a successful career. This is your chance. Don't let it slip by. Mark and mail this coupon *now*.

TEAR OUT HERE

INTERNATIONAL CORRESPONDENCE SCHOOLS
BOX 6179, SCRANTON, PA.

Explain, without obligating me, how I can qualify for the position, or in the subject, before which I mark X.

- ☐ ELECTRICAL ENGINEER
- ☐ Electrician
- ☐ Electric Wiring
- ☐ Electric Lighting
- ☐ Electric Car Running
- ☐ Heavy Electric Traction
- ☐ Electrical Draftsman
- ☐ Electric Machine Designer
- ☐ Telegraph Expert
- ☐ Practical Telephony
- ☐ MECHANICAL ENGINEER
- ☐ Mechanical Draftsman
- ☐ Ship Draftsman
- ☐ Machine Shop Practice
- ☐ Toolmaker
- ☐ Gas Engineer
- ☐ CIVIL ENGINEER
- ☐ Surveying and Mapping
- ☐ MINE FOREM'N OR ENG'R
- ☐ ARCHITECT
- ☐ Architectural Draftsman
- ☐ PLUMBING AND HEATING
- ☐ Sheet Metal Worker
- ☐ CHEMICAL ENGINEER
- ☐ SALESMANSHIP
- ☐ ADVERTISING MAN
- ☐ Window Trimmer
- ☐ Show Card Writer
- ☐ Outdoor Sign Painter
- ☐ RAILROADER
- ☐ ILLUSTRATOR
- ☐ DESIGNER
- ☐ BOOKKEEPER
- ☐ Stenographer and Typist
- ☐ Cert. Pub. Accountant
- ☐ Traffic Management
- ☐ Commercial Law
- ☐ GOOD ENGLISH
- ☐ STATIONARY ENGINEER
- ☐ CIVIL SERVICE
- ☐ Railway Mail Clerk
- ☐ Textile Overseer or Supt.
- ☐ AGRICULTURE
- ☐ Navigator
- ☐ Poultry Raising
- ☐ Automobiles
- ☐ Spanish
- ☐ French
- ☐ Italian

Name_____

Present Occupation_____

Street and No._____

City_____ State_____

30 DAYS FREE TRIAL



and *freight prepaid* on a new 1919 "RANGER" bicycle. Write at once for our *big catalog* and *special offers*. Take your choice from 44 styles, colors and sizes in the famous "RANGER" line.

Marvelous Improvements. Extraordinary values in our 1919 price offers. *You cannot afford to buy* without getting our *latest propositions* and **Factory-to-Rider** prices.

Boys, be a "Rider Agent" and make big money taking orders for bicycles and supplies. Get our *liberal terms* on a sample to introduce the new "RANGER".

TIRES, equipment, sundries and everything in the bicycle line at *half usual prices*. *Write Today.*

Ranger Electric Lighted Motorbike

MEAD CYCLE COMPANY Dept. D-107 Chicago

RAISE BELGIAN HARES For U.S.

HUGE PROFITS easily and pleasantly made We furnish stock and pay you $6.00 a pair and express charges for all you raise. Contract and book "Fortunes in Hares", by mail Free.

NATIONAL FOOD & FUR ASSOCIATION
Dept. 116 MILWAUKEE, WISC.

EXPERIMENTAL PHYSICS.

(*Continued from page* 806)

near the electroscope, we find that the electroscope discharges rapidly. The Bunsen flame ionizes the air very rapidly. A small quantity of radio-active material will discharge the electroscope very rapidly, showing that *radio-active materials have the ability to IONIZE the air.* The larger the amount of radio-active material the faster the rate of discharge of the electroscope. A pinch of Uranium Oxid in the electroscope chamber, will ionize the air so rapidly that the leaf will fall practically instantaneously!

Experiment 113.

A third test for the presence of most radio-active substances is the *"Fluorescence Effect"*—which some of them have upon certain compounds, especially *Zinc Sulfid.* Any of the substances which give off alpha radiations (see figure 102) will cause a zinc sulfid screen to fluoresce. If the screen is observed thru a sufficiently high power magnifying lens, or microscope (say ten or fifteen diameters magnification), the continuous soft glow of the zinc sulfid seen by the naked eye becomes, on magnification, hundreds of tiny flashes of light, not unlike the sparks obtained by striking flint and steel together. Figure 101 shows the *Spinthariscope,* which can be easily made by the reader. A is small metal tube with a hole, S, in its cap. E and F are lenses. C is the fluorescent screen on the cap of tube B. D is a small particle of the radio-active substance. A practical use of the fluorescent effect of alpha particles is familiar to all of us in the *radium paints, luminous dials,* et cetera. These compounds consist of specially prepared zinc sulfid, mixed with about 2,000 parts of radium bromid, or a radio-active compound having an equivalent of alpha-ray activity. Altho the period of half decay of radium itself is approximately 2,000 years, see table 102, the luminosity of the compound falls off, due to the fact that the *zinc sulfid loses its power to luminesce,* but not because the radium gives out. Some specifications for luminous paint, as for government work, stipulate that the zinc sulfid and radio-active substance shall be mixed in such proportions that the average useful life of the paint will be from 8 to 10 years.

The discovery of radio-activity has given us a vast field for research and as a result the physicist has been able to make subatomic investigations. Atoms are constantly exploding and shoot out as fragments, the alpha and beta particles. Altho the energy liberated by these explosions is fairly large, no diminution in the weight of the radio-active substance has been detected after the liberation of the energy. J. J. Thomson computed that the disintegration of one gram of hydrogen would liberate sufficient energy to raise a million tons 300 feet. See Fig. 103. If only this energy could be trapt, and recent research shows the possibility of it, Garfield and his coal-house gang would lose their job, for who would use ten tons of coal when one gram of hydrogen would give an equivalent heating value. Table 102 gives interesting data concerning the radio-active substances. In each series the first substance gives the second on disintegration and the second the third, etc. The second column gives the kind of radiation given off by the respective substances and the last column tells how long it takes for the substance to disintegrate to half of the original amount. This half-period means that after 2,000 years, for instance, one-half of the substance in question will have disintegrated. After 4,000 years, one-half of the remainder will have disintegrated or disappeared, etc., etc. The total life of pure Radium is computed from this law to be about 22,000 years.

(*To be continued*)

HISTORIC ELECTRIC SWITCH-BOARD AND DYNAMO.

(*Continued from page* 778)

field magnet type with surface wound armatures. There are quite a number of these generators still in existence in various parts of the country, and in tribute to their designer, it should be said that they perform their duty very well indeed, considering the time at which they were built, for thirty to thirty-five years in the electrical industry has, we might almost say, witnest the entire development of the whole scheme of electrical generation, transmission and utilization of power, under the directorship of such men as Edison, Thomson, Houston, Tesla, Westinghouse and Sprague.

The wooden switch-board, shown in the photograph, contains four box-type field rheostats, and it is peculiar to note that they are mounted on the face of the board instead of in the rear, as in present day practise.—*Photo by Richard Nelson.*

THE TESLA EGG OF COLUMBUS.

(*Continued from page* 775)

Tesla had other surprises for his audiences, which were even more wonderful. So, for instance, the coil on three legs, visible in the foreground, was used to operate wireless motors, lamps and other devices, and the spiral coil in the background served to show extraordinary high potential phenomena, as streamers of great length.

ULTRAVIOLET ENERGY AND ITS USE.

By M. Luckiesh, Physicist, Nela Research Laboratory.

Since the discovery of ultraviolet rays, more than a century ago, their production and properties have been subjected to a great deal of investigation. However, notwithstanding the extensive literature on the subject we must agree with Sheppard, who says in his book on Photo-chemistry:

"We are only at the beginning of the conscious utilization of the powers of light, as distinct from the unconscious enjoyment of them."

Owing to the many unique properties of these invisible rays, they are extremely valuable in certain scientific investigations, tests, and industrial processes, and it appears certain, that with the progress of the development of sources of ultraviolet rays, and of media transparent to them, the usefulness of ultraviolet energy will be rapidly extended. The problems in which these unique properties may be utilized are manifold.

As to Sources:—There are many sources of ultraviolet energy, but few are powerful enough to be widely useful. The ideal source, which emits a continuous non-banded spectrum of high intensity thruout the entire ultraviolet region, does not exist. Some of the sources are here ranked in order: magnetite arc, old mercury arc, new mercury arc, and carbon arc.

The blue flame arc emits ultraviolet energy very strongly. It is a simple matter to construct an arc which will emit ultraviolet energy strongly, provided hand-control is satisfactory. An iron rod and a carbon rod may be employed successfully for the two poles, however two iron rods may answer the purpose very well. These poles may be kept cool effectively by means of heavy brass or copper sleeves, which may be wound along the iron rods as the latter are consumed.

Uses of Ultraviolet Rays:—Ionization of air; powerful bactericidal agent; kill germs in water; effect upon animal tissue to bronze the skin. In industrial processes such as acetylene and arc welding, which are attended by powerful ultraviolet energy, there is a demand for eye-protecting glasses.

MY INVENTIONS.

(*Continued from page 907*)

was won. Back in the deep recesses of the brain was the solution, but I could not yet give it outward expression. One afternoon, which is ever present in my recollection, I was enjoying a walk with my friend in the City Park and reciting poetry. At that age I knew entire books by heart, word for word. One of these was Göethe's "Faust." The sun was just setting and reminded me of the glorious passage:

"Sie rückt und weicht, der Tag ist überlebt,
Dort eilt sie hin und fördert neues Leben.
Oh, dass kein Flügel mich vom Boden hebt
*Ihr nach und immer nach zu streben!"**

* * * * * * *

Ein schöner Traum indessen sie entweicht,
Ach, zu des Geistes Flügeln wird so leicht
Kein körperlicher Flügel sich gesellen!"†

As I uttered these inspiring words the idea came like a flash of lightning and in an instant the truth was revealed. I drew with a stick on the sand the diagrams shown six years later in my address before the American Institute of Electrical Engineers, and my companion understood them perfectly. The images I saw were wonderfully sharp and clear and had the solidity of metal and stone, so much so that I told him: "See my motor here; watch me reverse it." I cannot begin to describe my emotions. Pygmalion seeing his statue come to life could not have been more deeply moved. A thousand secrets of nature which I might have stumbled upon accidentally I would have given for that one which I had wrested from her against all odds and at the peril of my existence.

* "The glow retreats, done is the day of toil;
It yonder hastes, new fields of life exploring;
Ah, that no wing can lift me from the soil,
Upon its track to follow, follow soaring!"

† A glorious dream! though now the glories fade.
Alas! the wings that lift the mind no aid
Of wings to lift the body can bequeath me."

TESLA ON HIGH FREQUENCY GENERATORS.

Editor, ELECTRICAL EXPERIMENTER:

It is to be regretted that a letter addrest to me by Mr. J. Harris Rogers, in your care, was published in the march number of the ELECTRICAL EXPERIMENTER, altho the concurrence of our views in some wireless features might have made this desirable to so wide-awake and enterprising a periodical as yours.

Mr. Rogers seems to be a very appreciative gentleman and nothing would be farther from my thoughts than to detract anything from his merit, but in a separate contribution, which I expect to prepare for your next issue, I shall express myself on this subject without prejudice and in the interest of truth. However, the article by your Mr. H. Winfield Secor on "America's Greatest War Invention—The Rogers Underground Wireless" contains a reference to "a novel and original high frequency generator" of Mr. Rogers' invention. May I not —to use the President's elegant expression —call attention to the fact that this device was described by me years ago, as will be evident from the following excerpt of a communication which appeared in the *Electrical Review* of March 15, 1899. In speaking of circuit controllers, I said: "I may mention here, based on a different principle, which is incomparably more effective, more efficient, and also simpler on the whole. It comprises a fine stream of conducting fluid which is made to issue, with any desired speed, from an orifice connected with one pole of a generator, thru the primary of the induction coil, against the other terminal of the generator placed at a small distance. This device gives discharges of a remarkable suddenness, and the frequency may be

(*Continued on page 914*)

Foremen and Superintendents $1800 to $5000 Yearly

Office Manager or Auditor $1800 to $5000 Yearly



Engineers (all kinds) $2000 to $5000 Yearly

Learn to Fill Bigger Shoes

NO matter what kind of work you are doing now, a set of these great home study books will quickly fit you for a bigger and better paying job. We will send any set you select for one week's FREE examination, and if you want to keep them you pay only the special reduced price—at the rate of 50 cents a week. This is your opportunity to make more money—grasp it NOW. Use these books and a little spare time and LEARN TO FILL BIGGER SHOES.

Carpentry and Contracting
Five volumes, 2138 pages and more than 400 illustrations. Prepares for Contractor, Building Superintendent and Carpenter Foreman. Regular price, $25.00. Special price, $17.80.

Civil Engineering
Nine volumes, 3900 pages and 3000 illustrations, plates and diagrams. Prepares for Civil or Structural Engineer, Transitman, Estimator, Designer or Chief Draftsman. Regular price, $45.00. Special price, $29.80.

Telephony and Telegraphy
Four volumes, 1728 pages and 2000 illustrations, plates and diagrams. Prepares for Telephone Engineer, Wire Chief, Exchange Manager, Trouble Man or Telegrapher. Regular price, $20.00. Special price, $12.80.

Steam and Gas Engineering
Seven volumes, 3300 pages and 2500 illustrations, plates, diagrams, etc. Prepares for Stationary, Marine or Locomotive Engineer or Fireman. Regular price, $35.00. Special price, $21.80.

Law and Practice
(with Reading Course in 25 bound pamphlets). Thirteen volumes, 6000 pages and 24 illustrations. Prepares for all Bar Examinations. A wonderful aid to business men. Regular price, $72.00. Special price, $39.80.

Practical Accounting
Four volumes, 1840 pages and 800 illustrations, plates and diagrams. C. P. A. questions and practical problems. Prepares for Accountant, Bookkeeper or Cost Clerk. Regular price, $20.00. Special price, $12.80.

Pay Raisers

These books are written by well known authorities — the top-notchers in each line. They will help you make more money. You can't fail to understand them, because they are written in plain, everyday language. Thousands of photographs, diagrams, charts, etc., help to make difficult points as simple as A-B-C.

See our Free Examination—no money down offer below

Ask Our Experts

With these books goes free of all charge a $12.00 Consulting Membership in the American Technical Society. If any question puzzles you—write us. Our corps of experts and engineers will solve any problem. Ask all the questions you want for a whole year. This service is absolutely FREE.

Automobile Engineering
Five volumes, 2400 pages and 2000 illustrations. Prepares for Garage Foreman, Automobile Mechanic or Chauffeur. Invaluable to car owners. Regular price, $25.00. Special price, $17.80.

Machine Shop Practice
Six volumes, 2300 pages and 2500 illustrations. Prepares for Machine Shop Superintendent or Foreman, Foundryman, Pattern Maker, Tool Designer or Tool Maker. Regular price, $30.00. Special price, $19.80.

Sanitary, Heating and Ventilating Engin'ring
Four volumes, 1454 pages and more than 1400 illustrations, etc. Prepares for Sanitary Engineer, Heating and Ventilating Engineer, Master Plumber or Plumber. Regular price, $20.00. Special price, $13.80.

Mechanical and Architectural Drawing
Four volumes, 1578 pages and more than one thousand illustrations. Prepares for Architectural or Mechanical Draftsman. Regular price, $20.00. Special price, only $13.80.

Electrical Engineering
Seven volumes, 3000 pages and 2600 illustrations, plates and diagrams. Prepares for Electrical Engineer, Power Plant Superintendent, Substation Operator or Electrician. Regular price, $35.00. Special price, $19.80.

Accountancy and Business Management
Ten volumes, 3680 pages and 1987 illustrations, forms, etc. Prepares for Certified Public Accountant, Auditor, Office Manager, Accountant, Credit Man or Bookkeeper. Regular price, $50.00. Special price, $24.80.

DON'T SEND ANY MONEY!

Write the name of the books you want on the coupon and mail it today. We will send the books at once, express collect, and you can use them just as if they were your own for a whole week. If you decide you don't want to keep them, send them back at our expense. If you like the books, as thousands of other men have after examination, just send us $2.00. You can send the balance of the special reduced price the same way—$2.00 each month (50 cents a week).

Start right now and learn to fill bigger shoes. There will be a better job looking for you if you do. Be ready to meet it when it comes. *Send the coupon now.*

American Technical Society, Dept. T3384, Chicago, Ill.

American Technical Society, Dept. T3384, Chicago, Illinois

Please send me set of ——— for 7 days' examination, shipping charges collect. I will examine the books thoroughly and, if satisfied, will send $2 within 7 days and $2 each month until I have paid the special price of ——— If I decide not to keep the books, I will return them by express at your expense. Title not to pass to me until the set is fully paid for.

Name ———

Address ———

Reference ———

SEND THE COUPON NOW

PATENTS

TO THE MAN WITH AN IDEA

I offer a comprehensive, experienced, efficient service for his prompt, legal protection and the development of his proposition.

Send sketch, or model and description, for advice as to cost, search through prior United States patents, etc. Preliminary advice gladly furnished without charge.

My experience and familiarity with various arts frequently enable me to accurately advise clients as to probable patentability before they go to any expense.

Booklet of valuable information and form for properly disclosing your idea, free on request. Write today.

RICHARD B. OWEN, Patent Lawyer
164 Owen Building, Washington, D. C.
2276-8 Woolworth Bldg., New York City

PATENTS

INVENTORS: Send us sketches or a model of your invention and a description of the device for advice in regard to the best way of obtaining patent protection. Our practical experience covers a period of twenty years. Our hand-book on patents is sent free on request. All communications strictly confidential. Write us today.

TALBERT & TALBERT
Patent Lawyers
4287 Talbert Bldg. Washington, D. C.

PATENTS

LACEY & LACEY

Attorneys-at-Law—Patent Practice Exclusively
Solicitors of
U. S. and Foreign Patents
Trade-Marks, Copyrights

639 F Street, N. W., Washington, D. C.

Write Us for Our Free Inventors' Book
PATENT-SENSE
ESTABLISHED 1869

Competent Patent Service
By a Former Examining Official of the U. S. Patent Office
NORMAN T. WHITAKER
Lawyer and Engineer
480 Whitaker Bldg. Washington, D. C.
Branch Office, 87 Nassau St., New York City.
INQUIRIES INVITED

DRAFTING
Inventions and Ideas Developed!
Mechanical, Electrical, Patent Office and Engineering Drawings of Every Description.
COMPETENT DRAFTSMEN AT YOUR SERVICE
A. G. HAGSTROM
116 Nassau St. New York City
Telephone Beekman 4589

Acetylene Bunsen Burner.

(312) Richard E. Mathes, Excelsior, Minn., writes: "I have devised a scheme whereby an acetylene gas plant for bunsen burners and gas in a small chemical laboratory may be installed at very low cost. This is meant especially for the amateur who does not have gas in his home. Is this practical? Could I sell a patent for it? If so, what would it be worth? Could I use an ordinary hunsen burner as part of the patent without infringement?"

A. We see nothing fundamentally new about this idea, as burners of this kind have been used for years, and such a device is well known in the art. We are quite positive that a patent could not be obtained upon it.

Double Lock.

(313) Chas. H. Morgan, Newton, Iowa, sends in an idea on a Double Hasp Lock which can be operated from both sides of the door. He wants to know if this device can be patented.

A. We see nothing fundamentally new in this, and furthermore douht the utility of the device. We also doubt if a patent can be obtained on it.

Envelope.

(314) José Mata, San Francisco, Cal., submits a sample of an envelope. He wishes us to give him our advice if such an envelope could be patented and if it is feasible. As will be noted, a string with a knot at each end is glued into the envelope when made.

A. This is a good idea but it is not new. Similar devices have been on the market for a long time, and some years ago very many magazines used a string of this kind to open up the mailing wrapper, simply by having a thread incorporated into the magazine wrapper. This thread was pulled in a similar fashion as the string of our correspondent's envelope. We are positive no patent can be obtained on this device.

Automatic Fuse Replacer.

(315) Wm. Sambur, New York City, says: "I would like to know if an automatic fuse replacer which instantly inserts new fuses after extracting burnt out fuses would be patentable. This device could be manufactured at a cost of $3.00. Would this be a good selling article? I await anxiously the next issue of the ELECTRICAL EXPERIMENTER for my answer."

A. Without having the necessary details, it is impossible for us to give advice. Correspondents should bear in mind that merely by giving vague indications, it is extremely dangerous for us to give advice as well as for correspondents to accept it.

Smoke Stack.

(316) Walter A. Buckheim, Boulder, Colo., asks us: "Please let me know thru your magazine if the following idea is patentable. It is desired to construct a chimney or factory smoke stack with rifles or vanes which will impart a rotary motion to the escaping gases. In forced draft plants the gases can be given a rotary motion by mechanical means. In this way a miniature whirlwind will be created which will hold the gases in a narrow column and carry them to a great height, where especially, if they are poisonous, they will be out of everyone's way. The gases will in effect pass thru a chimney made of air."

A. This is a clever idea, but it has one great fault, namely, it won't work. No matter what arrangement were used and even if you were to expend 10,000 H. P. to push the gases out of the smoke stack, if a moderately strong wind was blowing the gases would positively be forced sidewise, and if the wind was blowing earthward, the gases in this case would be blown earthward too. You cannot hope to raise a gaseous column into the air and prevent its swaying sidewise by any known means. For this reason smelters and chemical industries having to do with poisonous gases build their chimneys as high as possible. There are some cases known where a chimney has actually been laid up the side of a moderate mountain in order to let the gases escape at the top as far away from human habitation as possible.

Radio Break-In System.

(317) C. E. Mitchell, Miami, Fla., submits for our advice the following idea: "I have a break-in system for use in wireless telegraphy that does away with anchor gaps and other troublesome apparatus used in break-in systems. It consists of the ordinary heavy wireless key, with an attachment at the rear, working something similar to a compound lever. When the key is raised the antenna is connected to the receiver, the detector unshorted, and circuit to power transformer opened. In this manner the receiver is always in a receptive condition at the instant the key is raised. The idea provides for an extension in length to the ordinary wireless key and may be installed in any circuit with ease and does not hamper the pressure adjustment of the key. This means of break-in will prevent considerable interference and loss of time.

A. This is not at all a new idea and the Patent Office is full of break-in systems of this kind. A great many similar ones have been described in the past volumes of the ELECTRICAL EXPERIMENTER. Many of these systems are very good, as is our correspondent's, and many are actually in use, particularly amateurs seem to like them.

NEW PULL SOCKET HAS CURRENT TAP.

In many cases it is desirable to connect an electrical appliance to a single-lamp wall bracket or ceiling fixture without interfering with the lamp. A very convenient way for doing this has been provided by means of the new pull socket current tap illustrated. It is a combination pull socket and plug receptacle built into a single compact body. It is also supplied with a ⅛", ¼", ⅜" or pendent cap. The pull chain controls the current to the lamp socket proper, whereas the terminals of the receptacle in the side of the body are continuously in circuit.

An advantage that this type of socket gives is that it eliminates the annoyance of the long cord running from side-wall outlets. By means of the new fitting, current can be supplied directly below the fixture

to operate various table appliances or other portable devices such as are in general use, without sacrificing the use of light from the lamp itself. It thus eliminates the annoyance of groping about in the dark while trying to plug into the socket.

AERONAUTICAL EXPOSITION AT NEW YORK.

Army Day at the Aeronautical Exposition in Madison Square Garden and the 69th Regiment Armory, New York City, brought several thousand uniformed spectators at the afternoon and evening sessions. Secretary of War Newton D. Baker was to have been the guest of honor, but at the last minute he notified the officials of the exposition that he had been summoned by the President for a conference. Major General Thomas Barry, Commandant of the Department of the East, accompanied by members of his staff, represented the Secretary of War.

At the wireless telephone exhibit in the 69th Regiment Armory, Lieutenant J. F. Adams entertained the spectators by reading news from a daily newspaper to ships in the harbor and places on land equipt with apparatus. The spectators, by means of a sounding horn, were able to hear the answers he received.

Brigadier General Guy Livingston, who represented the British Air Ministry in this country, was an interested spectator at the afternoon session. He said that he believed the Atlantic would be crost by airplane or dirigible within the next two or three months.

TESLA ON HIGH FREQUENCY GENERATORS.

(*Continued from page* 909)

brought within reasonable limits, almost to anything desired. I have used this device for a long time in connection with ordinary coils and in a form of my own coil with results greatly superior in every respect to those obtainable with the form of your letter, make a few statements referring to such make-and-break devices in general, and various forms based on this new principle."

I may add that a great many forms of this apparatus were constructed and employed by me for a long time, proving very convenient and useful. Water does not give particularly good results, being incapable of causing very abrupt changes, but electrolytes have the property of diminishing enormously in resistance when they are heated and the effects are much more intense. Salts of lithium are especially efficient.

NIKOLA TESLA.

New York, February 20, 1919.



RADIO DEPARTMENT



The True Wireless

By NIKOLA TESLA

Written Exclusively for The Electrical Experimenter

EVER since the announcement of Maxwell's electro-magnetic theory scientific investigators all the world over had been bent on its experimental verification. They were convinced that it would be done and lived in an atmosphere of eager expectancy, unusually favorable to the reception of any evidence to this end. No wonder then that the publication of Dr. Heinrich Hertz's results caused a thrill as had scarcely ever been experienced before. At that time I was in the midst of pressing work in connection with the commercial introduction of my system of power transmission, but, nevertheless, caught the fire of enthusiasm and fairly burned with desire to behold the miracle with my own eyes. Accordingly, as soon as I had freed myself of these imperative duties and resumed research work in my laboratory on Grand Street, New York, I began, parallel with high frequency alternators, the construction of several forms of apparatus with the object of exploring the field opened up by Dr. Hertz. Recognizing the limitations of the devices he had employed, I concentrated my attention on the production of a powerful induction coil but made no notable progress until a happy inspiration led me to the invention of the oscillation transformer. In the latter part of 1891 I was already so far advanced in the development of this new principle that I had at my disposal means vastly superior to those of the German physicist. All my previous efforts with Rhumkorf coils had left me unconvinced, and in order to settle my doubts I went over the whole ground once more, very carefully, with these improved appliances. Similar phenomena were noted, greatly magnified in intensity, but they were susceptible of a different and more plausible explanation. I considered this so important that in 1892 I went to Bonn, Germany, to confer with Dr. Hertz in regard to my observations. He seemed disappointed to such a degree that I regretted my trip and parted from him sorrowfully. During the succeeding years I made numerous experiments with the same object, but the results were uniformly negative. In 1900, however, after I had evolved a wireless transmitter which enabled me to obtain electro-magnetic activities of many millions of horse-power, I made a last desperate attempt to prove that the disturbances emanating from the oscillator were ether vibrations akin to those of light, but met again with utter failure. For more than eighteen years I have been reading treatises, reports of scientific transactions, and articles on Hertz-wave telegraphy, to keep myself informed, but they have always imprest me like works of fiction.



Alternator of 10,000 Cycles p.s., Capacity 10 K.W., Which Was Employed by Tesla in His First Demonstrations of High Frequency Phenomena Before the American Institute of Electrical Engineers at Columbia College, May 20, 1891. Fig. 1.



Diagram Illustrating the Circuit Connections and Tuning Devices Employed by Tesla in His Experimental Demonstrations Before the American Institute of Electrical Engineers With the High Frequency Alternator Shown in Fig. 1. Fig. 2.

The history of science shows that theories are perishable. With every new truth that is revealed we get a better understanding of Nature and our conceptions and views are modified. Dr. Hertz did not discover a new principle. He merely gave material support to a hypothesis which had been long ago formulated. It was a perfectly well-established fact that a circuit, traversed by a periodic current, emitted some kind of space waves, but we were in ignorance as to their character. He apparently gave an experimental proof that they were transversal vibrations in the ether. Most people look upon this as his great accomplishment. To my mind it seems that his immortal merit was not so much in this as in the focusing of the investigators' attention on the processes taking place in the ambient medium. The Hertz-wave theory, by its fascinating hold on the imagination, has stifled creative effort in the wireless art and retarded it for twenty-five years. But, on the other hand, it is impossible to over-estimate the beneficial effects of the powerful stimulus it has given in many directions.

As regards signaling without wires, the application of these radiations for the purpose was quite obvious. When Dr. Hertz was asked whether such a system would be of practical value, he did not think so, and he was correct in his forecast. The best that might have been expected was a method of communication similar to the heliographic and subject to the same or even greater limitations.



Electric Transmission Thru Two Wires and Hydraulic Analog. Fig. 3.

In the spring of 1891 I gave my demonstrations with a high frequency machine before the American Institute of Electrical Engineers at Columbia College, which laid the foundation to a new and far more promising departure. Altho the laws of electrical resonance were well known at that time and my lamented friend, Dr. John Hopkinson, had even indicated their specific application to an alternator in the Proceedings of the Institute of Electrical Engineers, London, Nov. 13, 1889, nothing had been done towards the practical use of this knowledge and it is probable that those experiments of mine were the first public exhibition with resonant circuits, more particularly of high frequency. While the spontaneous success of my lecture was due to spectacular features, its chief import was in showing that all kinds of devices could be operated thru a single wire without return. This was the initial step in the evolution of my wireless system. The idea presented itself to me that it might be possible, under ob-



Electric Transmission Thru a Single Wire Hydraulic Analog. Fig. 4.

IN this remarkable and complete story of his discovery of the "True Wireless" and the principles upon which transmission and reception, even in the present day systems, are based, Dr. Nikola Tesla shows us that he is indeed the "Father of the Wireless." To him the Hertz wave theory is a delusion; it looks sound from certain angles, but the facts tend to prove that it is hollow and empty. He convinces us that the real Hertz waves are blotted out after they have traveled but a short distance from the sender. It follows, therefore, that the measured antenna current is no indication of the effect, because only a small part of it is effective at a distance. The limited activity of pure Hertz wave transmission and reception is here clearly explained, besides showing definitely that in spite of themselves, the radio engineers of today are employing the original Tesla tuned oscillatory system. He shows by examples with different forms of aërials that the signals picked up by the instruments must actually be induced by earth currents—not etheric space waves. Tesla also disproves the "Heaviside layer" theory from his personal observations and tests.

EDITOR.



Illustrating Typical Arrangements for Collecting Energy in a System of Transmission Thru a Single Wire. Fig. 5.

servance of proper conditions of resonance, to transmit electric energy thru the earth, thus dispensing with all artificial conductors. Anyone who might wish to examine impartially the merit of that early suggestion must not view it in the light of present day science. I only need to say that as late as 1893, when I had prepared an elaborate chapter on my wireless system, dwelling on its various instrumentalities and future prospects, Mr. Joseph Wetzler and other friends of mine emphatically protested against its publication on the ground that such idle and far-fetched speculations would injure me in the opinion of conservative business men. So it came that only a small part of what I had intended to say was embodied in my address of that year before the Franklin Institute and National Electric Light Association under the chapter "On Electrical



Diagram Elucidating Effect of Large Capacity on One End. Fig. 6.

Resonance." This little salvage from the wreck has earned me the title of "Father of the Wireless" from many well-disposed fellow workers, rather than the invention of scores of appliances which have brought wireless transmission within the reach of every young amateur and which, in a time not distant, will lead to undertakings overshadowing in magnitude and importance all past achievements of the engineer.

The popular impression is that my wireless work was begun in 1893, but as a matter of fact I spent the two preceding years in investigations, employing forms of apparatus, some of which were almost like those of today. It was clear to me from the very start that the successful consummation could only be brought about by a number of radical improvements. Suitable high frequency generators and electrical oscillators had first to be produced. The energy of these had to be transformed in effective transmitters and collected at a distance in proper receivers. Such a system would be manifestly circumscribed in its usefulness if all extraneous interference were not prevented and exclusiveness secured. In time, however, I recognized that devices of this kind, to be most effective and efficient, should be designed **with due regard to the physical properties of this planet and the electrical conditions obtaining on the same.** I will briefly touch upon the salient advances as they were made in the gradual development of the system.



Transmission of Electrical Energy Thru the Earth as Illustrated in Tesla's Lectures Before the Franklin Institute and Electric Light Association in February and March, 1893, and Mechanical Analog of the Same. Fig. 7.

The high frequency alternator employed in my first demonstrations is illustrated in Fig. 1. It comprised a field ring, with 384 pole projections and a disc armature with coils wound in one single layer which were connected in various ways according to requirements. It was an excellent machine for experimental purposes, furnishing sinusoidal currents of from 10,000 to 20,000 cycles per second. The output was comparatively large, due to the fact that as much as 30 amperes per square millimeter could be past thru the coils without injury.

The diagram in Fig. 2 shows the circuit arrangements as used in my lecture. Resonant conditions were maintained by means



Tesla's System of Wireless Transmission Thru the Earth as Actually Exposed in His Lectures Before the Franklin Institute and Electric Light Association in February and March, 1893. Fig. 8.

of a condenser subdivided into small sections, the finer adjustments being effected by a movable iron core within an inductance coil. Loosely linked with the latter was a high tension secondary which was tuned to the primary.

The operation of devices thru a single wire without return was puzzling at first because of its novelty, but can be readily explained by suitable analogs. For this purpose reference is made to Figs. 3 and 4.

In the former the low resistance electric conductors are represented by pipes of large section, the alternator by an oscillating piston and the filament of an incandescent lamp by a minute channel connecting the pipes. It will be clear from a glance at the diagram that very slight excursions of the piston would cause the fluid to rush with high velocity thru the small channel and that virtually all the energy of movement would be transformed into heat by friction, similarly to that of the electric current in the lamp filament.



The Forerunner of the Audion—the Most Sensitive Wireless Detector Known, as Described by Tesla in His Lecture Before the Institution of Electrical Engineers, London, February, 1892. Fig. 9.

The second diagram will now be self-explanatory. Corresponding to the terminal capacity of the electric system an elastic reservoir is employed which dispenses with the necessity of a return pipe. As the piston oscillates the bag expands and contracts, and the fluid is made to surge thru the restricted passage with great speed, this


SYSTEM OF CONCATENATED TUNED CIRCUITS SHOWN AND DESCRIBED IN TESLA'S U.S. PATENT No. 568,178 of Sept. 22, 1896, AND CORRESPONDING ARRANGEMENTS IN WIRELESS TRANSMISSION
WIRELESS TRANSMITTER
Adjustable Inductance
Primary Condenser
Source of impulses of arbitrary frequency
Adjustable Inductance
WIRELESS RECEIVER
Tuned secondary with adjustable capacity
Circuit controller in synchronism with impulses
Primary
Circuit
I
II
III
IV
THE FOUR TUNED CIRCUITS OF ABOVE DIAGRAM SHOWN SEPARATELY
Energizing circuit (I) supplying oscillations of arbitrary frequency
Adjustable inductance
Transforming circuit (II) tuned to frequency of circuit (I) or a harmonic of the same
Adjustable inductance
Discharge circuit (III) similarly tuned
Transforming Circuit (IV) similarly tuned
Adjustable capacity
THE CORRESPONDING FOUR TUNED CIRCUITS OF THE WIRELESS SYSTEM
Energizing wireless primary I supplying oscillations of arbitrary frequency
Wireless transforming circuit II tuned to frequency of circuit I or a harmonic of the same
Wireless receiving circuit III similarly tuned
Wireless transforming circuit IV similarly tuned
Adjustable capacity
Adjustable inductance
Adjustable inductance
Fig. 10.

Tesla's System of Concatenated Tuned Circuits Shown and Described in U. S. Patent No. 568,178 of September 22, 1896, and Corresponding Arrangements in Wireless Transmission.

resulting in the generation of heat as in the incandescent lamp. Theoretically considered, the efficiency of conversion of energy should be the same in both cases.

Granted, then, that an economic system of power transmission thru a single wire is



Tesla's Four Circuit Tuned System Contrasted With the Contemporaneous Hertz-wave System. Fig. 11.

practicable, the question arises how to collect the energy in the receivers. With this object attention is called to Fig. 5, in which a conductor is shown excited by an oscillator joined to it at one end. Evidently, as the periodic impulses pass thru the wire, differences of potential will be created along the same as well as at right angles to it in the surrounding medium and either of these may be usefully applied. Thus at *a*, a circuit comprising an inductance and capacity is resonantly excited in the transverse, and at *b*, in the longitudinal sense. At *c*, energy is collected in a circuit parallel to the conductor but not in contact with it, and again at *d*, in a circuit which is partly sunk into the conductor and may be, or not, electrically connected to the same. It is important to keep these typical dispositions in mind, for however the distant ac-


Transmitting Circuit
Forms of Receiving Circuits
Transmitting Circuit connected to two points of the ground
Receiving Circuit grounded on one or both ends
Source of high frequency currents

Arrangements of Directive Circuits Described in Tesla's U. S. Patent No. 613,809 of November 8, 1898, on "Method of and Apparatus for Controlling Mechanism of Moving Vessels or Vehicles." Fig. 12.

tions of the oscillator might be modified thru the immense extent of the globe the principles involved are the same.

Consider now the effect of such a conductor of vast dimensions on a circuit exciting it. The upper diagram of Fig. 6 illustrates a familiar oscillating system comprising a straight rod of self-inductance $2L$ with small terminal capacities cc and a node in the center. In the lower diagram of the figure a large capacity C is attached to the rod at one end with the result of shifting the node to the right, thru a distance corresponding to self-inductance X. As both parts of the system on either side of the node vibrate at the same rate, we have evidently, $(L + X)\ c = (L - X)\ C$ from which $X = L \frac{C - c}{C + c}$. When the capacity C becomes commensurate to that of the earth, X approximates L, in other words, the node is close to the ground connection. *The exact determination of its position is very important in the calculation of certain terrestrial electrical and geodetic data* and I have devised special means with this purpose in view.

My original plan of transmitting energy without wires is shown in the upper diagram of Fig. 7, while the lower one illustrates its mechanical analog, first publisht in my article in the *Century Magazine* of June, 1900. An alternator, preferably of high tension, has one of its terminals connected to the ground and the other to an elevated capacity and impresses its oscillations upon the earth. At a distant point a receiving circuit, likewise connected to ground and to an elevated capacity, collects some of the energy and actuates a suitable device. I suggested a multiplication of such units in order to intensify the effects, an idea which may yet prove valuable. In the analog two tuning forks are provided, one at the sending and the other at the receiving station, each having attached to its lower prong a piston fitting in a cylinder. The two cylinders communicate with a large elastic reservoir filled with an incom-


Hertz waves passing off into space through the earth's atmosphere
TRANSMITTER
Hertz waves extinct
Hertz waves extinct
Resultant current through earth

Diagram Exposing the Fallacy of the Gliding Wave Theory as Propounded in Wireless Text Books. Fig. 13.

pressible fluid. The vibrations transmitted to either of the tuning forks excite them by resonance and, thru electrical contacts or otherwise, bring about the desired result. This, I may say, was not a mere mechanical illustration, but a simple representation of my apparatus for submarine signaling, perfected by me in 1892, but not appreciated at that time, altho more efficient than the instruments now in use.

The electric diagram in Fig. 7, which was reproduced from my lecture, was meant only for the exposition of the principle. The arrangement, as I described it in detail, is shown in Fig. 8. In this case an alternator energizes the primary of a transformer, the high tension secondary of which is connected to the ground and an elevated capacity and tuned to the imprest oscillations. The receiving circuit consists of an inductance connected to the ground and to an elevated terminal without break and is resonantly responsive to the transmitted oscillations. A specific form of receiving device was not mentioned, but I had in mind to transform the received currents and thus make their volume and tension suitable for any purpose. This, in substance, is the system of today and I am not aware of a single authenticated instance of successful transmission at considerable distance by different instrumentalities. It might, perhaps, not be clear to



Fig. 14. Diagram Explaining the Relation Between the Effective and the Measured Current in the Antenna.

those who have perused my first description of these improvements that, besides making known new and efficient types of apparatus, I gave to the world a wireless system of potentialities far beyond anything before conceived. I made explicit



Fig. 15. Illustrating One of the General Evidences Against the Space Wave Transmission.

and repeated statements that I contemplated transmission, absolutely unlimited as to terrestrial distance and amount of energy. But, altho I have overcome all obstacles which seemed in the beginning unsurmountable and found elegant solutions of all the problems which confronted me, yet, even at this very day, the majority of experts are still blind to the possibilities which are within easy attainment.

My confidence that a signal could be easily flashed around the globe was strengthened thru the discovery of the "rotating brush," a wonderful phenomenon which I have fully described in my address before the Institution of Electrical Engineers, London, in 1892, and which is illustrated in Fig. 9. This is undoubtedly the most delicate wireless detector known, but for a long time it was hard to produce and to maintain in the sensitive state. These difficulties do not exist now and I am looking to valuable applications of this device, particularly in connection with the high-speed photographic method, which I suggested, in wireless, as well as in wire, transmission.

Possibly the most important advances during the following three or four years were my system of concatenated tuned circuits



Fig. 16. Showing Unimportance of Relative Position of Transmitting and Receiving Antennae in Disproval of the Hertz-wave Theory.

and methods of regulation, now universally adopted. The intimate bearing of these inventions on the development of the wireless art will appear from Fig. 10, which illus-

(*Continued on page* 61)

The True Wireless

By Nikola Tesla

(*Continued from page 30*)

trates an arrangement described in my U. S. Patent No. 568178 of September 22, 1896, and corresponding dispositions of wireless apparatus. The captions of the individual diagrams are thought sufficiently explicit to dispense with further comment. I will merely remark that in this early record, in addition to indicating how any number of resonant circuits may be linked and regulated, I have shown the advantage of the proper timing of primary impulses and use of harmonics. In a farcical wireless suit in London, some engineers, reckless of their reputation, have claimed that my circuits were not at all attuned; in fact they asserted that I had looked upon resonance as a sort of wild and untamable beast!

It will be of interest to compare my system as first described in a Belgian patent of 1897 with the Hertz-wave system of that period. The significant differences between them will be observed at a glance. The first enables us to transmit economically energy to any distance and is of inestimable value; the latter is capable of a radius of only a few miles and is worthless. In the first there are no spark-gaps and the actions are enormously magnified by resonance. In both transmitter and receiver the currents are transformed and rendered more effective and suitable for the operation of any desired device. Properly constructed, my system is safe against static and other interference and the amount of energy which may be transmitted is *billions of times greater* than with the Hertzian which has none of these virtues, has never been used successfully and of which no trace can be found at present.

A well-advertised expert gave out a statement in 1899 that my apparatus did not work and that it would take 200 years before a message would be flashed across the Atlantic and he even accepted stolidly my congratulations on a supposed great feat. But subsequent examination of the records showed that my devices were secretly used all the time and ever since I learned of this I have treated these Borgia-Medici methods with the contempt in which they are held by all fair-minded men. The wholesale appropriation of my inventions was, however, not always without a diverting side. As an example to the point I may mention my oscillation transformer operating with an air gap. This was in turn replaced by a carbon arc, quenched gap, an atmosphere of hydrogen, argon or helium, by a mechanical break with oppositely rotating members, a mercury interrupter or some kind of a vacuum bulb and by such *tours de force* as many new "systems" have been produced. I refer to this of course, without the slightest ill-feeling, let us advance by all means. But I cannot help thinking how much better it would have been if the ingenious men, who have originated these "systems," had invented something of their own instead of depending on me altogether.

Before 1900 two most valuable improvements were made. One of these was my individualized system with transmitters emitting a wave-complex and receivers comprising separate tuned elements coöperatively associated. The underlying principle can be explained in a few words. Suppose that there are n simple vibrations suitable for use in wireless transmission, the probability that any one tune will be struck by an extraneous disturbance is $\frac{1}{n}$. There will then remain $n-1$ vibrations and the chance that one of these will be excited is $\frac{1}{n-1}$, hence the probability that two tunes would

WANTED!

OFFICE MEN
Auditors, Accountants, Office Managers, Credit Men, Cashiers, Bookkeepers and Cost Clerks—$1,200 to $7,500.

FACTORY MEN
Electrical and Mechanical Engineers, Factory Managers, Superintendents, Foremen, Designers, Draftsmen—$1,500 to $12,000.

CONSTRUCTION MEN
Civil and Structural Engineers, Transitmen, Construction Superintendents and Foremen, Estimators, Designers and Draftsmen—$1,200 to $10,000.

TRADES—Machinists and Toolmakers, Auto Repairers, Electricians, Stationary Engineers, Firemen, Plumbers, Carpenters, etc.—$1,200 to $2,000.

All these positions were advertised in a single issue of a Chicago newspaper

Which Job Can You Fill?

Which one of them could *you* fill? If you haven't the knowledge necessary to break into the *big-pay class*, decide to *get that knowledge NOW!* Any of the books listed below will quickly fit you for a well-paid job—at home—in your spare time.

These books were written by experts in plain, everyday language. They are free from puzzling technical terms. Numerous illustrations, diagrams and tables make difficult points as simple as A-B-C. They are handsomely bound in half or full leather (except Law and Practice, which is bound in law buckram) and stamped in gold. Fill out the coupon.



Carpentry and Contracting
Five volumes, 2138 pages and more than 400 illustrations. Prepares for Contractor, Building Superintendent and Carpenter Foreman. Regular price, $25.00. Special price, $17.80.

Fire Prevention and Insurance
Four volumes, 1500 pages and 600 illustrations, diagrams, forms, etc. Prepares for Counterman, Rate Clerk, Inspector or Agent. Regular price, $20.00. Special price, $15.80.

Civil Engineering
Nine volumes, 3900 pages and 3000 illustrations, plates and diagrams. Prepares for Civil or Structural Engineer, Transitman, Estimator, Designer or Chief Draftsman. Regular price, $45.00. Special price, $29.80.

Electrical Engineering
Seven volumes 3000 pages and 2600 illustrations, plates and diagrams. Prepares for Electrical Engineer, Power Plant Superintendent, Substation Operator or Electrician. Regular price, $35.00. Special price, $19.80.

Telephony and Telegraphy
Four volumes, 1728 pages and 2000 illustrations, plates and diagrams. Prepares for Telephone Engineer, Wire Chief, Exchange Manager, Trouble Man or Telegrapher. Regular price, $20.00. Special price, $12.80.

Accountancy and Business Management
Ten volumes, 3680 pages and 1987 illustrations, forms, etc. Prepares for Certified Public Accountant, Auditor, Office Manager, Accountant, Credit Man or Bookkeeper. Regular price, $60.00. Special price, $24.80.

Automobile Engineering
Five volumes, 2400 pages and 2000 illustrations. Prepares for Garage Foreman, Automobile Mechanic or Chauffeur. Invaluable to car owners. Regular price, $25.00. Special price, $17.80.

Steam and Gas Engineering
Seven volumes, 3300 pages and 2500 illustrations, plates, diagrams, etc. Prepares for Stationary, Marine or Locomotive Engineer or Fireman. Regular price, $35.00. Special price, $21.80.

Machine Shop Practice
Six volumes, 2300 pages and 2500 illustrations. Prepares for Machine Shop Superintendent or Foreman, Foundryman, Pattern Maker, Tool Designer or Tool Maker. Regular price, $30.00. Special price, $19.80.

Law and Practice
(with Reading Course in 25 bound pamphlets). Thirteen volumes, 6000 pages and 24 illustrations. Prepares for all Bar Examinations. A wonderful aid to business men. Regular price, $72.00. Special price, $39.80.

Sanitary, Heating and Ventilating Engin'ring
Four volumes, 1454 pages and more than 1400 illustrations, etc. Prepares for Sanitary Engineer, Heating and Ventilating Engineer, Master Plumber or Plumber. Regular price, $20.00. Special price, $13.80.

Practical Accounting
Four volumes, 1840 pages and 800 illustrations, plates and diagrams. C. P. A. questions and practical problems. Prepares for Accountant, Bookkeeper or Cost Clerk. Regular price, $20.00. Special price, $12.80.

One Week Free Trial

We'll gladly send you any set for seven days' examination. Don't send us a penny; just pay the small shipping charge when the books arrive. Examine them carefully—use them at your work for an entire week. At the end of that time, if you feel they aren't worth far more than we ask, return them *at our expense*. If you keep them, pay the bargain price on the easy terms explained below.

American Technical Society
Dept. X3385 **Chicago, U. S. A.**

50c A WEEK

Yes, if you decide to keep the set you have selected, send $2 within seven days and then $2 a month (*50c a week*) until the present low price has been paid. Have you ever heard of a more generous offer? Remember, you take no chances whatever—we send the books for examination and you are not obliged to keep them if you do not care to buy. Mail the coupon *now*—before you turn the page.

American Technical Society, Dept. X3385, Chicago, Ill.

Please send me set of ..... for 7 days' examination, shipping charges collect. I will examine the books thoroughly and, if satisfied, will send $2 within 7 days and $2 each month until I have paid the special price of ..... If I decide not to keep the books, I will return them by express at your expense. Title not to pass to me until the set is fully paid for.

Name .....

Address .....

Reference .....

Learn Watchwork, Jewelrywork and Engraving A fine trade commanding a good salary, and your services are always in demand. Address HOROLOGICAL Department, Bradley Institute, Peoria, Ill., for our latest catalog.

WRITE THE WORDS FOR A SONG
We write music, guarantee publisher's acceptance. Submit poems on patriotism, love or any subject.
CHESTER MUSIC COMPANY
918 S. Michigan Ave., Room 313 Chicago, Illinois

FOR THOSE WHO LOVE GOOD MUSIC



The Ellis "Music Master" Reproducer

Will make your Talking Machine "The Soul of the Living Artist"

NO ordinary sound-box can reproduce a composition as originally played or sung by the artist. The true tone coloring is lacking—the beautiful overtones completely lost. And if not perfectly adjusted the ordinary reproducer vibrates, causing a harsh and shrill tone so commonly associated with mechanical music.

But with the Ellis "Music Master" Reproducer all this is changed. Every shade of expression that originally went into the record is faithfully and accurately reproduced. By its special, improved features and construction all harsh discordant sounds are eliminated and the music flows out in a clear, round tone exactly as if the artist himself were in your home, playing or singing at his very best.

You must hear the "Music-Master" to apppreciate its great merit

It took 10 years of hard study and constant experimenting to develop this one reproducer that faithfully brings to life all there is in the record.

Words cannot convey to you an adequate idea of how much this wonderful device will do to improve the playing of records. You must see it—hear it—compare the effect with any and all other reproducers you know of; then you will understand why every music-lover owner of a phonograph who hears the "Music-Master" Reproducer wants to own one.

For all machines— Plays all Records

No matter what style, size or make of talking machine you have if it uses disc records you can use the Ellis "Music-Master" and enjoy the *real* music. Easily put on, it prolongs the life of the records, because it is much lighter in weight than other reproducers. And the price is so low that you cannot afford to be without it—it will double the worth of your instrument.

Write today for full details

Thousands of satisfied users attest to the *real* value of my reproducer. I want to send you some of their letters and tell you more about my "Music-Master". Fill in and mail the coupon below for full particulars. Ask for Circular E.

J. H. ELLIS Patentee and Manufacturer P. O. Box 882 MILWAUKEE, WIS.

Mail this Coupon Now!

J. H. ELLIS. P. O. Box 882, Milwaukee, Wis.

Please send me full information about the Ellis "Music-Master" Reproducer.

Name .....

Address .....

City ..... State .....

Make Big Profits in Battery Charging

$150 to $250 Clear Profit Each Month recharging auto storage batteries. The HB 16-Battery Charger recharges 1 to 16 6-volt batteries or their equivalent at once with current cost of 12c to 15c per battery. Motorist pays 75c to $1.50. Figure your profits! This season means bigger battery business than ever—more old cars driven—new Fords to have storage batteries. Get busy now! Don't delay! Start after those profits!

$57 Puts This Money-Maker in Your Garage on Money-Back Guarantee

Balance in 10 monthly payments of $23. each. Earnings pay for machine. No electrical knowledge necessary to operate. Uses 2 or 3 phase city current. Furnished complete with 2 charging panels capable of charging 1 to 8 batteries each. No adjustments or expensive renewals. Big, permanent profits. Sold on HB Absolute Money Back Guarantee. Order Now—you run no risk. Pin your check to this ad and mail today for trial order. Do it NOW!

Hobart Brothers Company, Box 5E, Troy, Ohio. Successful Manufacturers Since 1893.

be struck at the same time is $\frac{1}{n\,(n-1)}$. Similarly, for a combination of three the chance will be $\frac{1}{n\,(n-1)\,(n-2)}$ and so on. It will be readily seen that in this manner any desired degree of safety against the statics or other kind of disturbance can be attained provided the receiving apparatus is so designed that its operation is possible only thru the joint action of all the tuned elements. This was a difficult problem which I have successfully solved so that now *any desired number of simultaneous messages is practicable in the transmission thru the earth as well as thru artificial conductors.*

The other invention, of still greater importance, is a peculiar oscillator enabling the transmission of energy without wires in any quantity that may ever be required for industrial use, to any distance, and with very high economy. It was the outcome of years of systematic study and investigation and wonders will be achieved by its means.

The prevailing misconception of the mechanism involved in the wireless transmission has been responsible for various unwarranted announcements which have misled the public and worked harm. By keeping steadily in mind that the transmission thru the earth is in every respect identical to that thru a straight wire, one will gain a clear understanding of the phenomena and will be able to judge correctly the merits of a new scheme. Without wishing to detract from the value of any plan that has been put forward I may say that they are devoid of novelty. So for instance in Fig. 12 arrangements of transmitting and receiving circuits are illustrated, which I have described in my U. S. Patent No. 613809 of November 8, 1898 on a Method of and Apparatus for Controlling Mechanism of Moving Vessels or Vehicles, and which have been recently dished up as original discoveries. In other patents and technical publications I have suggested conductors in the ground as one of the obvious modifications indicated in Fig. 5.

For the same reason the statics are still the bane of the wireless. There is about as much virtue in the remedies recently proposed as in hair restorers. *A small and compact apparatus has been produced which does away entirely with this trouble,* at least in plants suitably remodelled.

Nothing is more important in the present phase of development of the wireless art than to dispose of the dominating erroneous ideas. With this object I shall advance a few arguments based on my own observations *which prove that Hertz waves have little to do with the results obtained even at small distances.*

In Fig. 13 a transmitter is shown radiating space waves of considerable frequency. It is generally believed that these waves pass along the earth's surface and thus affect the receivers. I can hardly think of anything more improbable than this "gliding wave" theory and the conception of the "guided wireless" which are contrary to all laws of action and reaction. Why should these disturbances cling to a conductor where they are counteracted by induced currents, when they can propagate in all other directions unimpeded? The fact is that the radiations of the transmitter passing along the earth's surface are soon extinguished, the height of the inactive zone indicated in the diagram being some function of the wave length, the bulk of the waves traversing freely the atmosphere. Terrestrial phenomena which I have noted conclusively show that there is no *Heaviside layer,* or if it exists, it is of no effect. It certainly would be unfortunate if the human race were thus imprisoned and forever without power to reach out into the depths of space.

The actions at a distance cannot be proportionate to the height of the antenna and the current in the same. I shall endeavor to make this clear by reference to diagram in Fig. 14. The elevated terminal charged to a high potential induces an equal and opposite charge in the earth and there are thus Q lines giving an average current $I = 4Qn$ which circulates locally and is useless except that it adds to the momentum. A relatively small number of lines q however, go off to great distance and to these corresponds a mean current of $i_e = 4qn$ to *which is due the action at a distance.* The total average current in the antenna is thus $I_m = 4Qn + 4qn$ and its intensity is no criterion for the performance. The electric efficiency of the antenna is $\frac{q}{Q+q}$ and this is often a very small fraction.

Dr. L. W. Austin and Mr. J. L. Hogan have made quantitative measurements which are valuable, but far from supporting the Hertz wave theory they are evidences in disproval of the same, as will be easily perceived by taking the above facts into consideration. Dr. Austin's researches are especially useful and instructive and I regret that I cannot agree with him on this subject. I do not think that if his receiver was affected by Hertz waves he could ever establish such relations as he has found, but he would be likely to reach these results if the Hertz waves were in a large part eliminated. At great distance the space waves and the current waves are of equal energy, the former being merely an accompanying manifestation of the latter in accordance with the fundamental teachings of Maxwell.

It occurs to me here to ask the question—why have the Hertz waves been reduced from the original frequencies to those I have advocated for my system, when in so doing the activity of the transmitting apparatus has been reduced a billion fold? I can invite any expert to perform an experiment such as is illustrated in Fig. 15, which shows the classical Hertz oscillator and my grounded transmitting circuit. It is a fact which I have demonstrated that, altho we may have in the Hertz oscillator an activity thousands of times greater, the effect on the receiver is not to be compared to that of the grounded circuit. This shows that *in the transmission from an airplane we are merely working thru a condenser,* the capacity of which is a function of a logarithmic ratio between the length of the conductor and the distance from the ground. The receiver is affected in exactly the same manner as from an ordinary transmitter, the only difference being that there is a certain modification of the action which can be predetermined from the electrical constants. It is not at all difficult to maintain communication between an airplane and a station on the ground, on the contrary, the feat is very easy.

To mention another experiment in support of my view, I may refer to Fig. 16 in which two grounded circuits are shown excited by oscillations of the Hertzian order. It will be found that the antennas can be put out of parallelism without noticeable change in the action on the receiver, this proving that it is due to currents propagated thru the ground and not to space waves.

Particularly significant are the results obtained in cases illustrated in Figures 17 and 18. In the former an obstacle is shown in the path of the waves but unless the receiver is within the effective *electrostatic* influence of the mountain range, the signals are not appreciably weakened by the presence of the latter, because the currents pass under it and excite the circuit in the same way as if it were attached to an energized wire. If, as in Fig. 18, a second range happens to be beyond the receiver, it could only strengthen the Hertz wave effect by reflection, but as a matter of fact it detracts

(*Continued on page 87*)

Learn Public Speaking

10 LESSONS FREE

Write — quick — for particulars of this extraordinary offer; an opportunity you will never forget if you take advantage of it. Ten lessons in effective public speaking absolutely FREE to those who act promptly, to introduce our course in localities where it is not already known.

We teach you by mail to become a powerful and convincing speaker—to influence and dominate the decisions of one man or an audience of a thousand. We have trained hundreds and helped them to increase their earnings and their popularity. Learn, in your spare time at home, how to overcome "stage fright" and conquer fear of others; how to enlarge your vocabulary; how to develop self-confidence and the qualities of leadership; how to RULE others by the power of your speech alone; how to train your memory. Our

WHAT THE COURSE TEACHES YOU.

How to talk before your club or lodge;
How to address board meetings;
How to propose and respond to toasts;
How to make a political speech;
How to tell entertaining stories;
How to make after-dinner speeches;
How to converse interestingly;
How to write better letters;
How to sell more goods;
How to train your memory;
How to enlarge your vocabulary;
How to develop self-confidence;
How to acquire a winning personality;
How to strengthen your will power and ambition;
How to become a clear, accurate thinker;
How to develop your power of concentration;
How to be the master of any situation.

New Easy Method

perfected and taught only by Prof. R. E. Pattison Kline, former Dean of the Public Speaking Department of the Columbia College of Expression, can be learned in 15 minutes a day. Prof. Kline is one of the foremost authorities in the country on public speaking and mental development. Do not let this chance escape you.

Offer Limited

Send This Free Coupon Now

This Special Offer of TEN LESSONS FREE is made strictly for advertising purposes and will be withdrawn without notice. Write now, before it expires, and receive full particulars with enrollment blank by return mail. No obligations of any kind. Just tear off and mail this free coupon—or a postal will do.

FREE LESSONS COUPON

North American Institute,
7445 Manhattan Bldg., Chicago

I am interested in your course in Effective Public Speaking and your offer of ten lessons free. Please send full particulars. It is understood that this request places me under no obligation of any kind.

.....

.....

The True Wireless

By Nikola Tesla

(Continued from page 63)

greatly from the intensity of the received impulses because the electric niveau between the mountains is raised, as I have explained in connection with my lightning protector in the EXPERIMENTER of February.



Fig. 17. Illustrating Influence of Obstacle in the Path of Transmission as Evidence Against the Hertz-wave Theory.

Again in Fig. 19 two transmitting circuits, one grounded directly and the other thru an air gap, are shown. It is a common observation that the former is far



Fig. 18. Showing Effect of Two Hills as Further Proof Against the Hertz-wave Theory.

more effective, which could not be the case in a transmission with Hertz radiations. In like manner if two grounded circuits are



Fig. 19. Comparing the Actions of Two Forms of Transmitter as Bearing Out the Fallacy of the Hertz-wave Theory.

observed from day to day the effect is found to increase greatly with the dampness of the ground, and for the same reason



Fig. 20. Disproving the Hertz-wave Theory by Two Transmitters, One of Great and the Other of Small Energy.

also the transmission thru sea-water is more efficient.

An illuminating experiment is indicated in Fig. 20 in which two grounded transmitters are shown, one with a large and the other with a small terminal capacity. Suppose that the latter be 1/10 of the former but that it is charged to 10 times the potential and let the frequency of the two circuits and therefore the currents in both antennas be exactly the same. The circuit with the smaller capacity will then have 10 times the energy of the other but the effects on the receiver will be in no wise proportionate.

The same conclusions will be reached by transmitting and receiving circuits with wires buried underground. In each case the actions carefully investigated will be found to be due to *earth currents*. Numerous other proofs might be cited which can be easily verified. So for example *oscillations of low frequency* are ever so much more effective in the transmission which is inconsistent with the prevailing idea. My observations in 1900 and the recent transmissions of signals to very great distances are another emphatic disproval.

The Hertz wave theory of wireless transmission may be kept up for a while, but I do not hesitate to say that in a short time it will be recognized as one of the most remarkable and inexplicable aberrations of the scientific mind which has ever been recorded in history.

TO ALL RADIO AMATEURS

We have received many thousands of communications from radio amateurs for the past few months asking us about the status of their radio stations, and when they will be allowed to operate them again.

Inasmuch as there has been no official information as to the reopening of amateur stations, during the armistice, we can only say that in all likelihood, amateurs will not be allowed to operate until actual peace has been signed. In his executive order of April the 6th, 1917, President Wilson closed all radio stations in the United States by an act approved in the Radio Law of August 13, 1912.

Such a measure, according to law, is only for the duration of the war, there being at present no legislation which prevents any station, amateur or otherwise, from operating after peace has actually been declared. Therefore, the minute newspapers announce that peace between the United States and the Central Powers has been signed, *all amateur stations automatically revert to their former status*, and amateurs need not wait for permission to operate their stations, once peace has been declared.

EDITOR.

WRINKLES, RECIPES & FORMULAS.

(Continued from page 42)

If carbon dioxid is to be generated, fill tube A with marble chips and tube B with dilute hydrochloric acid.

It is evident that the parts of the generator can be easily cleaned and new chemicals put in. The completed apparatus is shown in Fig. 3.

Contributed by S. WEISINGER, JR.

Strengthen Your EYES!

Preserve Your Most Precious Possession

Your sight is your most precious gift. Weak eyesight means **weak power of observation**, eye strain, eye disease, and untold inconvenience. Take no chances with your eyes—you cannot get along without them. Make them stronger every day instead of weaker. Let us send you Bernarr Macfadden's wonderful new Course in "Strengthening the Eyes." Send no money—just mail coupon.

Glasses Do Not Remove the Cause of Eye Trouble

Instead, the eyes come to depend on them more every day. Glasses are eye crutches! They simply holster up the eyes—they do not strengthen them. It has been definitely proven that practically all defects of the eyes can be cured without glasses. Most people now wearing glasses can be freed from the inconvenience, and expense of constant breakages, by strengthening and correcting their vision through the simple, yet effective eye educational exercises recommended by Mr. Macfadden.

Eye Defects Removed

This remarkable new Course teaches you how to use your eyes without strain at all distances—how to do without glasses—how to remedy cross eyes or squint eyes—how to restore the normal sight—how to restore perfect control to eye nerves and muscles.

Beneficial Results at Once

No drugs, medicines or operations. The Course includes a simple, yet thoroughly scientific system of eye educational exercises which strengthen the eyes exactly as the muscles of the body can be strengthened through body exercises. Results are immediate, and improvement continues daily. One woman writes: "I notice a great improvement in my eyes since learning to use them right." Another user says, "Your Eye Strengthening Course is fine. My eyes are already improving." Still another writes, "Words cannot express my great gratitude for these excellent books." (Names on request.)

Send No Money

Let us send you this new Course "Strengthening the Eyes" on five days' approval. There are twenty-eight simple little lessons which will show you the way to strengthen and preserve your sight—the gift of the gods! Try the exercises, then return the Course if not satisfied and you will owe nothing. If, however, you feel that the Course will help your eyes wonderfully, send only $5.00.

Mail Coupon!

If you value your eyes, if you wear glasses and want to get rid of them, if your eyes are weak or strained, or if you want to insure freedom from eye troubles, mail coupon now and investigate this New Course "Strengthening the Eyes." Send no money—but mail coupon now, as this offer may never appear again

Physical Culture Publishing Company
Dept. 5605
119 West 40th Street
N. Y. C.

Physical Culture Pub. Co.
Dept. 5605
119 W. 40th St.
New York City

Gentlemen:
Send me your Course "Strengthening the Eyes" which I will return in 5 days or send you $5 in payment for the course.

Name .....
Address .....

WANTED — Railway Mail Clerks

Age 18 to 35
$1100 to $2000 Year
Common Education Sufficient
Sure pay.
Life job.
Pull unnecessary.

Franklin Institute
Dept. E101
Rochester, N. Y.

COUPON

Sirs: Send me, without charge, (1) sample Railway Mail Clerk Examination questions; (2) schedule showing places of all U. S. Government coming examinations; (3) list of other government jobs now open, and (4) free book describing them.

NAME.....
ADDRESS.....

RADIO DEPARTMENT

Tesla Bulbs



Early in Nikola Tesla's Researches—in Fact as Far Back as 1892—He Discovered a Most Peculiar and Wonderful Vacuum Bulb Phenomena. The Effect was That, Under Certain Critical Conditions, This Bulb Would Cause a Ray to Be Shot off in the Manner Shown, Which Ray Would Revolve or Oscillate Under the Influence of a High-Frequency Current and in Synchrony with It. By Utilizing This Principle, Dr. Tesla Believes It is Possible to Produce a Radio Detector More Sensitive Than the Audion or Fleming Valve.

IN the May issue in his article, "True Wireless," Nikola Tesla mentions the forerunner of the Audion, a Vacuum Bulb, which he used in his earlier experiments.

We have been in receipt of numerous letters from many individuals interested in this bulb who desire further particulars as to its operation, etc.

Accordingly, we publish herewith some excerpts from a lecture by Dr. Tesla delivered before the Institution of Electrical Engineers and Royal Institution, London, February, 1892.

"I think it best at this juncture to bring before you a phenomenon, observed by me some time ago, which to the purely scientific investigator may perhaps appear more interesting than any of the results which I have the privilege to present to you this evening.

"It may be quite properly ranked among the brush phenomena—in fact, it is a brush, formed at, or near, a single terminal in high vacuum.

"In bulbs provided with a conducting terminal, tho it be of aluminum, the brush has but an ephemeral existence, and cannot, unfortunately, be indefinitely preserved in its most sensitive state, even in a bulb devoid of any conducting electrode. In studying the phenomenon, by all means a bulb having no leading-in wire should be used. I have found it best to use bulbs constructed as indicated in Figs. 1 and 2.

"In Fig. 1 the bulb comprises an incandescent lamp globe L, in the neck of which is sealed a barometer tube b, the end of which is blown out to form a small sphere *s*. This sphere should be sealed as closely as possible in the center of the large globe. Before sealing, a thin tube *t*, of aluminum sheet, may be slipt in the barometer tube, but it is not important to employ it.

"The small hollow sphere *s* is filled with some conducting powder, and a wire *w* is cemented in the neck for the purpose of connecting the conducting powder with the generator.

"The construction shown in Fig. 2 was chosen in order to remove from the brush any conducting body which might possibly affect it. The bulb consists in this case of a lamp globe L, which has a neck *n*, provided with a tube *b* and small sphere *s*, sealed to it, so that two entirely independent compartments are formed, as indicated in the drawing. When the bulb is in use the neck *n* is provided with a tinfoil coating, which is connected to the generator and acts inductively upon the moderately rarefied and highly conducting gas inclosed in the neck. From there the current passes thru the tube *b* into the small sphere *s*, to act by induction upon the gas contained in the globe L.

"It is of advantage to make the tube *t* very thick, the hole thru it very small, and to blow the sphere *s* very thin. It is of the greatest importance that the sphere *s* be placed in the center of the globe L.

"Figs. 3, 4, 5, indicate different forms, or stages, of the brush. Fig. 1 shows the brush as it first appears in a bulb provided with a conducting terminal; but, as in such a bulb it very soon disappears—often after a few minutes—I will confine myself to the de-

(*Continued on page* 179)

Experimenters—**KNOBS BASES — INSULATION**

Fine black composition base suitable for detector, fixed condenser, etc. The bottom has a cavity 3" x 1½" x ⅜". Over all dimensions 4¼" x 2" x ½". Two holes for binding posts and two for fastening down to table. Post paid.....30c

Knob 1¼ x ¾

Hole through center for mounting.

Post paid 20c

Knob 11/16 x 21/32

With 8/32 brass threaded bushing.

Post paid 20c

Contact points, switch levers, condenser plating, etc.

Bakelite panels, about

9 x 19 x ¼	Black XX	$4.00
19 x 19 x ¼	Black XX	8.00
9 x 19 x 3/16	Black XX	3.00
19 x 19 x 3/16	Black XX	6.00

A. H. CORWIN & CO.

924 Kinney Building Newark, N. J.

PREPARED!

The lifting of the wireless ban finds the Newman-Stern Co. fully prepared to meet the increased needs of its customers.

Tremendous stocks of apparatus, wires and raw materials, accumulated and reserved for the day when amateur wireless would be resumed, now assure our customers IMMEDIATE Service.

Ninety-nine of every hundred orders will be shipped within twenty-four (24) hours following their receipt.

Present prices are in accordance with price-change schedule effective Feb. 20, 1919, applying to Catalog C-3.

Present prices on any item listed in Catalog B-2 (Handy-Book) will be quoted on request.

The Newman-Stern Co.

CLEVELAND, OHIO

CHEMICALS for THE EXPERIMENTER

DON'T PAY FANCY PRICES for chemicals. Buy highest quality for lowest price. Our unique system of standardization guarantees you at all times the most for your money. Send today for interesting free booklet describing the money-saving, value-giving, N-S plan and listing hundreds of chemicals, chemical glass ware, and apparatus.

Send today for FREE Catalogue

THIS RELIABLE MAIL ORDER HOUSE world famed for its wireless telegraph apparatus and experimenters' supplies, has been urged by hundreds of its patrons to establish a chemistry department. In answer we offer what we believe to be the most complete amateur experimental chemistry in the U. S. Buy where you are always assured of *Standard Quality, Standard Quantity, Standard Packing, Standard Price.*

THE NEWMAN-STERN CO.

Department E E CLEVELAND, O.

STANDARDIZED N-S Co. CHEMICALS

The Newman-Stern System

Not Toys But Real Apparatus

the same as used by all operating companies. You had better send us your order immediately to insure prompt delivery, as this equipment will not last long at these prices.

110 Volt Hand Generators	**3 bars, each**	**$3.00**
	4 bars, each	**4.00**
	5 or 6 bars, each	**5.00**
Telephone transmitters with arms, each		**.75**
Good ringers complete with bells, each		**.50**
Telephone receivers, each		**.75**
Condensers, ½ to 2 M.F., each		**.50**
Induction coils, each		**.50**
Relays, each		**1.50**
Repeating coils, each		**2.00**
Real complete C.B. wall type telephone		**4.50**
Slightly used dry cells, per dozen		**1.25**

Please send money-order or cash with your order

ELECTRICAL SPECIALTY COMPANY

Dept. E, 48-50 So. Front St., Columbus, Ohio

Dept. E, 128 So. 11th St., Philadelphia, Pa.

Tesla Bulbs

(*Continued from page* 134)

scription of the phenomenon, as seen in a bulb without conducting electrode. It is observed under the following conditions:

"When the globe L (Figs. 1 and 2) is exhausted to a very high degree, generally the bulb is not excited upon connecting the wire *w* (Fig. 1), or the tinfoil coating of the bulb (Fig. 2) to the terminal of the induction coil. To excite it, it is usually sufficient to grasp the globe L with the hand. An intense phosphorescence then spreads at first over the globe, but soon gives place to *a white, misty light.* Shortly afterward one may notice that the luminosity is unevenly distributed in the globe, and after passing the current for some time the bulb appears as in Fig. 4. From this stage the phenomenon will gradually pass to that indicated in Fig. 5, after some minutes, hours, days or weeks, according as the bulb is worked. Warming the bulb or increasing the potential hastens the transit.

"When the brush assumes the form indicated in Fig. 5, it may be brought to a state of *extreme sensitiveness to electrostatic and magnetic influence.* The bulb hanging straight down from a wire, and all objects being remote from it, *the approach of the observer at a few paces from the bulb will cause the brush to fly to the opposite side, and if he walks around the bulb it will always keep on the opposite side.* It may begin to spin around the terminal long before it reaches the sensitive stage. *When it begins to turn around, principally, but also before, it is affected by a magnet,* and at a certain stage it is susceptible to magnetic influence to an astonishing degree. A small permanent magnet, with its poles at a distance of no more than two centimeters, will affect it visibly at a distance of two meters, slowing down or accelerating the rotation according to how it is held relatively to the brush. I think I have observed that at the stage when it is most sensitive to magnetic, it is not most sensitive to electrostatic, influence.

"When the bulb hangs with the globe L down, the rotation is always clockwise. In the southern hemisphere it would occur in the opposite direction, and on the equator the brush should not turn at all. The rotation may be reversed by a magnet kept at some distance. The brush rotates best, seemingly, when it is at right angles to the lines of force of the earth. It very likely rotates, when at its maximum speed, in synchronism with the alternations, say, 10,000 times a second. The rotation can be slowed down or accelerated by the approach or receding of the observer, or any conducting body, but it cannot be reversed by putting the bulb in any position. When it is in the state of the highest sensitiveness and the potential or frequency be varied, the sensitiveness is rapidly diminished. Changing either of these but little will generally stop the rotation. The sensitiveness is likewise affected by the variations of temperature. To attain great sensitiveness it is necessary to have the small sphere *s* in the center of the globe *L*, as otherwise the electrostatic action of the glass of the globe will tend to stop the rotation. The sphere *s* should be small and of uniform thickness; any dissymmetry of course has the effect to diminish the sensitiveness.

"The fact that the brush rotates in a definite direction in a permanent magnetic field seems to show that in alternating currents of very high frequency the positive and negative impulses are *not* equal, but that one always preponderates over the other.

"Of course, this rotation in one direction may be due to the action of the two elements of the same current upon each other, or to the action of the field produced by one of the elements upon the other, as in a



HB 16-Battery Charging Set

CHARGING AUTO BATTERIES will Pay $150 to $250 *Clear Profit* Every Month

All you need is HB Equipment. The business is waiting for you—*right now.* More cars are being driven than ever before, with batteries to recharge, and all new Fords are equipped with storage battery. Start **NOW** to get these big steady profits.

This HB 16-Battery Charger Can Be The Biggest Money-Maker In Your Garage

Recharge 1 to 16-volt batteries or equivalent in 12- or 24-volt batteries at once. Current cost 12 to 15c each. Owner pays 75c to $1.50. Figure those profits. Compare them with other branches of your business! HB Chargers last for years—sturdy, economical, dependable. Finest materials and construction. Long service with *quick, clean, permanent profits.*

$57 Puts This Money-Maker in Your Garage on Money-Back Guarantee

Balance in 10 monthly payments of $23 each. Earnings pay for machine. No electrical knowledge necessary to install or operate. Uses 2 or 3 phase city current. Furnished complete with 2 charging panels capable of charging 1 to 8 batteries each. No burn-outs or expensive renewals. Nothing to wear out or break. Sold on HB Absolute Money-Back Guarantee. Order now—you run no risk. Pin your $57 Check to this ad and mail *today* for trial order.

Hobart Brothers Company, Box 6E, Troy, Ohio

Successful Manufacturers Since 1893.

Commercial Telegraph Apparatus Bargains

Standard twenty ohm Telegraph Sounders at	**$2.00 each**
Standard Telegraph Keys at	**1.25 each**
110 Volt A.C. Dynamos	
Three Bar	**1.75 each**
Four Bar	**2.25 each**
Five Bar	**2.75 each**

For other bargains see pages 90 & 91

Skinderviken Telephone Equipment Co

Abbreviated Address

STECO-2118-2136 N. Clark St. CHICAGO

Send To-day for the

"Electrical Worker's Friend"

An electrical book of 66 motor drawings with complete instructions for rewinding and reconnecting A.C. motors. **Special at $3.50**

Or write for full particulars of this valuable book.

SMITH & SMITH PUBLISHING CO.

1524 LOWRIE ST., N.S., PITTSBURGH, PA.

110-V. TRANSFORMERS

8 Volt Secondary

Consumes so little current will not move ordinary meter.

$1.00 *Postpaid*

Only $1.00

No. 10 gives 3 currents — 6, 12 and 18 volts secondary. Ideal for experimental work. A standard transformer, guaranteed. Complete with plug, $2.00 postpaid. Order from this ad.

NATIONAL TRANSFORMER CO.,
Dept. 13, 3124 No. California Ave., Chicago

Arnold Navy Model Loose Couple



Literature describing the above and new apparatus is now ready. Also shows the line of accessories so much desired by the amateur.

My knobs are of real hard rubber; switch points, binding posts, etc., are perfect, polished and plated.

SPECIAL

Round Dials for Condensers, Variometers, etc., made of hard rubber, the handsomest thing you can put on your set. Send 3c stamp for Bulletin.

J. F. ARNOLD

2082 Lexington Ave. Near 125th St., N. Y.
Established 1910

"The Livest Catalog in America"

Our big, new electrical cyclopedia No. 20 is waiting for you. Positively the most complete Wireless and electrical catalog in print today. 180 Big Pages, 500 illustrations, 300 instruments and apparatus, etc. Big "Treatise on Wireless Telegraphy." 20 FREE coupons for our 160-page FREE Wireless Course in 20 lessons. FREE Cyclopedia No. 20 measures 7x5¼". Weight ½ lb. Beautiful stiff covers.

Send 6 cents in stamps or coin for which we will send our latest Cyclopedia Catalog No. 20 as described.

ELECTRO IMPORTING COMPANY
231 Fulton St., New York City

TELEGRAPHY

Both wire and wireless, and Station Agency taught thoroughly and quickly. BIG WAGES NOW PAID, some of our recent graduates procuring $138.00 per month to start. Great opportunities for advancement. Our school the oldest and largest—annual enrollment 600 students. Endorsed by railway, telegraph, wireless and government officials. Expenses low—chance to earn part. Catalog free. Write.

DODGE' INSTITUTE, 22nd St. Valparaiso, Ind.

WIRELESS IS SIMPLE

when the Summers' theories of wireless are applied to wireless systems, transmitting and receiving apparatus. Will advance the wireless art by leaps and bounds. Get on the right track with your experiments. This booklet should be in every home and school. United States and foreign copyrights. Price $2.00 registered postpaid to any part of the world.

Address FRANK E. SUMMERS, Memphis, Mo.

TELEGRAPHY AND RADIO

DAY AND EVENING CLASSES
SEND FOR PROSPECTUS
IN SUBJECT INTERESTED

EASTERN RADIO INSTITUTE
899-B Boylston St. Boston, Mass.

FRENCH WIRELESS

FROG made of steel with large clicker inside, used to learn telegraphy. GREAT FUN. SEND YOUR FRIENDS WIRELESS MESSAGES. SENT complete with code, and to make a big bundle we will send a Ford joke book, Parlor games, etc., all for 10c. **10c**

Dept. 72, American Toy Co., Lowell, Mass., U.S.A.

series motor, without necessarily one impulse being stronger than the other. The fact that the brush turns, as far as I could observe, in any position, would account for this theory. In such case it would turn at any point of the earth's surface. But, on the other hand, it is then hard to explain why a permanent magnet should reverse the rotation, and one must assume the preponderance of impulses of one kind.

"As to the causes of the formation of the brush or stream, I think it is due to the electrostatic action of the globe and the dissymmetry of the parts. If the small bulb *s* and the globe L were perfect concentric spheres, and the glass thruout of the same thickness and quality, I think the brush would not form, as the tendency to pass would be equal on all sides. That the formation of the stream is due to an irregularity is apparent from the fact that it has the tendency to remain in one position, and rotation occurs most generally only when it is brought out of this position by electrostatic or magnetic influence. When in an extremely sensitive state it rests in one position, and most curious experiments may be performed with it. For instance, the experimenter may, by selecting a proper position, approach the hand at a certain considerable distance to the bulb, and he may cause the brush to pass off by merely stiffening the muscles of the arm. When it begins to rotate slowly, and the hands are held at a proper distance, it is impossible to make even the slightest motion without producing a visible effect upon the brush. A metal plate connected to the other terminal of the coil affects it at a great distance, slowing down the rotation often to one turn a second.

"I am firmly convinced that such a brush, when we learn how to produce it properly, will prove a valuable aid in the investigation of the nature of the forces acting in an electrostatic or magnetic field. If there is any motion which is measurable going on in the space, such a brush ought to reveal it. It is, so to speak, a beam of light—frictionless, devoid of inertia.

"I think that it may find practical applications in telegraphy. With such a brush it would be possible to send dispatches across the Atlantic, for instance, with any speed, since its sensitiveness may be so great that the slightest changes will affect it. If it were possible to make the stream more intense and very narrow, its deflections could be easily photographed.

"I have been interested to find whether there is a rotation of the stream itself, or whether there is simply a stress traveling around the bulb. For this purpose I mounted a light mica fan so that its vanes were in the path of the brush. If the stream itself was rotating the fan would be spun around. I could produce no distinct rotation of the fan, altho I tried the experiment repeatedly; but as the fan exerted a noticeable influence on the stream, and the apparent rotation of the latter was, in this case, never quite satisfactory, the experiment did not appear to be conclusive.

"I have been unable to produce the phenomenon with the disruptive discharge coil, altho every other form of these phenomena can be well produced by it—many, in fact, much better than with coils operated from an alternator.

"It may be possible to produce the brush by impulses of one direction, or even by a steady potential, in which case it would be still more sensitive to magnetic influence."

Fig. 6 shows a practical application of the Tesla bulb. The bulb itself, as will be seen, is excited by means of a Tesla high frequency alternator which, in turn, is connected to the primary of a transformer. The secondary of the transformer is grounded at one end, while the other end of the transformer connects with the Tesla bulb.

Dr. Tesla, in an interview, stated that

(*Continued on page* 184)

USE HB BALL BEARING ELECTRIC MOTORS

HB Electrical Motors Save Power—Get Ball Bearing equipped HB Motors, as they save you a substantial sum each month on your power bills. Absolutely they are trouble-proof, economical, amply designed, just right for your requirements—one to 15 h.p. They substantially lower your power costs. Easy to install and operate. Require practically no attention.



$20.00 gives you an HB Ball Bearing Motor. The balance on easy terms. Suits your requirements. Let our engineering department advise you. Send in your problems. State kind of machinery you wish to run and type of current available. We can also furnish Battery Charging Outfits, Lighting Generators, etc. Pin this ad to your letterhead and mail for further information today.

HOBART BROTHERS COMPANY
Box 6E Troy, Ohio
Successful Manufacturers Since 1893

SMALL ENGINES

Perfected Gasoline Engines—½, 1 and 1½ h. p.—for Farm and Shop use. Price, $27.50 and up. Also,

WASHING MACHINES

We ship on trial. Send for Booklet and Special Offer.

SIEVERKROPP ENGINE CO.
1401—19th St., Racine, Wis.

STARTER for FORD CARS

Yankee Wireless 50¢

The only dependable wireless set at a low price. It is not a toy and with little practice you can send and receive clear messages anywhere as quick as a flash.

THE YANKEE

is for two complete stations—with Morse code and instructions for operating. We will also include our picture code attachment, which will enable the operator to send and receive pictures and photographs by wireless. The complete Yankee Wireless set can be obtained only from us. All charges paid for 50c money order.

A. & R. MFG. CO., 1303 Peoria St., Chicago, Ill.

DOLLAR ADDING MACHINE $1

Adds and multiplies with speed of expensive machines. Seven columns capacity. Remarkably simple in construction. Nothing to get out of order. Weight one



ounce. Made of metal and celluloid. The ideal pocket, desk or home machine. Order today. The best way not to forget is to do it now.

L. J. LEISHMAN CO., Dept. 142, Ogden, Utah

MARKO STORAGE BATTERIES

ARE GOOD—TRY ONE

Paul M. Marko & Co., Inc.
1402-1412 Atlantic Ave.
Brooklyn, N. Y.

SELENIUM CELLS

Guaranteed 99% pure selenium

Made by people who know their business, for the most difficult work, requiring very sensitive, quick acting cells.

Special cells to order.

THE SELENIUM LABORATORIES,
New York Offices, 56 West 45th St.

WIRELESS BOOKS

Send for Catalogue

BUY NOW and Save a Dollar

PRACTICAL WIRELESS TELEGRAPHY By E. E. Bucher and THE WIRELESS AGE for one year, $2.75. *Regular price, $3.75.*

WIRELESS PRESS, INC., 33 ELM ST., NEW YORK.

"BOW LEGS and KNOCK-KNEES" UNSIGHTLY

Send for booklet showing photos of men with and without THE PERFECT LEG FORMS.

PERFECT SALES CO.
140 N. Mayfield Ave., Dept. 50 Chicago, Ill.

INSYDE TYRES Inner Armor

for Auto Tires. Double mileage, prevent blow-outs and punctures. Easily applied in any tire. Thousands sold. Details free. Agents wanted.
Amer. Accessories Co., Dept. 53, Cincinnati

ADVERTISING PAYS

It pays the man who advertises and it pays the man who answers ads. For advertising rates in the E. E., address

Advertising Dept., 233 Fulton St., N. Y.

"The National Authority on Electric Wiring for Twenty-Five Years"

All You Need to Know About Wiring

is in the Latest Edition of

"Standard Wiring"



THIS year's edition, completely revised to date, is the only accurate book on electric light and power wiring and construction published.

The National Electrical Code, with all its new rules, is explained and illustrated. 52 of the latest and simplest tables which show, at a glance, just what size of wire is needed for any kind and size of lighting or motor installation, for any voltage, current and drop desired for any system. Direct Current, Alternating Current, single, two or three-phase. The latest Code Rules on grounding required on all work.

How to install and operate generators, motors and every kind of wiring device with diagrams of connections. Special chapters on illumination, House Wiring, Electrical Units and their Equivalents. The latest lamp data. Proper symbols to use to indicate outlets, etc., etc.

It Will Make You an Expert Wireman

Leather Cover - Pocket Size - 375 Pages - Price $1.50

Sent to any address, postpaid, on receipt of price

H. C. Cushing, Jr., 10 West 40th St., New York

YOUR OPPORTUNITY

Canceled Government Contracts

We have secured a large quantity of Small Motors, Generators and Charging Outfits. This material is new, still in original cases and carries the full factory guarantee.

This is Your Opportunity to buy new, guaranteed Electrical Apparatus of Standard Manufacture



1/2 H. P. INDUCTION MOTOR 110 or 220 volts, A. C. 60 cycle, single phase, 1750 R. P. M. **$32.50**

ALL MOTORS COMPLETE AS CUT

Battery Charging Outfits

For use on 110 volt, A. C., 00 cycle, single phase current only.

60 watts, 8 volts, 10 amperes . **$48.50**
130 watts, 80 volts, 5 amperes . **$68.50**
150 watts, 15 volts, 10 amperes . **$68.50**
300 watts, 80 volts, 10 amperes . **$94.50**

All outfits complete with switchboard as cut shown.

Mail $5.00 cash or Money Order. We will send C. O. D. subject to full examination.

MONEY BACK GUARANTEE

1/4 H. P. 110 volts A. C., 60 cycle, single phase 1750 R. P. M.

WASHING MACHINE MOTOR

Suitable for operating Small Compressors, Coffee Grinders, Bottle Washers, Lathes Drill Presses, etc. **$18.50**

WRITE FOR CATALOGUE. BARGAINS IN MOTORS AND GENERATORS. SPECIAL QUANTITY PRICES

220 volts **POLYPHASE MOTORS** 1750 RPM. 60 cycle, 2 or 3 phase. Complete, pulley and base
1 H. P. $59.50 3 H. P. $ 84.50
2 H. P. $72.50 5 H. P. $102.50

NEW MOTORS

110-220 volts **REPULSION MOTORS** 1800 RPM. 60 cycle, single phase. Complete with pulley.
1/2 Hp. $44.50 1 Hp. $67.50

MANUFACTURERS' DISTRIBUTER

CHAS. H. JOHNSTON - West End - PITTSBURGH, PA.

What 15c will bring You from the Nation's Capital

Washington, the home of the Pathfinder, is the nerve center of civilization; history is being made at this world capital. The Pathfinder's illustrated weekly review gives you a clear, impartial and correct diagnosis of public affairs during these strenuous, epoch-making days.

The little matter of **15c** in stamps or coin will bring you the Pathfinder **13** weeks on trial. The Pathfinder is an illustrated weekly, published at the Nation's center, for the Nation; a paper that prints all the news of the world and tells the truth and only the truth; now in its **26th** year. This paper fills the bill without emptying the purse; it costs but $1 a year. If you want to keep posted on what is going on in the world, at the least expense of time or money, this is your means. If you want a paper in your home which is sincere, reliable, entertaining, wholesome, the Pathfinder is yours. If you would appreciate a paper which puts everything clearly, fairly, briefly—here it is. Send **15c** to show that you might like such a paper, and we will send the Pathfinder on probation **13** weeks. The 15c does not repay us, but we are glad to invest in new friends. **The Pathfinder, Box 576, Washington, D. C.**

Tesla Bulbs

(*Continued from page* 180)

the best way to use the bulb for such experiments is when the shaft of light is in the position as shown in Figs. 5 and 6, at rest, but in a state of equilibrium inconceivably delicate. This is fully described above in Dr. Tesla's lecture. The inventor states that in such a condition, the shaft of light is marvelously sensitive to magnetic disturbances. Dr. Tesla informs us that a toy permanent horseshoe magnet not longer than ½" and with its poles ⅛" apart could with ease throw the shaft of light out of its normal direction across the whole room. In our illustration, an electromagnet is shown a few inches away from light ray, and we can imagine a slot in a screen in such a way that normally no light falls thru it. If, however, very faint radio-telegraphic impulses surge thru the electromagnet, the light ray will immediately become displaced, and will fall into the slot. Inasmuch as this shaft of light has no inertia, it will follow exactly the dot and dash impulses surging thru the electromagnet, no matter how rapidly they take place. They can then either be read off by the eye, or if desired, can be registered upon a fast moving film. This method will, of course, only be used where the transmission is made at high speed, and where it would be impossible for an operator at the receiving end to follow the dots and dashes with the eye.

The method shown by us in Fig. 6, of course, represents only one. Many others can undoubtedly be evolved to use the Tesla bulb to advantage.

STATEMENT OF THE OWNERSHIP, MANAGEMENT, CIRCULATION, ETC., REQUIRED BY THE ACT OF CONGRESS OF AUGUST 24, 1912, of Electrical Experimenter, published monthly at New York, N. Y., for April 1, 1919.

State of New York, County of New York—ss.

Before me, a Notary Public in and for the State and county aforesaid, personally appeared Hugo Gernsback, who, having been duly sworn according to law, deposes and says that he is the Editor of the Electrical Experimenter, and that the following is, to the best of his knowledge and belief, a true statement of the ownership, management, etc., of the aforesaid publication for the date shown in the above caption, required by the Act of August 24, 1912, embodied in section 443, Postal Laws and Regulations:

1. That the names and addresses of the publisher, editor, managing editor, and business manager are: Publisher, The Experimenter Publishing Co., 233 Fulton Street, New York City; Editor, Hugo Gernsback, 233 Fulton Street, New York City; Managing Editor, Harry Winfield Secor, 233 Fulton Street, New York City; Business Manager, Hugo Gernsback, 233 Fulton Street, New York City.

2. That the owners are: Experimenter Publishing Co., 233 Fulton Street, New York City; Hugo Gernsback, 233 Fulton Street, New York City; Sidney Gernsback, 233 Fulton Street, New York City; Mrs. K. Hymes, 233 Fulton Street, New York City; Harry Winfield Secor, 233 Fulton Street, New York City.

3. That the known bondholders, mortgagees, and other security holders owning or holding 1 per cent or more of total amount of bonds, mortgages, or other securities are: None.

4. That the two paragraphs next above, giving the names of the owners, stockholders, and security holders, if any, contain not only the list of stockholders and security holders as they appear upon the books of the company but, also, in cases where the stockholder or security holder appears upon the books of the company as trustee or in any other fiduciary relation, the name of the person or corporation for whom such trustee is acting, is given; also that the said two paragraphs contain statements embracing affiant's full knowledge and belief as to the circumstances and conditions under which stockholders and security holders who do not appear upon the books of the company as trustees, hold stock and securities in a capacity other than that of a bona fide owner; and this affiant has no reason to believe that any other person, association, or corporation has any interest direct or indirect in the said stock, bonds, or other securities than as so stated by him.

5. That the average number of copies of each issue of this publication sold or distributed, through the mails or otherwise, to paid subscribers during the six months preceding the date shown above is —(Required only of daily publications.)

(SEAL) H. GERNSBACK.

Sworn to and subscribed before me this 4th day of April, 1919.

BEATRICE K. OWEN.

(My commission expires March 30, 1921.)

The Moon's Rotation

By NIKOLA TESLA

SINCE the appearance of my article entitled the "Famous Scientific Illusions" in your February issue, I have received a number of letters criticizing the views I exprest regarding the moon's "axial rotation." These have been partly answered by my statement to the *New York Tribune* of February 23, which allow me to quote:

In your issue of February 2, Mr. Charles E. Manierre, commenting upon my article in the *Electrical Experimenter* for February which appeared in the *Tribune* of January 26, suggests that I give a definition of axial rotation.

I intended to be explicit on this point as may be judged from the following quotation: "The unfailing test of the spinning of a mass is, however, the existence of *energy of motion.* The moon is not posest of such *vis viva.*" By this I meant that "axial rotation" is not simply "rotation upon an axis nonchalantly defined in dictionaries, but is a circular motion in the true physical sense—that is, one in which half the product of the mass with the square of velocity is a definite and positive quantity. The moon is a nearly spherical body, of a radius of about 1,087.5 miles, from which I calculate its volume to be approximately 5,300,216,300 cubic miles. Since its mean density is 3.27, one cubic foot of material composing it weighs close on 205 lbs. Accordingly, the total weight of the satellite is about 79,969,000,000,000,000,000, and its mass 2,483,500,000,000,000,000 terrestrial short tons. Assuming that the moon does physically rotate upon its axis, it performs one revolution in 27 days, 7 hours, 43 minutes and 11 seconds, or 2,360,591 seconds. If, in conformity with mathematical principles, we imagine the entire mass concentrated at a distance from the center equal to two-fifths of the radius, then the calculated rotational velocity is 3.04 feet per second, at which the globe would contain 11,474,000,000,000,000,000 short foot tons of energy sufficient to run 1,000,000,000 horsepower for a period of 1,323 years. Now, I say, that there is not enough of that energy in the moon to run a delicate watch.

In astronomical treatisies usually the argument is advanced that "if the lunar globe did not turn upon its axis it would expose all parts to terrestrial view. As only a little over one-half is visible it *must* rotate." But this inference is erroneous, for it only admits of one alternative. There are an infinite number of axis besides its own in each of which the moon might turn and still exhibit the same peculiarity.

I have stated in my article that the moon rotates about an axis passing thru the center of the earth, which is not strictly true, but it does not vitiate the conclusions I have drawn. It is well known, of course, that the two bodies revolve around a common center of gravity, which is at a distance of a little over 2,899 miles from the earth's center.



If You Still Think That the Moon Rotates on Its Axis, Look at This Diagram and Follow Closely the Successive Positions Taken by One of the Balls M While It Is Rotated by a Spoke of the Wheel. Substitute Gravity for the Spoke and the Analogy Solves the Moon Rotation Riddle.

Another mistake in books on astronomy is made in considering this motion equivalent to that of a weight whirled on a string or in a sling. In the first place there is an essential difference between these two devices tho involving the same mechanical principle. If a metal ball, attached to a string, is whirled around and the latter breaks, an axial rotation of the missile results which is definitely related in magnitude and direction to the motion preceding. By way of illustration—if the ball is whirled on the string clockwise ten times per second, then when it flies off, it will rotate on its axis ten times per second, likewise in the direction of a clock. Quite different are the conditions when the ball is thrown from a sling. In this case a *much more rapid* rotation is imparted to it in the *opposite sense.* There is no true analogy to these in the motion of the moon. *If the gravitational string, as it were, would snap, the satellite would go off in a tangent without the slightest swerving or rotation, for there is no moment about the axis and, consequently, no tendency whatever to spinning motion.*

Mr. Manierre is mistaken in his surmise as to what would happen if the earth were suddenly eliminated. Let us suppose that this would occur at the instant when the moon is in *opposition.* Then it would continue on its eliptical path around the sun, presenting to it steadily the face which was always exposed to the earth. If, on the other hand, the latter would disappear at the moment of *conjunction,* the moon would gradually swing around thru 180° and, after a number of oscillations, revolve, again with the same face to the sun. In either case there would be no periodic changes but eternal day and night, respectively, on the sides turned towards, and away from, the luminary.

Some of the arguments advanced by the correspondents are ingenious and not a few comical. None, however, are valid.

One of the writers imagines the earth in the center of a circular orbital plate, having fixedly attached to its periperal portion a disk-shaped moon, in frictional or geared engagement with another disk of the same diameter and freely rotatable on a pivot projecting from an arm entirely independent of the planetary system. The arm being held continuously parallel to itself, the pivoted disk, of course, is made to turn on its axis as the orbital plate is rotated. This is a well-known drive, and the rotation of the pivoted disk is as palpable a fact as that of the orbital plate. But, the moon in this model only revolves about the center of the system *without the slightest angular displacement* on its own axis. The same is true of a cart-wheel to which this writer refers. So long as it advances on the earth's surface it turns on the axle in the true physical sense; when one of its spokes is always kept in a perpendicular position the wheel still *revolves* about the earth's center, *but axial rotation has ceased.* Those who think that it then still exists are laboring under an illusion.

An obvious fallacy is involved in the following abstract reasoning. The orbital plate is assumed to gradually shrink, so that finally the centers of the earth and the satellite coincide when the latter revolves simultaneously about its own and the earth's axis. We may reduce the earth to a mathematical point and the distance between the two planets to the radius of the moon without affecting the system in principle, but a further diminution of the distance is mani- (*Cont. on p.* 892)

WE believe the accompanying illustration and its explanation will dispel all doubts as to whether the moon rotates on its axis or not. Each of the balls, as M, depicts a different position of, and rotates exactly like, the moon keeping always the same face turned towards the center O, representing the earth.

But as you study this diagram, can you conceive that any of the balls turn on their axis? Plainly this is rendered physically impossible by the spokes. But if you are still unconvinced, Mr. Tesla's experimental proof will surely satisfy you. A body rotating on its axis must contain rotational energy. Now it is a fact, as Mr. Tesla shows, that no such energy is imparted to the ball as, for instance, to a projectile discharged from a gun. It is therefore evident that the moon, in which the gravitational attraction is substituted for a spoke, cannot rotate on its axis or, in other words, contain rotational energy. If the earth's attraction would suddenly cease and cause it to fly off in a tangent, the moon would have no other energy except that of translatory movement, and it would not spin like the ball.—Editor.

Tobacco Habit BANISHED in 48 to 72 Hours

No craving for tobacco in any form when you begin taking Tobacco Redeemer.

Don't try to quit the tobacco habit unaided. It's a losing fight against heavy odds and means a serious shock to the nervous system. **Let the tobacco habit quit YOU.** It will quit you, if you will just take **Tobacco Redeemer,** according to directions for two or three days. It is a most marvelously quick and thoroughly reliable remedy for the tobacco habit.

Not a Substitute

Tobacco Redeemer contains no habit-forming drugs of any kind. It is in no sense a substitute for tobacco. After finishing the treatment you have absolutely no desire to use tobacco again or to continue the use of the remedy. It makes not a particle of difference how long you have been using tobacco, how much you use or in what form you use it—whether you smoke cigars, cigarettes, pipe, chew plug or fine cut or use snuff, **Tobacco Redeemer** will positively banish every trace of desire in from 48 to 72 hours. This we absolutely guarantee in every case or money refunded.

Write today for our free booklet showing the deadly effect of tobacco upon the human system and **positive proof** that **Tobacco Redeemer** will quickly free you of the habit.

Newell Pharmacal Company,
Dept. 521 St. Louis, Mo.

BOYS! *Write For New AUTO-WHEEL BOOKLET, and*

FREE FELT PENNANT

Send us the names of three coaster wagon dealers, mentioning which handle the AUTO-WHEEL, and we'll send you a beautiful Felt Pennant FREE and tell you all about the wonderful Auto-Wheel Coaster and the patented Auto-Wheel Convertible Roadster.

Wouldn't YOU Like to Organize a Coaster Club?

It's great fun. Every member receives a cap and the Captain a special cap. When you write, be sure to ask for full information and the new Auto-Wheel Booklet. It's brimful of information you should have.

The Buffalo Sled Co.
Dept. 163 N. Tonawanda, N. Y.

In Canada: Preston, Ont.

Auto-Wheel

BOYS BUILD THIS CAR

This nifty little car driven by gasoline motor, can be built by any boy. Parts are furnished by us and are very cheap. Send 26 cents for building plans and price list of parts showing how to build this lads' car.

SYPHER MFG. CO.
156 Warren Street
TOLEDO, OHIO.

BUSH CAR—FREE

This Five Passenger 37 H. P. car, 116 in. whl. base. All bearings Timken. Delco Ign.—Dyneto Stg. and Ltg. Write at once for my great Free Offer and 48-page catalog. Agents wanted to drive and demonstrate. Territory open. Prompt shipments. Big money. Cars guaranteed or money back. 1919 cars ready.

BUSH Address J. H. Bush, President. Dept. D15 MOTOR CO., Bush Temple, Chicago, Illinois

The Moon's Rotation

(*Continued from page* 866)

festly absurd and of no bearing on the question under consideration.

In all the communications I have received, tho different in the manner of presentation, the successive changes of position in space are mistaken for axial rotation. So, for instance, a positive refutation of my arguments is found in the observation that the moon exposes all sides to other planets! It revolves, to be sure, but none of the evidences is a proof that it turns on its axis. Even the well-known experiment with the Foucault pendulum, altho exhibiting similar phenomena as on our globe, would merely demonstrate a motion of the satellite about *some* axis. The view I have advanced is NOT BASED ON A THEORY but on facts *demonstrable by experiment.* It is not a matter of *definition* as some would have it. A MASS REVOLVING ON ITS AXIS MUST BE POSEST OF MOMENTUM. If it has none, there is no axial rotation, all appearances to the contrary notwithstanding.

A few simple reflections based on well establisht mechanical principles will make this clear. Consider first the case of two equal weights w and w_1, in Fig. 1, whirled about the center O on a string s as shown. Assuming the latter to break at a both weights will fly off on tangents to their circles of gyration, and, being animated with different velocities, they will rotate around their common center of gravity o. If the weights are whirled n times per second then the speed of the outer and the inner one will be, respectively, $V = 2(R + r)\,n$ and $V_1 = 2\pi(R - r)\,n$, and the difference $V - V_1 = 4\pi r n$, will be the length of the circular path of the outer weight. Inasmuch, however, as there will be equalization of the speeds until the mean value is attained, we shall have $\frac{V - V_1}{2} = 2\pi r n = 2\pi r N$, N being the number of revolutions per second of the weights around their center of gravity. Evidently then, the weights continue to rotate at the original rate and in the same direction. I know this to be a fact from actual experiments. It also follows that a ball, as that shown in the figure, will behave in a similar manner for the two half-spherical masses can be concentrated at their centers of gravity and m and m_1, respectively, which will be at a distance from o equal to $\frac{3}{8}\,r$.

This being understood, imagine a number of balls M carried by as many spokes S radiating from a hub H, as illustrated in Fig. 2, and let this system be rotated n times per second around center O on frictionless bearings. A certain amount of work will be required to bring the structure to this speed, and it will be found that it equals exactly half the product of the masses with the square of the tangential velocity. Now if it be true that the moon rotates in reality on its axis *this must also hold good for EACH of the balls as it performs the same kind of movement.* Therefore, in imparting to the system a given velocity, energy must have been used up in the axial rotation of the balls. Let M be the mass of one of these and R the radius of gyration, then the rotational energy will be $E = \frac{1}{2}M\,(2\pi Rn)^2$. Since for one complete turn of the wheel every ball makes one revolution on its axis, according to the prevailing theory, the energy of axial rotation of each ball will be $e = \frac{1}{2}M\,(2\pi r_1 n)^2$, r_1 being the radius of gyration about the axis and equal to 0.6325 r. We can use as large balls as we like, and so make e a considerable percentage of E and yet, it is positively established by experiment that each of the rotating balls contain only the energy E, no power whatever being consumed in the supposed axial rotation, which is, consequently, wholly illusionary. Something even more interesting may, however, be stated. As I have shown before, a ball flying off will rotate at the rate of the wheel and in the same direction. But this whirling motion, unlike that of a projectile, neither adds to, nor detracts from, the energy of the translatory movement which is exactly equal to the work consumed in giving to the mass the observed velocity.

From the foregoing it will be seen that in order to make one physical revolution on its axis the moon should have twice its present angular velocity, and then it would contain a quantity of stored energy as given in my above letter to the *New York Tribune,* on the assumption that the radius of gyration is 2/5 that of figure. This, of course, is uncertain, as the distribution of density in the interior is unknown. But from the character of motion of the satellite it may be concluded with certitude *that it is devoid of momentum about its axis.* If it be bisected by a plane tangential to the orbit, the masses of the two halves are inversely as the distances of their centers of gravity from the earth's center and, therefore, if the latter were to disappear suddenly, no axial rotation, as in the case of a weight thrown off, would ensue.



Diagram Illustrating the Rotation of Weights Thrown Off By Centrifugal Force.

WHAT IS MAN?

A man weighing 150 pounds will contain approximately 3,500 cubic feet of gas,—oxygen, hydrogen and nitrogen in his constitution, which at eighty cents per thousand cubic feet would be worth $2.80 for illuminating purposes. He also contains all the necessary fats to make a 15-pound candle, and thus, together with his 3,500 cubic feet of gases, he possesses considerable *illuminating* possibilities. His system contains 22 pounds and ten ounces of carbon, or enough to make 780 dozen, or 9,360 lead pencils. There are about fifty grains of iron in his blood and the rest of the body would supply enough of this metal to make one spike large enough to hold his weight. A healthy man contains 54 ounces of phosphorus. This deadly poison would make 800,000 matches, or enough poison to kill five hundred persons. This, with two ounces of lime, make the stiff bones and brains. No difference how *sour* a man looks, he contains about 60 lumps of sugar of the ordinary cubical dimensions, and to make the seasoning complete, there are 20 *spoonfuls of salt.* If a man were distilled into water, he would make about 38 quarts, or more than half his entire weight. He also contains a great deal of starch, chlorid of potash, magnesium, sulfur, and hydrochloric acid in his wonderful human system.

Break the shells of 1,000 eggs into a huge pan or basin, and you have the contents to make a man from his toe-nails to the most delicate tissues of his brain. And this is the scientific answer to the question, "What is Man?"

The Moon's Rotation

By NIKOLA TESLA

In this article Dr. Tesla proves conclusively by theory and experiment that all the kinetic energy of a rotating mass is purely translational and that the moon contains absolutely no rotational energy, in other words, does not rotate on its axis.—EDITOR.

IN revising my article on "The Moon's Rotation", which appeared in the April issue of the ELECTRICAL EXPERIMENTER, I appended a few remarks to the original text in further support and eluci-



Fig. 1. In Determining the Kinetic Energy of a Rotating Mass, This Figure Shows the Selection of a Number of Points Taken Within the Straight Rod or Mass M, at Successive Distances from the Axis of Rotation O, Knowing These Values and the Speed of Rotation the Kinetic Energy of the Mass Is Readily Computed.

dation of the theory advanced. Due to the printer's error these were lost and, in consequence, I found it necessary to forward another communication which, unfortunately, was received too late for embodiment in the May number. Meanwhile many letters have reached me in which certain phenomena presented by rotating bodies, as the moon's librations of longitude, are cited as evidences of energy due to spinning motion, i. e., proofs of axial rotation of the satellite in the true physical sense. I trust that the following amplified statement will meet all of the objections raised and convert to my views those who are still unconvinced.

The kinetic energy of a rotating mass can be determined in four ways which are illustrated in diagrams, Figs. 1, 2, 3 and 4 and may be found more or less suitable.

Referring to Fig. 1, the method consists in selecting judiciously a number of points as o_1, o_2, o_3, etc., within the straight rod or mass M, respectively at distances r_1, r_2, r_3, etc., from the axis of rotation 0 and calculating the square root of the mean square of these distances. Its value being R_g, denoted radius of gyration, the *effective* velocity of the mass at n revolutions per second will be $V_e = 2\pi R_g n$ and its kinetic energy $E = \frac{1}{2} M V_e^2 = \frac{1}{2} M (2\pi R_g n)^2$.

In Fig. 2 the mass M, rotating n times per second about an axis 0 at right angles to the plane of the paper, is divided into numerous elements or small parts, most conveniently very thin concentric laminae, as l_1, l_2, l_3, etc., at distances r_1, r_2, r_3, etc., from 0. Since the kinetic energy of each part is equal to half the product of its mass and the square of the velocity, the sum of all these elemental energies $E = \frac{1}{2} \Sigma m V^2 = \frac{1}{2} m_1 V_1^2 + \frac{1}{2} m_2 V_2^2 + \frac{1}{2} m_3 V_3^2 + \ldots\ldots = \frac{1}{2} m_1 (2\pi r_1 n)^2 + \frac{1}{2} m_2 (2\pi r_2 n)^2 + \frac{1}{2} m_3 (2\pi r_3 n)^2 + \ldots\ldots$.

A different form of expression for the energy of a rotating body may be obtained by determining its moment of inertia. For this purpose the mass M (in Fig. 3), rotating n times per second about an axis 0, is separated into minute parts, as m_1, m_2, m_3, etc., respectively at distances r_1, r_2, r_3, etc., from the same. The sum of the products of all these small masses and the squares of their distances is the moment of inertia I, and then $E = \frac{1}{2} I \omega^2$, $\omega = 2\pi n$ being the angular velocity.

It is obvious that in all these instances many points or elements will be required for great accuracy but, as a rule, very few are sufficient in practice.

Still another way to compute the kinetic energy is illustrated in Fig. 4, in which case the quantity I is given in terms of the moment of inertia I_c about another axis parallel to 0 and passing thru the center of gravity C of mass M. In conformity with this the energy of motion $E = \frac{1}{2} M V^2 + \frac{1}{2} I_c \omega^2$ in which equation V is the velocity of the center of gravity.

The preceding is deemed indispensable as I note that the correspondents, even those who seem thoroly familiar with mechanical principles, fail to make a distinction between theoretical and physical truths which is essential to my argument.

In estimating the kinetic energy of a rotating mass in any of the ways indicated we arrive, thru suitable conceptions and methods of approximation, at expressions which may be made quantitatively precise to any desired degree, but do not truly de-



Fig. 3. Another Form of Expression for the Energy of a Rotating Body May Be Obtained by Determining Its Moment of Inertia. Here the Mass M is Subdivided Into Minute Parts m_1, m_2, m_3, ... etc. The Sum of the Products of These Masses and the Squares of Their Distances Is the Moment of Inertia, Which with the Angular Speed, Gives the Kinetic Energy E.

fine the actual condition of the body. To illustrate, when proceeding according to the plan of Fig. 1, we find a certain hypothetical velocity with which the entire mass should



Fig. 4. In this Case the Motion is Resolved Into Two Separate Components—One Translational About O and the Other Rotational About C. The Total Kinetic Energy of the Mass Equals the Sum of These Two Energies.

move in order to contain the same energy, a state wholly imaginary and irreconcilable with the actual. Only, when *all* particles of the body have the same velocity, does the



Fig. 2. In This Case the Mass M, Rotating n Times Per Second, About An Axis O, Is Divided Into Numerous Elements or Small Parts at Various Radii from O. Knowing the Kinetic Energy of Each Part, the Whole Kinetic Energy of the Mass Is Easily Determined by Taking a Summation of the Individual Quantities.

product $\frac{1}{2} M V^2$ specify a physical fact and is numerically and descriptively accurate. Still more remote from palpable truth is the equation of motion obtained in the manner indicated in Fig. 4, in which the first term represents the kinetic energy of translation of the body as a whole and the second that of its axial rotation. The former would demand a movement of the mass in a definite path and direction, all particles having the same velocity, the latter its simultaneous motion in another path and direction, the particles having different velocities. This abstract idea of angular motion is chiefly responsible for the illusion of the moon's axial rotation, which I shall endeavor to dispel by additional evidences.

With this object attention is called to Fig. 5 showing a system composed of eight balls M, which are carried on spokes S, radiating from a hub H, rotatable around a central axis 0 in bearings supposed to be frictionless. It is an arrangement similar to that before illustrated with the exception that the balls, instead of forming parts of the spokes, are supported in screw pivots *s*, which are normally loose but can be tightened so as to permit both free turning and rigid fixing as may be desired. To facilitate observation the spokes are provided with radial marks and the lower sides of the balls are shaded. Assume, first, that the drawing depicts the state of rest, the balls being rotatable without friction, and let an angular velocity $\omega = 2\pi n$ be imparted to the system in the clockwise direction as indicated by the long solid arrow. Viewing a ball as M, its successive positions 1, 2, 3—8 in space, and also relatively to the spoke, will be just as drawn, and it is evident from an inspection of the diagram that while moving with the angular velocity ω about 0, in the clockwise direction, the ball turns, with respect to its axis, at the same angular velocity but in the opposition direction, that of the dotted arrow. The combined result of these two motions is a translatory movement of the ball such that all particles are animated with the same velocity V, which is that of its center of gravity. In this case, granted that there is absolutely no friction the

kinetic energy of each ball will be given by the product of ½ M V² not approximately, but with mathematical rigor. If now the pivots are screwed tight and the balls fixt rigidly to the spokes, this angular motion relatively to their axes becomes physically impossible and then it is found that the kinetic energy of each ball is increased, the increment being exactly the energy of rotation of the ball on its axis. This fact, which is borne out both by theory and experiment, is the foundation of the general notion that a gyrating body—in this instance ball M—presenting always the same face towards the center of motion, *actually* rotates upon its axis in the same sense, as indicated by the short full arrow. *But it does not tho to the eye it seems so.* The fallacy will become manifest on further inquiry.

To begin with, observe that when a mass, say the armature of an electric motor, rotating with the angular velocity ω, is reversed, its speed is $-\omega$ and the difference $\omega - (-\omega) = 2\omega$. Now, in fixing the ball to the spoke, the change of angular velocity is only ω; therefore, an additional velocity ω would have to be imparted to it in order to cause a clockwise rotation of the ball on its axis in the true significance of the word. The kinetic energy would then be equal to the sum of the energies of the translatory and axial motions, not merely in the abstract mathematical meaning, but as a physical fact. I am well aware that, according to the prevailing opinion, when the ball is free on the pivots it does not turn on its axis at all and only rotates with the angular velocity of the frame when rigidly attached to the same, but the truth will appear upon a closer examination of this kind of movement.



Fig. 5. This Diagram Represents a System Composed of 8 Balls M, Carried on Spokes S, and Rotating Around Center O. The Balls Are Freely Rotatable on Pivots Which Can Be Tightened. With This Model the Fallacy of the Moon's Rotation on Its Axis Is Demonstrable.



Fig. 6. Diagram Showing a Ball Having Mass M, of Radius r, Rotating About Center O, and Used in the Theoretical Analysis of the Moon's Motion.

Let the system be rotated as first assumed and illustrated, the balls being perfectly free on the pivots, and imagine the latter to be gradually tightened to cause friction slowly reducing and finally preventing the slip. At the outset all particles of each ball have been moving with the speed of its center of gravity, but as the bearing resistance asserts itself more and more the translatory velocity of the particles nearer to the axis 0 will be *diminishing*, while that of the diametrically opposite ones will be *increasing*, until the maxima of these changes are attained when the balls are firmly held. In this operation we have thus deprived those parts of the masses which are nearer to the center of motion, of some kinetic energy of *translation* while adding to the energy of those which are farther and, obviously, the gain was greater than the loss so that the *effective* velocity of each ball as a whole was increased. *Only so* have we augmented the kinetic energy of the system, not by causing *axial rotation* of the balls. The energy E of each of these is *solely* that of translatory movement with an effective velocity V_e as above defined such that $E = \frac{1}{2} M V_e^2$. The axial rotations of the ball in either direction are but apparent; *they have no reality whatever* and call for no mechanical effort. It is merely when an extraneous force acts independently to turn the whirling body on its axis that energy comes into play. Incidentally it should be pointed out that in true axial rotation of a rigid and homogenous mass all symmetrically situated particles contribute equally to the momentum which is not the case here. That there exists not even the slightest tendency to such motion can, however, be readily established.

For this purpose I would refer to Fig. 6 showing a ball M of radius *r*, the center C of which is at a distance R from axis 0 and which is bisected by a tangential plane *pp* as indicated, the lower half sphere being shaded for distinction. The kinetic energy of the ball when whirled *n* times per second about 0 is according to the first form of expression $E = \frac{1}{2} M V_e^2 = \frac{1}{2} M (2\pi R_g n)^2$, M being the mass and R_g the radius of gyration. But, as explained in connection with Fig. 4, we have also $E = \frac{1}{2} M V^2 + \frac{1}{2} I_c \omega^2, V = 2\pi R n$ being the velocity of the center of gravity C and I_c the moment of inertia of the ball, about the parallel axis passing thru C and equal to $\frac{2}{5} M i^2$ so that $E = \frac{1}{2} M (2\pi R n)^2 + \frac{1}{5} M r^2 (2\pi n)^2$. Neither of these two expressions for E describes the actual state of the body but the first is certainly preferable conveying, as it does, the idea of a single motion instead of two, one of which moreover is devoid of existence. I shall first undertake to demonstrate that there is no torque or rotary effort about center C and that the kinetic energy of the supposed axial rotation of the ball is mathematically equal to zero. This makes it necessary to consider the two halves separated by the tangential plane *pp* wholly independent from one another. Let c_1 and c_2 be their centers of gravity, then $Cc_1 = Cc_2 = \frac{3}{8} r$. In order to ascertain the kinetic energy of the hemispheres we have to find their radii of gyration which can be done by determining the moments of inertia I_{c_1} and I_{c_2} about parallel axes passing thru c_1 and c_2. Complex calculation will be avoided by remembering that the moment of inertia of either one of the half spheres about an axis thru C is $I_C = \frac{1}{2} \times \frac{2}{5} M r^2, = \frac{1}{5} M r^2$, and since $M = 2 m$, $I_C = \frac{2}{5} m r^2$. This can be exprest in terms of the moments I_{c_1} and I_{c_2}; namely, $I_C = I_{c_1} + m (\frac{3}{8} r)^2 = I_{c_2} + m (\frac{3}{8} r)^2$. Hence $I_{c_1} = I_{c_2} = I_C - m (\frac{3}{8} r)^2 = \frac{2}{5} m r^2 - 9/64 m r^2 = 83/320 m r^2$. Following the same rule the moments of inertia of the half spheres about the axis passing thru the center of motion 0 can be found. Designating the moments for the upper and lower halves of the ball, respectively, I_{O_1} and I_{O_2} we have $I_{O_1} = m (R + \frac{3}{8} r)^2 + I_{c_1} = m (R + \frac{3}{8} r)^2 + 83/320 m r^2$ and $I_{O_2} = m (R - \frac{3}{8} r)^2 + I_{c_2} = m (R - \frac{3}{8} r)^2 + 83/320 m r^2$. Thus for the upper half sphere the radius of gyration $R_{g_1} =$

$$\sqrt{\frac{I_{O_1}}{m}} = \sqrt{(R + \tfrac{3}{8} r)^2 + 83/320\ r^2}$$

and for the lower one $R_{g_2} =$

$$\sqrt{\frac{I_{O_2}}{m}} = \sqrt{(R - \tfrac{3}{8} r)^2 + 83/320\ r^2}$$

These are the distances from center 0, at which the masses of the half spheres may be concentrated and then the algebraic sum of their energies—which are wholly translatory those of axial rotation being nil—will be exactly equal to the total kinetic energy of the ball as a unit. The

(*Continued on page* 156)



Fig. 7. Here Two Masses m-m, Are Considered as Condensed Into Points, Attached to Weightless Strings of Different Radii. If Both Strings Are Cut, and the Masses Considered as Joined, Then There Will Be No Rotation About the Common Center of Gravity.



Fig. 8. To Make the Problem Shown in Fig. 7 Clear, Imagine Two Rifle Barrels Parallel to Each Other. If Two Balls M-M Are Fired Simultaneously, Joined by a Theoretical Bond, They Will Revolve About Their Common Center of Gravity, Proving That the Moon Possesses Only Kinetic Energy of Translation.



For Perfect Health, Strength, Unlimited Vitality & Improved Personal Appearance

The STERLING HIGH FREQUENCY VIOLET RAY



CELEBRATED Physicians and leading Beauty Specialists receive fabulous fees for treating with the Violet Ray. *You* can have a health doctor and beauty specialist right in your own home for your daily service at an average cost of less than a penny stamp.

The Sterling High Frequency Violet Ray was specially designed for home use—fitted to work from the ordinary lamp socket—easy to manipulate—under control at all times—and contains within its covers the Services of a servant, a doctor of medicine, and a nerve and beauty specialist—all in one, ready for instant service.

The Sterling Violet Ray is invaluable in the treatment of diseases of the skin, mouth, throat and lungs, derangements of the liver, kidneys, stomach and intestines—soreness in muscles and joints—tired or "sick" brains or lack of "nerve tone." It strengthens heart action—cleanses the blood—brings the flush of youth to the skin—enlivens the hair—puts a "spring in your step" and creates a clear eye and brain.

Six hundred thousand vibrations per second saturate the entire body with electricity—fill the blood with oxygen—eliminate waste, toxins, and poisons—ALL enemies of youthfulness.

Sterling Violet Ray Generators are the creations of Mr. Anthony Longoria, our Chief Designing Engineer, whose long years of practical experience in the designing and operation of Violet Ray Generators entitle him to the commanding position he holds in their manufacture. They are based upon the original discoveries of Nikola Tesla, first given to the world in May, 1891, but have been developed to the highest state of perfection ever reached in this type of generators.

Book and Valuable Information Free

We want to send you our book and full particulars about the Sterling Violet Ray Machines. Read how you can treat innumerable diseases and ailments, improve your personal charm, add strength and vitality and help yourself in hundreds of ways. Just mail the coupon or drop a postal. Do it now, this minute, before you forget it.

THE STERLING ELECTRICAL CORPORATION

1278 West Third Street **Cleveland Ohio**

STERLING ELECTRICAL SPECIALTIES

MAIL THIS COUPON FOR FREE BOOK

The Sterling Electrical Corporation, 1278 West 3rd St., Cleveland, Ohio.

Gentlemen:—

As per your offer in Electrical Experimenter, please mail me at once, free and postpaid, your book and full information about the Sterling Violet Ray Generators.

NAME .....

ADDRESS .....

CITY .....STATE .....

The Moon's Rotation

By Nikola Tesla

(*Continued from page* 133)

significance of this will be understood by reference to Fig. 7 in which the two masses, condensed into points, are represented as attached to independent weightless strings of lengths R_{g1} and R_{g2} which are purposely shown as displaced but should be imagined as coincident. It will be readily seen that if both strings are cut in the same instant the masses will fly off in tangents to their circular orbits, the angular movement becoming rectilinear without any transformation of energy occurring. Let us now inquire what will happen if the two masses are rigidly joined, the connection being assumed imponderable. *Here we come to the real bug in the question under discussion.* Evidently, so long as the whirling motion continues, and both the masses have precisely the same angular velocity, this connecting link will be of no effect whatever, not the slightest turning effort about the common center of gravity of the masses or tendency of equalization of energy between them will exist. The moment the strings are broken and they are thrown off they will begin to rotate but, as pointed out before, this motion neither adds to or detracts from the energy stored. **The rotation is, however, not due to an exclusive virtue of angular motion, but to the fact that the tangential velocities of the masses or parts of the body thrown off are different.**

To make this clear and to investigate the effects produced, imagine two rifle barrels, as shown in Fig. 8, placed parallel to each other with their axes separated by a distance $R_{g1} - R_{g2}$ and assume that two balls of same diameter, each having mass *m*, are discharged with muzzle velocities V_1 and V_2, respectively equal to $2\pi n R_{g1}$ and $2\pi n R_{g2}$ as in the case just considered. If it be further supposed that at the instant of leaving the barrels the balls are joined by a rigid but weightless link they will rotate about their common center of gravity and in accordance with the statement in my previous article above mentioned, the relation will exist $\frac{V_1 - V_2}{2} = \pi n (R_{g1} - R_{g2})$ n being the number of revolutions per second. The equalization of the speeds and kinetic energies of the balls will be, under these circumstances, very rapid but in two heavenly bodies linked by gravitational attraction, the process might require ages. Now, this whirling movement is real and requires energy which, obviously, must be derived from that originally imparted and, consequently, must reduce the velocity of the balls in the direction of flight by an amount which can be easily calculated. At the moment of discharge the total kinetic energy was $E = \frac{1}{2} m V_1^2 + \frac{1}{2} m V_2^2$ which is evidently equal to $m V_3^2$, V_3 being the effective velocity of the common center of gravity, from which follows that $V_3 = \sqrt{\frac{V_1^2 + V_2^2}{2}}$. The speed of revolution of the masses is, of course, $\frac{V_1 - V_2}{2}$ and the rotational energy of both balls, which must be considered as points, is $e = m\left(\frac{V_1 - V_2}{2}\right)^2$ The kinetic energy of translation in the direction of flight is then $\frac{1}{2} m V_1^2 + \frac{1}{2} m V_2^2 - m\left(\frac{V_1 - V_2}{2}\right)^2 = m\left(\frac{V_1 + V_2}{2}\right)^2 = m V_4^2$, $V_4 = \frac{V_1 + V_2}{2}$ being the speed of the

AK TABLETS FOR All Pain

Headaches
Neuralgias
Colds and La Grippe

Women's Aches and Ills
Rheumatic and Sciatic Pains

Ask Your Druggist for A-K Tablets
(If he cannot supply you, write us)

Small Size 10c — AK Fac-Simile — **Dozen Size 25c**

See Monogram AK on the Genuine

The Antikamnia Remedy Company, St. Louis, Mo.

Write for Free Samples

The Electric Safety razor makes shaving a pleasure. Blade vibrating 7,200 times a minute cuts the beard smoothly and without slightest pull or irritation—feels like a gentle massage. Can be used with or without electric current.

All users of the Lek-Tro-Shav speak well of it

A barber says—"Have shaved for years and have never used any shaving device near its equal."
A home user says—"The most pleasing shave I've ever had in my life. Shaves my face closer than I used to shave, but there is no after irritation or ill effects as I usually get from another razor."

No. 1 Made for use from Light Socket.
No. 2 Made for use from Dry Battery.

Write for illustrated circular describing Lek-Tro-Shav Safety Razor fully.

VIBRATING ELECTRIC RAZOR CO.
Dept. 122. Omaha, Nebr.



FUN **$5.00**

Noiseless Target Practice

Fit your .22 with a Maxim Silencer and get no end of fun this summer practicing in your back yard and on your vacation.

MAXIM SILENCER
MAKES YOU A BETTER MARKSMAN

It eliminates recoil and all noise of the report, and steadies your aim. Direct from Dealer or Factory $5.00. Write for Free Book of Stories.

FREE BOOK

MAXIM SILENCER CO.
89 Homestead Ave., Hartford, Conn.

A Cigarette With One Hand

Don't drop everything every time you want a smoke. Let

The "HANDY" Cigarette Case



Hand it to you. Pull the cover down, then up, and the cigarette is ready. Fits the pocket. Full Nickel-Plated, shipped Post-Paid on receipt of price..... **50c**

CASE MFG. CO., 241 W. 23rd St., New York

common center of gravity, so that $V_2 - V_1$ is the loss of velocity in the direction of flight owing to the rotation of the two mass points. If instead of these we would deal with the balls as they are, their rotational energy

$$e_1 = e + i\omega^2 = m\left(\frac{V_1 + V_2}{2}\right)^2 + i(2\pi n)^2$$

i being the moment of inertia of each ball about its axis.

As will be seen, we arrive at precisely the same results whether the movement is rectilinear or in a circle. In both cases the total kinetic energy can be divided into two parts, respectively of the same numerical values, *but there is an essential difference.* In angular motion the axial rotation is nothing more than an *abstract conception;* in rectilinear movement it is a *positive event.*

Virtually all satellites rotate in like manner and the probability, that the acceleration or retardation of their axial motions—if they ever existed—should come to a stop precisely at a definite angular velocity, is infinitesimal while it is almost absolutely certain that all movement of this kind would ultimately cease. The most plausible view is that no true moon has ever rotated on its axis, for at the time of its birth there must have been some deformation and displacement of its center of gravity thru the attractive force of the mother planet so as to make its peculiar position in space, relative to the latter, in which it persists irrespective of distance, more or less stable. In explanation of this, suppose that one of the balls as M in Fig 5 is not of homogenous material and that it is similarly supported but on an axis passing thru its center of gravity instead of form. Then, no matter in what position the ball is fixed on the pivots, its kinetic energy and centrifugal pull will be the same. Nevertheless a directive tendency will exist as the two centers do not coincide and there is, consequently, no *dynamic* balance. When permitted to turn freely on the axis of gravity the body, of whatever shape it may be, will tend to place itself so that the line joining the two centers points to O and there may be two positions of stability but, generally, if the center of gravity is not greatly displaced, the heavier side will swing outwardly. Such condition may obtain in the moon if it had solidified before receding from the earth to great distance, when the

(*Continued on page* 160)

POPULAR ASTRONOMY
The Evolution of the Stars

(*Continued from page* 121)

Canopus, one of the giants of the universe. The transition of this type into the solar type stars of class G, to which our sun belongs, occurs when the group of iron lines known as group G begins to appear (see diagram I). The lines of calcium and hydrogen still remain more intense than any other lines in the spectrum, but many fine metallic lines now appear in ever-increasing intensity. The transition of this type into the advanced solar type K occurs when some of the metallic lines surpass the hydrogen lines in intensity. The group of iron lines has also greatly increased in intensity until it becomes one of the most conspicuous features of the K type stars. Stars of the solar type such as Capella and the sun are yellow, and stars of the advanced solar type, such as Arcturus and Aldebaran, are orange colored bordering on red. Their atmospheres are filled with dense metallic vapors. (See photos of solar and advanced solar type spectra.)

Class M is divided into giant and dwarf

Drake's Practical Mechanical Books

For Home Study



Pave the way for the big positions—the fat pay-envelopes. Written in non-technical language—easy to read—easy to understand. We will send any book postpaid—keep them five days—if not entirely satisfied return the books and your money will be refunded in full. Order direct from this page. Use the coupon.

Electrical Books

Electric Motor Control Systems and Methods. Leatherette	$1.50
Electrical Tables and Engineering Data. Leatherette	1.50
Motion Picture Operation. Leatherette	1.50
Alternating Current. Leatherette	1.50
Wiring Diagrams and Descriptions. Leatherette	1.50
Armature and Magnet Winding. Leatherette	1.50
Modern Electric Illumination. Leatherette	1.50
Modern Electrical Construction. Leatherette	1.50
Electricians' Operating and Testing Manual. Leatherette	1.50
Drake's Electrical Dictionary. Leatherette	1.50
Electric Motors, D and A. Leatherette	1.50
Electrical Measurements and Meter Testing. Leatherette	1.50
Drake's Telephone Handbook. Leatherette	1.50

Automobile Books



Automobile Ignition. Leatherette, $2.00
Brookes' Automobile Handbook. Leatherette $2.00
Automobile Starting and Lighting. Leatherette $1.50
Ford Motor Car, Truck and Tractor Attachments. Cloth, $1.00
Ford Motor Car, Truck and Tractor Attachments. Leatherette $1.50
Automobile Catechism and Repair Manual. Leatherette $1.25
Gas and Oil Engine Handbook. Cloth 1.00
Gas and Oil Engine Handbook. Leatherette 1.50

Modern Language Courses



French Without a Teacher, Spanish Without a Teacher, German Without a Teacher. By Professor Philip Schuyler Allen, University of Chicago. An entirely new home series of modern foreign languages. Simplest, easiest-to-master language method ever devised. French, Spanish or German. Pocket size. Each $1.25

Mail the Coupon NOW

Order on our five day money back plan.

FREDERICK J. DRAKE & CO.,
1009 Michigan Ave., Chicago, Ill.

Enclosed find ($.....), for which please send me prepaid the books checked in this adv. (or list attached). It is agreed that I may return same in 5 days if not entirely satisfied, and money will be refunded in full.

Name .....

Address .....

MY NEW BOOK

"Muscular Development"

will tell you how to get a wonderful muscular development like mine, perfect health, abundance of vitality and great strength as I have.

EARLE E. LIEDERMAN
Why not look as healthy and be as strong as I am?

The results of my system are shown on my own person and that is recommendation enough. To give every one the opportunity to profit by what I have learned, I will mail my book, for a limited time only, on receipt of

10c Stamps or Coin

This wonderful book will help you. It is profusely illustrated and contains pictures of many of the world's strongest men whom I have trained. Send for it **to-day.** Right now, while it is on your mind.

EARLE LIEDERMAN, Dept. 209, 203 Broadway, N.Y.

RIGHT NOW—You Can Make Big Profits In BATTERY CHARGING

Owners of HB Chargers everywhere are making $100 to $400 *Clear Profit* every month. Business better than ever. YOU can do as well. Don't delay. Get out and get this business with sturdy, dependable HB Equipment.

THIS HB 500 WATT CHARGER WILL PAY $100 to $200 CLEAR PROFIT EACH MONTH

No electrical knowledge required to install or operate. Recharges 7 6-volt batteries at once. Costs 12c to 15c each to recharge, customer pays 75c to $1.50. Big, quick, clean profits--easily made. No burnouts or expensive renewals. Steady service 24 hours a day. Economical to run, requires no attention, save occasional oiling.



$25 Puts This Money-Maker in Your Garage on Money-Back Guarantee

Balance in 9 monthly payments of $20 each. Earnings easily pay for machine. Pin $25 initial payment check to this ad and send today for trial order. Sold under **HB Absolute Money-Back Guarantee.** Order NOW. Don't delay. Get busy! Get those Profits!

HOBART BROTHERS COMPANY
Box 6E, Troy, Ohio
Successful Manufacturers Since 1893

Mining Engineering

For Your Profession

A wide and profitable field, not overcrowded, is open to forward-looking young men. The Michigan College of Mines (established 1886) offers a comprehensive four year course which can be completed in three years. Its breadth provides foundation for expert specialization in that field of engineering which most appeals to the student. All phases of technical knowledge and instruction relative to mine development and operation thoroughly presented by constructive methods. Practical experience is here combined with theoretical work in a rare way. *College is located in center of one of the world's greatest copper mining districts.* Close relations are constantly maintained with mines, mills, smelters, electrolytic and power plants which are practically a part of the College equipment and a factor of enormous value in instruction. "M. C. M. Men Make Good." For descriptive book address Administrative officer, Houghton, Mich.

Michigan College of Mines

Do You Want to Know

HOW TO DEVELOP

Vitality, Energy, Endurance, Nerve Strength, Muscular Strength, Perfect Physique?

SEND for my FREE BOOKS

My FREE BOOKS, **"The Whys of Exercise"** and **"The First and Last Law or Physical Culture,"** tell you if you are weak or underdeveloped, how to grow strong; if strong, how to grow stronger. They explain how to develop the lungs and muscle, the strong heart and vigorous digestion—in short, how to improve health and strength internally as well as externally. SEND TODAY—NOW—for these FREE BOOKS. Enclose 4c in stamps to cover postage.

PROF. H. W. TITUS
56-58 Cooper Sq. Dept. 602. New York City



Swing 4 in., 11 in. between centers, 17 in. total length. Shipping weight 131bs. Bed of lathe is machined. Workmanship first-class. Equipped with wood turning chuck. Can be fitted with 3 in. face plate and drill chuck as special equipment. Order one today. Price $5.00 cash with order. **SYPHER MFG. CO., DEPT. C TOLEDO, OHIO**

Learn to PAINT SIGNS and SHOW CARDS

I teach you personally, by mail, in a short time. Oldest and largest School. Big field, work interesting. You can

EARN $18 TO $45 A WEEK

Fritzner, Minn., wrote. "Did job after first lesson, got $10, profit $7.05." Crawford, B. C., says: "Earned $200.00 while taking course." Get literature, samples, guarantee; all FREE.

DETROIT SCHOOL OF LETTERING
Established 1899. 686 D. S. of L. Bldg., DETROIT, MICH.

The Moon's Rotation

By Nikola Tesla

(*Continued from page* 157)

arrangement of the masses in its interior became subject to gravitational forces of its own, vastly greater than the terrestrial. It has been suggested that the planet is egg-shaped or ellipsoidal but the departure from spherical form must be inconsiderable. It may even be a perfect sphere with the centers of gravity and symmetry coinciding and still rotate as it does. Whatever be its origin and past history, the fact is, that at present all its parts have the same angular velocity as though it were rigidly connected with the earth. This state must endure forever unless forces from without the luna-terrestrial system bring about different conditions and thus the hope of the star-gazers that its other side may become visible some day must be indefinitely deferred.

A motion of this character, as I have shown, precludes the possibility of axial rotation. The easiest way to free ourselves of this illusion is to conceive the satellite subdivided into minute and entirely independent parts, as dust particles, which have different orbital, but rigorously the same angular, velocities. One must at once recognize that the kinetic energy of such an agglomeration is solely translational, there being absolutely no tendency to axial rotation. This makes it also perfectly clear why the moon, provided its distance does not greatly increase, *must* always turn the same face to us even *without any inherent directive tendency* nor so much as *the slightest effort from the earth.*

Referring to the librations of longitude, I do not see that they have any bearing on this question. In astronomical treatises the axial rotation of the moon is accepted as a material fact and it is thought that its angular velocity is constant while that of the orbital movement is not, this resulting in an apparent oscillation revealing more of its surface to our view. To a degree this may be true, but I hold that the mere change of orbital velocity, as will be evident from what has been stated before could not produce these phenomena, for no matter how fast or slow the gyration, the position of the body relative to the center of attraction remains the same. The real cause of these axial displacements is the changing distance of the moon from the earth owing to which the tangential components of velocity of its parts are varied. In *apogee*, when the planet recedes, the radial component of velocity decreases while the tangential increases but, as the decrement of the former is the same for all parts, this is more pronounced in the regions facing the earth than in those turned away from it, the consequence being an axial displacement exposing more of the eastern side. In *perigee*, on the contrary, the radial component increases and the effect is just the opposite with the result that more of the western side is seen. The moon actually swings on the axis passing thru its center of gravity on which it is supported like a ball on a string. The forces involved in these pendular movements are incomparably smaller than those required to effect changes in orbital velocity. If we estimate the radius of gyration of the satellite at 600 miles and its mean distance from the earth at 240,000 miles, then the energy necessary to rotate it once in a month would be only

$$\left(\frac{600}{240{,}000}\right)^2 = \frac{1}{160{,}000}$$ of the kinetic energy

of the orbital movement.

ZIP-ZIP Patented Sept. 3rd, 1918

The Greatest 50 Ct. Article on the Market. Shipped right from the factory the same day we receive your order. The Prong is made of beautiful metal; never breek or weer out; scientifically mede end best workmenship. The rubbers are elastic and lasting, with plenty of pep and force. Zip-Zip, complete, only **50c** prepaid. Be sure the neme Zip-Zip and our address eppear on the article you buy. Order from us or eny Sporting Goods Store in your city. Send Stamps, Coin or Money Order.

AUTOMATIC RUBBER CO.
COLUMBIA, S. C.

Telegraph Pictures
BY ELECTRICITY

Complete sets of two machines of this marvelous equipment at ridiculously low prices. Instructive, mystifying and useful. This picture of President Wilson was telegraphed by these machines. Will transmit pictures, maps, drawings and hand writing. Picture telegraphing is the coming science. Write today.

J. LEISHMAN CO., Dept. T Ogden, Utah

CLEARTONE PHONOGRAPHS
$4.00 to $200.00 Retail

Needles 45c per thousand in lots of 500,000 Motors $1.35 to $14.75 each. Tone Arms and Reproducers $1.30 to $5.75 per set. Main Springs 20c to 90c each. Records, Needles, Sapphire Points and Parts at reasonable prices.

Write for our 84 page catalogue, the only one of its kind in America, illustrating 33 different styles of Talking Machines and over 500 different Phonographic Parts.

LUCKY 13 PHONOGRAPH COMPANY
Export Dept. 46B E. 12th St., N. Y., U.S.A.

SAVE 25% to 60%
on slightly used
GRAFLEX-KODAKS

Cameras and Lenses of every description. Equal to new. Save money. Write now for **Free Bargain Book and Catalog** listing hundreds of money-saving bargains in slightly used and new cameras and supplies. **All goods sold on 10 days' Free Trial.** Money back if not satisfied. You take no chances dealing with us. We have been in the photographic business over 16 years. Write now.

CENTRAL CAMERA CO., Dept. 176 124 S. Wabash Ave., Chicago

UMAKEM

Airplane Workchest, containing aircraft work table with mitre cutting board and length gauge, steel drill, steel hammer, Model Maker's steel square, screwdriver, sandpaper block, 10" scroll saw, together with finest quality reed and bass wood, aluminum, silk, para rubber, full set of blueprints, directions, and all fittings for building one 36" Bleriot Model flying Monoplane. Price $10.00. Other UmakeM Outfits 50c to $50.

W. R. PRICE, Inc.
No. 2 UmakeM Building, 127 Fifth Avenue, New York

RAISE BELGIAN HARES For U.S.

HUGE PROFITS easily and pleasantly made. We furnish stock and pay you $6.00 a pair and express chergee for all you raise. Contract and book "Fortunes in Hares", by mail **Free.**

NATIONAL FOOD & FUR ASSOCIATION
Dept. 24 MILWAUKEE, WISC.



EARN MONEY

Stamping Names on Key Tags. **$50**
Either sex. Spare time. Some make
Send 25c for Tag with your neme on and instructions. Returned if required. **Exp. Key Tag Co., Cohoes, N. Y.**

STAMMERER



Send 10 cents for my remarkable book, "How To Stop Stammering." Kill the fear of stammering. Re education the key.

The Hatfield Institute, 109 N. Dearborn St., Chicago, Ill.

TYPEWRITERS

$10 AND UP. ALL MAKES. SAVE $25 TO $50 on rebuilt at the factory by the well-known "YoungProcess." Sold for low cash—instalment or rented. Rental applies on purchase price. Write for full details and guarantee. Free triel. **YOUNG TYPEWRITER CO., Dept. 819, Chicago**

BE A C.P.A. ACCOUNTANCY

The Highest Paid Profession taught thoroughly in a few months of home study by new system.

FREE BOOK International Accountants Society Dept. 39F, 2626 S. Mich. Ave. Chicago

158 Genuine Foreign Stamps—Mexican War Issues, Venezuela, Salvador and India Service, Guatemala, China, etc., only **10c.** 100 all diff., fine, 15c; 200 all diff., 25c. FINEST APPROVAL SHEETS 60% to 80%. AGENTS WANTED. Big 72-page Lists FREE! **We Buy Stamps.** Est. 25 years. **C. E. HUSSMAN STAMP CO., Dept. G ST. LOUIS, MO.**

Learn Watchwork, Jewelrywork and Engraving A fine trade commanding a good salary, and your services are always in demand. Address HOROLOGICAL Department, Bradley Institute, Peoria, Ill., for our latest catalog.

Electrical Oscillators

By NIKOLA TESLA

FEW fields have been opened up the exploration of which has proved as fruitful as that of high frequency currents. Their singular properties and the spectacular character of the phenomena they presented immediately commanded universal attention. Scientific



Fig. 13—Tesla Oscillator with Magnetically Controlled, Sealed Mercury Interrupter.

men became interested in their investigation, engineers were attracted by their commercial possibilities, and physicians recognized in them a long-sought means for effective treatment of bodily ills. Since the publication of my first researches in 1891, hundreds of volumes have been written on the subject and many invaluable results obtained thru the medium of this new agency. Yet, the art is only in its infancy and the future has incomparably bigger things in store.

From the very beginning I felt the necessity of producing efficient apparatus to meet a rapidly growing demand and during the eight years succeeding my original announcements I developed not less than fifty types of these transformers or electrical oscillators, each complete in every detail and refined to such a degree that I could not materially improve any one of them today. Had I been guided by practical considerations I might have built up an im-



Fig. 14—Electrical Oscillator, Illustrated in Fig. 13, Showing Details and Circuit Connections.

MR. TESLA makes a very important contribution to the electrical arts with this article.

The pioneer of all high frequency apparatus divulges much that is new and startling in these pages. Few people realize the enormous value of Mr. Tesla's machines and the many different important uses to which they can be applied in our everyday lives. New and startling uses are being found every year for these machines.

It is characteristic of Mr. Tesla that he has developed and actually built an astounding variation of these machines, and we regret that we can publish only a very few of the more important models.

Most of the Tesla coils shown have never been publisht before. —EDITOR.

mense and profitable business, incidentally rendering important services to the world. But the force of circumstances and the ever enlarging vista of greater achievements turned my efforts in other directions. And so it comes that instruments will shortly be placed on the market which, oddly enough, were perfected twenty years ago!

These oscillators are expressly intended to operate on direct and alternating lighting circuits and to generate damped and undamped oscillations or currents of any frequency, volume and tension within the widest limits. They are compact, self-contained, require no care for long periods of time and will be found very convenient and useful for various purposes as, wireless telegraphy and telephony; conversion of electrical energy; formation of chemical compounds thru fusion and combination; synthesis of gases; manufacture of ozone; lighting; welding; municipal, hospital, and domestic sanitation and sterilization, and numerous other applications in scientific laboratories and industrial institutions. While these transformers have never been described before, the general principles underlying them were fully set forth in my publisht articles and patents, more particularly those of September 22, 1896, and it is thought, therefore, that the appended photographs of a few types, together with a short explanation, will convey all the information that may be desired.

The essential parts of such an oscillator are: a condenser, a self-induction coil for

SPECIAL NOTICE

Last month we announced another special feature article by Mr. Tesla, which altho made in good faith by us was not authorized by him. Due to very important duties of Mr. Tesla, it was impossible for him to furnish his historical article this month, so the special feature article publisht on this page takes its place. An important historical article will appear in the August issue.—Editor.



Fig. 15—Tesla Transformer with Gravity Controlled, Sealed Mercury Interrupter.

charging the same to a high potential, a circuit controller, and a transformer which is energized by the oscillatory discharges of the condenser. There are at least three, but usually four, five or six, circuits in tune and the regulation is effected in several ways, most frequently merely by means of an adjusting screw. Under favorable conditions an efficiency as high as 85% is attainable, that is to say, that percentage of the energy supplied can be recovered in the secondary of the transformer. While the chief virtue of this kind of apparatus is obviously due to the wonderful powers of the condenser, special qualities result from concatenation of circuits under observance of accurate harmonic relations, and minimization of frictional and other losses which has been one of the principal objects of the design.

(*Continued on page 259*)



Fig. 16—Electrical Oscillator, Illustrated in Fig. 15, Showing Details of Motor and Break Mechanism.

Electrical Oscillators

By Nikola Tesla

(Continued from page 229)

Broadly, the instruments can be divided into two classes: one in which the circuit controller comprises solid contacts, and the other in which the make and break is effected by mercury. Figures 1 to 8, inclusive, belong to the first, and the remaining ones to the second class. The former are capable of an appreciably higher efficiency on account of the fact that the losses involved in the make and break are reduced to the minimum and the resistance component of the damping factor is very small. The latter are preferable for purposes requiring larger output and a great number of breaks per second. The operation of the motor and circuit controller of course consumes a certain amount of energy which, however, is the less significant the larger the capacity of the machine.

In Fig. 1 is shown one of the earliest forms of oscillator constructed for experimental purposes. The condenser is contained in a square box of mahogany upon which is mounted the self-induction or charging coil wound, as will be noted, in two sections connected in multiple or series according to whether the tension of the supply circuit is 110 or 220 volts. From the box protrude four brass columns carrying a plate with the spring contacts and adjusting screws as well as two massive terminals for the reception of the primary of the transformer. Two of the columns serve as condenser connections while the other pair is employed to join the binding posts of the switch in front to the self-inductance and condenser. The primary coil consists of a few turns of copper ribbon to the ends of which are soldered short rods fitting into the terminals referred to. The secondary is made in two parts, wound in a manner to reduce as much as possible the distributed capacity and at the same time enable the coil to withstand a very high pressure between its terminals at the center, which are connected to binding posts on two rubber columns projecting from the primary. The circuit connections may be slightly varied but ordinarily they are as diagrammatically illustrated in the ELECTRICAL EXPERIMENTER for May on page 89, relating to my oscillation transformer photograph of which appeared on page 16 of the same number. The operation is as follows: When the switch is thrown on, the current from the supply circuit rushes thru the self-induction coil, magnetizing the iron core within and separating the contacts of the controller. The high tension induced current then charges the condenser and upon closure of the contacts the accumulated energy is released thru the primary, giving rise to a long series of oscillations which excite the tuned secondary circuit.

This device has proved highly serviceable in carrying on laboratory experiments of all kinds. For instance, in studying phenomena of impedance, the transformer was removed and a bent copper bar inserted in the terminals. The latter was often replaced by a large circular loop to exhibit inductive effects at a distance or to excite resonant circuits used in various investigations and measurements. A transformer suitable for any desired performance could be readily improvised and attached to the terminals and in this way much time and labor was saved. Contrary to what might be naturally expected, little trouble was experienced with the contacts, altho the currents thru them were heavy, namely, proper conditions of resonance existing, the great flow occurs only when the circuit is closed and no destructive arcs can develop. Origi-

Starrett Tools

have gaged the accuracy of the world's work for thirty-nine years.

Manufacturers, toolmakers, machinists and mechanics in all trades, rely upon this precision.

Illustrated catalog No. 21LE sent free upon request.

The L. S. Starrett Co.

The World's Greatest Toolmakers

Manufacturers of Hack Saws Unexcelled

42-940

Athol, Mass.



YOUR OPPORTUNITY

Canceled Government Contracts

We have secured a large quantity of Small Motors, Generators and Charging Outfits. This material is new, still in original cases and carries the full factory guarantee.

This is Your Opportunity to buy new, guaranteed Electrical Apparatus of Standard Manufacture

Battery Charging Outfits

For use on 110 volt, A. C., 60 cycle, single phase current only.

80 watts, 8 volts, 10 amperes . $48.50
150 watts, 30 volts, 5 amperes . $68.50
150 watts, 15 volts, 10 amperes . $68.50
300 watts, 30 volts, 10 amperes . $94.50

All outfits complete with switchboard as cut shown.

1/2 H. P. INDUCTION MOTOR $32.50
110 or 220 volts, A. C. 60 cycle, single phase, 1750 R. P. M.

ALL MOTORS COMPLETE AS CUT

Mail $5.00 cash or Money Order. We will send C. O. D. subject to full examination.

MONEY BACK GUARANTEE

1/4 H. P. 110 volts A. C., 60 cycle, single phase 1750 R. P. M.

WASHING MACHINE MOTOR

Suitable for operating Small Compressors, Coffee Grinders, Bottle Washers, Lathes Drill Presses, etc. $18.50

WRITE FOR CATALOGUE. BARGAINS IN MOTORS AND GENERATORS. SPECIAL QUANTITY PRICES

220 volts **POLYPHASE MOTORS** 1750 RPM.
60 cycle, 2 or 3 phase. Complete, pulley and base
1 H. P. $59.50 3 H. P. $ 84.50
2 H. P. $72.50 5 H. P. $102.50

NEW MOTORS

110-220 volts **REPULSION MOTORS** 1800 RPM.
60 cycle, single phase. Complete with pulley.
1/2 Hp. $44.50 1 Hp. $67.50

MANUFACTURERS' DISTRIBUTER

CHAS. H. JOHNSTON - West End - PITTSBURGH, PA.

Health, Strength, Vitality

Personal Appearance—All Demand

The STERLING HIGH FREQUENCY VIOLET RAY



Specially designed for home use—fitted to work from the ordinary lamp socket—easy to manipulate under control at all times—and contains within its covers the Services of a servant, a doctor of medicine and a nerve and beauty specialist—all in one, ready for Instant service.

The Sterling Violet Ray is invaluable in the treatment of diseases of the skin, mouth, throat and lungs, derangements of the liver, kidneys, stomach and intestines—soreness in muscles and joints—tired or "sick" brains or lack of "nerve tone." It strengthens heart action—cleanses the blood—brings the flush of youth to the skin—enlivens the hair—puts a "spring in your step" and creates a clear eye and brain.

Sterling Violet Ray Generators are based upon the original discoveries of Nikola Tesla, but have been developed to the highest state of perfection ever reached by Mr. Anthony Longoria, whose long years of practical experience entitle him to the commanding position he holds.

VALUABLE BOOK FREE

We want to send you our book and full particulars about the Sterling Violet Ray Machines. Read how you can treat innumerable diseases and ailments, improve your personal charm, add strength and vitality and help yourself in hundreds of ways. Just mail the coupon or drop a postal. Do it now, this minute, before you forget it.

The STERLING ELECTRICAL CORPORATION

1278 West 3rd St. Cleveland, Ohio

STERLING ELECTRICAL SPECIALTIES

MAIL THIS COUPON — FOR FREE BOOK.

THE STERLING ELECTRICAL CORPORATION 1278 West 3rd Street Cleveland, Ohio

Gentlemen:—As per your offer in Electrical Experimenter, please mail me at once, free and postpaid, your book and full information about the Sterling Violet Ray Generators.

NAME .....

ADDRESS .....

CITY..... STATE.....

nally I employed platinum and iridium tips but later replaced them by some of meteorite and finally of tungsten. The last have given the best satisfaction, permitting working for hours and days without interruption.

Fig. 2 illustrates a small oscillator designed for certain specific uses. The underlying idea was to attain great activities during minute intervals of time each succeeded by a comparatively long period of inaction. With this object a large self-induction and a quick-acting break were employed owing to which arrangement the condenser was charged to a very high potential. Sudden secondary currents and sparks of great volume were thus obtained, eminently suitable for welding thin wires, flashing lamp filaments, igniting explosive mixtures and kindred applications. The instrument was also adapted for battery use and in this form was a very effective igniter for gas engines on which a patent bearing number 609,250 was granted to me August 16, 1898.

Fig. 3 represents a large oscillator of the first class intended for wireless experiments, production of Röntgen rays and scientific research in general. It comprises a box containing two condensers of the same capacity on which are supported the charging coil and transformer. The automatic circuit controller, hand switch and connecting posts are mounted on the front plate of the inductance spool as is also one of the contact springs. The condenser box is equipt with three terminals, the two external ones serving merely for connection while the middle one carries a contact bar with a screw for regulating the interval during which the circuit is closed. The vibrating spring itself, the sole function of which is to cause periodic interruptions, can be adjusted in its strength as well as distance from the iron core in the center of the charging coil by four screws visible on the top plate so that any desired conditions of mechanical control might be secured. The primary coil of the transformer is of copper sheet and taps are made at suitable points for the purpose of varying, at will, the number of turns. As in Fig. 1 the inductance coil is wound in two sections to adapt the instrument both to 110 and 220 volt circuits and several secondaries were provided to suit the various wave lengths of the primary. The output was approximately 500 watt with damped waves of about 50,000 cycles per second. For short periods of time undamped oscillations were produced in screwing the vibrating spring tight against the iron core and separating the contacts by the adjusting screw *which also performed the function of a key.* With this oscillator I made a number of important observations and it was one of the machines exhibited at a lecture before the New York Academy of Sciences in 1897.

Fig. 4 is a photograph of a type of transformer in every respect similar to the one illustrated in the May, 1919, issue of the ELECTRICAL EXPERIMENTER to which reference has already been made. It contains the identical essential parts, disposed in like manner, but was specially designed for use on supply circuits of higher tension, from 220 to 500 volts or more. The usual adjustments are made in setting the contact spring and shifting the iron core within the inductance coil up and down by means of two screws. In order to prevent injury thru a short-circuit, fuses are inserted in the lines. The instrument was photographed in action, generating undamped oscillations from a 220 volt lighting circuit.

Fig. 5 shows a later form of transformer principally intended to replace Rhumkorf coils. In this instance a primary is employed, having a much greater number of turns and the secondary is closely linked with the same. The currents developed in the latter, having a tension of from 10,000 to 30,000 volts, are used to charge con-

(*Continued on page 276*)

FREE!



YES, a $15 Complete Working Outfit with instruments, drawing board, etc., and a drawing table absolutely free. It does not cost a penny.

Draw $150 to $300 a Month

Companies are calling for men to fill positions paying from $150.00 to $300.00 a month. I will give you just the training you need to hold one of the big jobs—right in your own home. I am Chief Draftsman of a large and well known company.

Write Today For my free book on drafting and my liberal "Personal Instruction" offer to a few students. A post card or letter will do. No obligations.

Chief Draftsman Dobe Engineers Equipment Co. Div. B744 Chicago, Ill.

Send Only 12c

(Stamps or Coin)

And I will send you a copy of my valuable booklet.

"Hints to Music Loving Owners of Talking Machines"

Tells you how to take care of your machine and records, preserve the life of both, and gives many pointers to improve the tone of your instrument and increase your enjoyment of it. Instructs on the care of the motor, cleaning, speed adjusment, care of the needles—in fact every thing you should know. Send 12c today and the booklet will come by return mail.

J. H. ELLIS, Box 882, Milwaukee, Wis.

Patentee & Manufacturer. Ellis Harmonious Reproducer

Build Your Own PHONOGRAPH,

It's Easy With Our Help

A few hours interesting work saves many dollars and gives you a machine exactly to suit your ideals. We furnish motors, tone arms, case material, blue prints and full instructions. Plays any record. You can make fine profit building phonographs for your friends. Write Today for Our Free Blue Print Offer. Agents wanted for our ready built Choraleons.

SAVE OVER HALF

Choraleon Phonograph Co.

707 Monger Bldg., Elkhart, Ind.

FREE

$20

Violin, Hawaiian Guitar Ukulele, Guitar, Mandolin, Cornet or Banjo

Wonderful new system of teaching note music by mail. To first pupils in each locality, we'll give a $20 superb Violin, Mandolin, Ukulele, Guitar, Hawaiian Guitar, Cornet or Banjo absolutely free. Very small charge for lessons only expense. We guarantee success or no charge. Complete outfit free. Write at once—no obligation.

SLINGERLAND SCHOOL OF MUSIC, Dept. 422, CHICAGO, ILL.

FREE! Sonora

These phonograph needles replace steel needles, play 50 to 100 times and are used on ALL MAKES of steel needle records. Economical, convenient, improve tone, and preserve records. 30c per card of 5, 40c in Canada. Write today for FREE sample.

Semi-Permanent Silvered NEEDLES

Sonora Phonograph Sales Company, Inc.

GEORGE E. BRIGHTSON, President

279 Broadway, Dept. G, New York Toronto: Ryrie Bldg.

CATALOG FREE!

BUILD A $100 PHONOGRAPH

Assemble your own Phonograph

Do it yourself easily. Have the finest machine. Astounding saving. We give you the phonograph secrets. Complete instructions 10 cents.

ELECTRO MECHANICAL PARTS CO.

160 N. Wells St. CHICAGO

MULTIPLYING SIMPLIFIED

By our Tabulated Multiplication Card! This is something which you do not think of until you need it. Its merit lies in its handiness. Pocket size card 2½ x 6 ins. Send for one now and be prepared! Price only 10 cents (coin). Payment with order.

TABULATED INFORMATION CARD CO.

2040 Chestnut St. Philadelphia, Pa.

STAMMERER

Send 10 cents for my remarkable book, "How To Stop Stammering." Kill the fear of stammering. Re education the key.

The Hatfield Institute, 109 N. Dearborn St., Chicago, Ill.

Electrical Oscillators

By Nikola Tesla

(*Continued from page 260*)

densers and operate an independent high frequency coil as customary. The controlling mechanism is of somewhat different construction but the core and contact spring are both adjustable as before.

Fig. 6 is a small instrument of this type, particularly intended for ozone production or sterilization. It is remarkably efficient for its size and can be connected either to a 110 or 220 volt circuit, direct or alternating, preferably the former.

In Fig. 7 is shown a photograph of a



Fig. 17. Tesla Transformer With Adjustable Mercury Controller.

larger transformer of this kind. The construction and disposition of the parts is as before but there are two condensers in the box, one of which is connected in the circuit as in the previous cases, while the other is in shunt to the primary coil. In this manner currents of great volume are produced in the latter and the secondary effects are accordingly magnified. The introduction of an additional tuned circuit secures also other advantages but the adjustments are rendered more difficult and for this reason it is desirable to use such an instrument in the production of currents of a definite and unchanging frequency.

Fig. 8 illustrates a transformer with rotary break. There are two condensers of the same capacity in the box which can be connected in series or multiple. The charging inductances are in the form of two long spools upon which are supported the secondary terminals. A small direct current motor, the speed of which can be varied within wide limits, is employed to drive a specially constructed make and break. In other features the oscillator is like the one illustrated in Fig. 3 and its operation will be readily understood from the foregoing. This transformer was used in my wireless experiments and frequently also for lighting the laboratory by my vacuum tubes and was likewise exhibited at my lecture before the New York Academy of Sciences above mentioned.

Coming now to machines of the second class, Fig. 9 shows an oscillatory transformer comprising a condenser and charging inductance enclosed in a box, a transformer and a mercury circuit controller, the latter being of a construction described for the first time in my patent No. 609,251 of August 16, 1898. It consists of a motor driven hollow pulley containing a small quantity of mercury which is thrown outwardly against the walls of the vessel by centrifugal force and entrains a contact wheel which periodically closes and opens the condenser circuit. By means of adjusting screws above the pulley, the depth of immersion of the vanes and consequently, also, the duration of each contact can be varied at desire and thus the intensity of the effects and their character controlled. This form of break has given thoro satisfaction, working continuously with currents of from 20 to 25 amperes. The number of interruptions is usually from 500 to 1,000 per second but higher frequencies are practicable. The space occupied is about 10″ x 8″ x 10″ and the output approximately ½ K.W.

In the transformer just described the break is exposed to the atmosphere and a slow oxidation of the mercury takes place. This disadvantage is overcome in the instrument shown in Fig. 10, which consists of a perforated metal box containing the condenser and charging inductance and carrying on the top a motor driving the break, and a transformer. The mercury break is of a kind to be described and operates on the principle of a jet which establishes, intermittently, contact with a rotating wheel in the interior of the pulley. The stationary parts are supported in the vessel on a bar passing thru the long hollow shaft of the motor and a mercury seal is employed to effect hermetic closure of the chamber enclosing the circuit controller. The current is led into the interior of the pulley thru two sliding rings on the top which are in series with the condenser and primary. The exclusion of the oxygen is a decided improvement, the deterioration of the metal and attendant trouble being eliminated and perfect working conditions continuously maintained.

Fig. 11 is a photograph of a similar oscillator with hermetically inclosed mercury break. In this machine the stationary parts of the interrupter in the interior of the pulley were supported on a tube thru which was led an insulated wire connecting to one terminal of the break while the other was in contact with the vessel. The sliding rings were, in this manner, avoided and the construction simplified. The instrument was designed for oscillations of lower tension and frequency requiring primary currents of comparatively smaller amperage and was used to excite other resonant circuits.

Fig. 12 shows an improved form of oscillator of the kind described in Fig. 10, in which the supporting bar thru the hollow motor shaft was done away with, the device pumping the mercury being kept in position by gravity, as will be more fully explained with reference to another figure. Both the capacity of the condenser and primary turns were made variable with the view of producing oscillations of several frequencies.

Fig. 13 is a photographic view of another form of oscillatory transformer with hermetically sealed mercury interrupter, and Fig. 14 diagrams showing the circuit connections and arrangement of parts reproduced from my patent, No. 609,245, of August 16, 1898, describing this particular device. The condenser, inductance, transformer and circuit controller are disposed as before, but the latter is of different construction, which will be clear from an inspection of Fig. 14. The hollow pulley *a* is secured to a shaft *c* which is mounted in a vertical bearing passing thru the stationary field magnet *d* of the motor. In the interior of the vessel is supported, on frictionless bearings, a body *h* of magnetic material which is surrounded by a dome *b* in the center of a laminated iron ring, with pole pieces *oo* wound with energizing coils *p*. The ring is supported on four columns and, when magnetized, keeps the body *h* in position while the pulley is rotated. The latter is of steel, but the dome is preferably made of German silver burnt black by acid or nickeled. The body *h* carries a short tube *k* bent, as indicated, to catch the fluid as it is whirled around, and project it against the teeth of a wheel fastened to the pulley. This wheel is insulated and contact from it to the external circuit is established thru a mercury cup. As the pulley is rapidly rotated a jet of the fluid is thrown against the wheel, *thus making and breaking contact about* 1,000 *times per second.* The instrument works silently and, owing to the absence of all deteriorating agents, keeps continually clean and in perfect condition. The number of interruptions per second may be much greater, however, so as to make the currents suitable for wireless telephony and like purposes.



Fig. 18. Tesla Transformer With Mercury Jet Interrupter.

A modified form of oscillator is represented in Figs. 15 and 16, the former being a photographic view and the latter a diagrammatic illustration showing the arrangement of the interior parts of the controller. In this instance the shaft *b* carrying the vessel *a* is hollow and supports, in frictionless bearings, a spindle *j* to which is fastened a weight *k*. Insulated from the latter, but mechanically fixt to it, is a curved arm L upon which is supported, freely rotatable, a break-wheel with projections QQ. The wheel is in electrical connection with the external circuit thru a mercury cup and an insulated plug supported from the top of the pulley. Owing to the inclined position of the motor the weight *k* keeps the break-wheel in place by the force of gravity and as the pulley is rotated the circuit, including the condenser and primary coil of the transformer, is rapidly made and broken.

Fig. 17 shows a similar instrument in which, however, the make and break device is a jet of mercury impinging against an insulated toothed wheel carried on an insulated stud in the center of the cover of the pulley as shown. Connection to the condenser circuit is made by brushes bearing on this plug.

Fig. 18 is a photograph of another transformer with a mercury circuit controller of the wheel type, modified in some features on which it is unnecessary to dwell.

These are but a few of the oscillatory transformers I have perfected and constitute only a small part of my high frequency apparatus of which I hope to give a full description, when I shall have freed myself of pressing duties, at some future date.